A TEXT BOOK

OF

CHEMICAL ENGINEERING

BY

EDWARD HART, Ph. D.

Professor of Chemical Engineering in Lafayette College. Sometime Editor of The Journal of Analytical and Applied Chemistry, and of The Journal of The American Chemical Society, President of The Baker & Adamson Chemical Co., and Vice President and General Manager of The Clinchfield Products Co.

SECOND EDITION

EASTON, PA.
THE CHEMICAL PUBLISHING CO.
1922.

LONDON, ENGLAND:
WILLIAMS & NORGATE
14 HENRIETTA STREET, COVENT GARDEN, W. C.

TOKYO, JAPAN:
MARUZEN COMPANY LTD.,
11-16 NIHONBASHI TORI-3-CHOME

Copyright, 1920, by Edward Hart.
Copyright, 1922, by Edward Hart.

PREFACE TO THE FIRST EDITION

For several years I have accumulated data with the intention of eventually publishing a book on chemical engineering to embody the elements of the subject. Publication has been hastened by the pressing need of a text book for my own classes. I realize more fully than any of my critics can do the imperfections of omission, and I fear some of commission in this first attempt to give a comprehensive view of the subject. The writer whose own experience shall fully qualify him to cover this whole subject is still to be discovered. I can only hope that this imperfect presentation may be allowed to pass muster as a first attempt. I am greatly indebted to many persons, some of whose names are mentioned in the text, for assistance. I am also indebted to many manufacturers for cuts of apparatus, for special drawings and other favors. The names of such firms inserted in the text have had the purpose of helping the beginner. They were not paid for in any way. If future editions should be called for I hope with the assistance which criticism of this one shall evoke to prepare a much better treatise on the subject. For all such criticism I shall be very grateful, especially if it be kindly criticism.

EDWARD HART.

Easton, Pa., Dec. 1, 1920.

PREFACE TO THE SECOND EDITION

Many drawings for the cuts in the first edition were made by R. T. Resnikoff and were not acknowledged through an oversight.

I have had much help in the preparation of this edition from suggestions made by Mr. Eugene Oster and from my colleague Prof. D. B. Prentice. As in the first edition, I have obtained considerable information not otherwise obtainable from the manufacturers of apparatus whose names are mentioned in the text. The ancient prejudice against such sources of information no longer holds good, but this some of the reviewers of the first edition seem not to be aware of. College graduates and some holders of the Doctor's degree are now in the service of commercial concerns to their very great advantage. Reviewers will please take notice that this is a text book and not a manual.

I expected great things of these reviewers but I have not found them; in some cases they were clearly incompetent and in some they had not even read the book; this I regard as essential in the preparation of any book review.

The exhaustion of the first edition in less than a year shows that such a book was needed and that this one in some degree filled the need. I do not regard the book as by any means complete but it contains all the additional material that I have been able to prepare in the time allowed. I hope for many additional suggestions, and with the help thus given will endeavor to bring the book up to the mark. For all the many favors received I am deeply grateful.

EDWARD HART.

Easton, Pa., April, 1922.

Contents.

	PAGE
Preface (First Edition)	
Preface (Second Edition)	
Introduction	1
CHAPTER I.—MATERIALS.....	1
(2) Iron	1
(3) Mild Steel	2
High Silicon Iron Alloys...	2
(4) Composition	2
(5) Physical Properties	3
(6) Chemical Properties	3
(7) Design of Apparatus	4
(8) Installation of Apparatus	5
(9) "Resistal"	5
(10) Nichrome	5
(11) Atherite	5
(12) Electron and Magnalium	6
(13) Copper	6
(14) Nickel	6
(15) Lead and Lead Lined Vessels ..	6
(16) Aluminum	8
(17) Silver	8
(18) Gold	8
(19) Platinum	9
(20) Illium	9
(21) Lead-Thallium Alloys	9
(22) Copper Iron Alloys	9
(23) Monel Metal	10
(24) Bronze	10
(25) Glass	10
(26) Fused Silica	14
(27) Chemical Stoneware	14
(28) Brick and Tile ..	14
(29) Wood and Rubber	14
(30) "Bakelite"	15
(31) Bakelite Enamel..	16
(32) Cement	16
(33) Paints and Varnishes References	17
CHAPTER II.—CORROSION (34)	18
(36) Arsenic Deposits	19
(37) Amalgamation ...	19
(39) The Corrosion of Gold	20
(40) Corrosion by Caustic Soda	21
(41) Paucity of Information	22
(42) Obstacles to Publication	22
CHAPTER III.—LOCATION OF WORKS (43)	24
(44) Laying out of Plant	24
(45) Railway Sidings..	26
(46) Water Supply ...	26
(47) Disposal of Waste	26
Buildings.	
(48) Concrete	26
(49) The Cement Gun	27
(50) Brick	27
(51) Hollow Tile	29
(52) Framed Buildings	30
(53) Foundations	30
(54) Safe Bearing Loads	30
(55) Footings	31
(56) Materials for Foundations ...	32
(57) Crushing Strength of Materials used in Walls	33

PAGE

(58) The Weight of Masonry in lbs. per cubic foot .. 33
(59) Brick Walls 33
(60) Laying out Buildings and Building Walls 34
(61) Hollow Tile 36
(62) Safe Load for Hollow Tile ... 38
(63) Pilasters 38
(64) Floors 38
(65) Roofs 39
(66) Weight of Wood 39
(67) Beams and Girders 40

CHAPTER IV.—INDUSTRIAL MANAGEMENT
(68) General Manager. 41
(69) The Superintendent 41
(70) The Foreman.... 41
(71) Chief Chemist .. 42
(72) The Men 42
(73) Reports 42
(74) Business Economics 43

CHAPTER V.—BOILERS
(75) Internally Fired Upright Tubular Boilers 44
(76) Horizontal Tubular Boilers 44
(77) Water Tube Boilers 50
(78) Surface Combustion Boilers 56
(79) Heat Transmission in Boilers 56
(80) Composition and Temperature of Chimney Gases 56
(81) Radiation 57

PAGE

CHAPTER VI.—PRIME MOVERS
(82) The Steam Engine 58
(83) Expansive Working 58
(84) Horse Power 60
(85) The Work Done by an Engine .. 60
(86) Heat and Work.. 60
(87) Indicator Diagrams 60
(88) The Indicator Piston 61
(89) Economy of the Engine 61
(90) The Piston 61
(91) The Stuffing Box 61
(92) The Cross Head and Connecting Rod 64
(93) The Governor .. 64
The Gas Engine
(94) The Gas Engine.. 64
(95) The Diesel Engine 64
(96) A New Variable-Speed Power-Transmission System 69

CHAPTER VII.—PLUMBING
(97) Lead Pipe 70
(98) Stoneware Pipe.. 70
(99) Silica Tubing ... 75

CHAPTER VIII.—PUMPS
(100) The Blow-case .. 76
(101) The Plath Acid Elevator 76
(102) The Air Lift 78
(103) Jet Pumps 79
(104) Pulsometers 79
(105) Plunger and Piston Pumps 80
(106) Centrifugal Pumps 81

CHAPTER IX.—CRUSHING
(107) 82
(108) Jaw Crushers ... 83

PAGE

(109) The Blake Crusher 83
Gyratory Breakers (110) ... 85
(111) Kennedy-Van Saun. Mfg. and Eng. Corporation Crusher .. 85
Intermediate Crushing (112) 87
(113) Sturtevant Coarse Crusher 90
(114) The Power 90
(115) The Cost of Crushing 90
Rolls (116) 90
(117) Cornish Rolls ... 90
(118) Shafts 93
(119) Feeders 93
(120) The Hardinge Mill 93
(121) The Ball Mill .. 93
(122) The Tube Mill .. 93
(123) A Pulverizer Jar Mill 93
(124) The Progress of a Grinding Operation 93
(125) Uniformity of Grain 93
(126) An Impact Screen 97
(127) Other Crushing Apparatus 99
(128) Raymond Mill .. 101
(129) Williams Mill ... 102

CHAPTER X.—Mechanical Handling of Material (130) 105
(131) Screw Conveyors. 106
(132) Spiral Chutes 106
(133) Work Trucks ... 106
(134) Tracks for Works 108
(135) Layout of Tracks 108

CHAPTER XI.—Dissolving (136) 109
(137) Salt Solutions ... 109
(138) Stirrers 109

PAGE

(139) Power Requirements 110
(140) W. and P. Dissolver 111
(141) Compressed Air . 112
(142) Setting 113
(143) The Buff-Dunlop or Shanks Apparatus 113

CHAPTER XII.—Filtration (144) 116
(145) Separators 116
(146) Density 118
(147) Separation and Filtration 118
(148) The Sharpless Super Centrifuge . 118
(149) Centrifugals 122
(150) Underdriven Centrifugal 123
(151) Selection of a Centrifugal 127
(152) Uses of Centrifugal 127
(153) Settlers 127
(154) Settling Process.. 127
(155) Counter Current. 128
(156) Washing Efficiency 129
(157) Mixing 130
(158) Dorr Thickeners. 130
(159) Dorrco Pump ... 131
(160) The Dorr Continuous Thickener 132
(161) The Dorr Thickener 132
(162) Capacity 133
(163) The Dorr Agitator 133
(164) Filters 134
(165) Filter Presses .. 135
(166) Sperry Press 137
(167) Shriver Press ... 137

PAGE

(168) Kelly Filter 141
(169) Sweetland Filter. 145
(170) Moore Filter 149
(171) American Filter .. 155
(172) Oliver Filter 155
(173) Portland Filter .. 155
(174) Filter Frames ... 156
(175) Recessed Frames. 156
(176) Flush Frames ... 160
(177) Makers of Filters 160
(178) Water in Press Cake 160
(179) Filtros 161
(180) Filtros Wheel ... 161
(181) Separating Precipitates 161

CHAPTER XIII.—TANKS
(182) Wooden Tanks... 163
(183) Kind of Wood... 163
(184) Hoops for Tanks 165
(185) Pressure on Tanks 165
(186) Tanks for Acids.. 166
(187) Lugs for Tanks.. 166
(188) Rectangular Tanks or Vats 168
(189) Cheap Tanks 168
(190) Stoneware Tanks 168
(191) Concrete Tanks.. 169
(192) Rectangular Concrete Tanks ... 170
(193) Construction of Tanks 170
(194) Brick Lined Tanks 171
(195) A Pachuca or Precipitating Tank. 171
(196) Action of Substances on Wood 172

CHAPTER XIV.—EVAPORATION
(197) 174
(198) Gradirhauser 174
(199) Brush Racks 174

PAGE

(200) Spray Evaporator 174
(201) Tower Evaporator 176
(202) Iron Pot Evaporator 176
(203) Lead Lined Evaporator 176
(204) Efficiency 176
(205) Capacity 177
(206) Arrangement 177
(207) Shallow Pans ... 177
(208) Steam Heated Seamless Cast Iron Pans 177
(209) Vacuum Evaporator 181
(210) Zaremba Evaporator 183
(211) Multiple Effect .. 185
(212) Efficiency 189
(213) Pumps and Condensers 190
(214) Zaremba Crystallizing Evaporator 190
(215) Lille Evaporator . 193
(216) Acid Linings 193
(217) High Pressure Evaporator 193
(218) Söderlund-Boberg Evaporator 193
(219) Evaporation of Acid Liquids ... 196

CHAPTER XV.—CRYSTALLIZATION (220) 197
(221) Purification of Crystals 197
(222) Size of Crystals.. 197
(223) Control of Crystallization 198
(224) Striking 198

PAGE

(225) Gravity of Solutions 199
(226) Viscosity of Solutions 200
(227) Crystallizing Pans 200
CHAPTER XVI.—Drying (228) 201
(229) Drying Pan 203
(230) Vacuum Pan 203
(231) Shelf Retort 203
(232) Conditioning 203
(233) Carrier Method .. 203
(234) Ruggles' Classification 206
(235) Lowden Dryer .. 211
(236) Efficiency 212
CHAPTER XVII.—Distillation (237) 215
(238) Example 215
(239) Object 215
(240) Partial Separation 215
(241) Distilling Acids .. 216
(242) Hart's Apparatus 219

PAGE

(243) Many Forms of Condensers 220
(244) Hough Condenser 222
(245) Efficiency 223
CHAPTER XVIII.—Absorption of Gases (246) 224
(247) Tower Absorber. 227
(248) Hart-Adamson Absorber 228
(249) Absorption of NO_2 229
CHAPTER XIX.—Mixing and Kneading (250) 231
CHAPTER XX.—Autoclaves (251) 233
CHAPTER XXI.—(252) 235
(253) Barrels 235
(254) Boxes 235
(255) Corrugated Fiber Boxes 235
(256) Glass Packages .. 235
(257) Paper or Cloth Bags 235

List of Illustrations

FIG.		PAGE
1.	Lead Lined Iron Pipe	7
2.	Lead Lined Iron Valve	7
3.	Hart Evaporator	10
4.	Jacketed Open Mixing Tank	11
5.	Open Mixing Tank and Evaporator	12
6.	One Piece Jacketed Closed Mixing Tank	12
7.	Jacketed Closed Mixing Tank	12
8.	Glass Lined Ware Made by the Pfaudler Co.	13
9.	Three Sizes of Enameled Vacuum Still	13
10.	Waterloo Concrete Mixer	27
11.	The Cement Gun	28
12.	Hollow Tile Construction	29
13.	Stepped Foundation	31
14.	Foundation Footing	31
15.	Improper Method—Daubing the Corner	33
16.	Proper Method—Shoving up the Brick	33
17.	Corner Layout	34
18.	Plumb Board	34
19.	American Bond	36
20.	Flemish Bond	36
21.	Proper Bonds and Corners	36
22.	Ashlar, or Dressed Stone Wall, with String Courses, (A) Window Opening, and Brick Corner	37
23.	Plan of Pilaster, with Bearing-plate of Cast-iron, and Steel Floor-beam	38
24.	Elevation of 23	38
25.	Section of 23	38
26.	Upright Boiler	43
27.	Boiler Tube Expanded into Top Sheet and Upset	43
28.	Horizontal Boiler	43
29.	Multiple Fire Tube Boiler	43
30.	The Cornish Boiler	46
31.	The Galloway and Lancashire Boilers	47
32.	Detail of Fig. 28	48
33.	Boiler Setting	48
34.	Herring Bone Grate	48
35.	Herring Bone Grate for Upright Boiler	48
36.	Boiler Setting	49
37.	Furnace Door	49
38.	Water Tube Boiler	51
39.	Detail Showing Position of Drum and Headers	51
40.	Detail Showing Front of Drum and Headers	51
41.	Detail of Hand Hole in Headers	51
42.	Detail of Water Gage	51a
43.	Cross Section of Lower Valve B of Water Gage	51a
44.	Gage-Cock	51a
45.	Steam Gage with Siphon	52
46.	Combined Safety and Stop Valve	52
47.	Safety Valve	52

FIG.		PAGE
48.	Check-Valve	52
49.	Plug-Cock	52
50.	Worthington Pump, Plunger and Ring Pattern	54
51.	Worthington Pump, Piston Pattern	55
52.	Steam Engine	59
53.	Slide Valve	59
54.	Crosby Indicator	59
55.	Indicator Diagram	62
56.	Steel-plate Piston	62
57.	Piston Ring	62
58.	Piston Ring	62
59.	Packing Box	63
60.	Cross Head	63
61.	Connecting Rod	63
62.	Governor	63
63.	Reeves Producer	65
64.	Sectional Elevation of Suction Gas Producer and Gas Engine	65
65.	Sectional Elevation of Three Cylinder Gas Engine	65a
66.	Vertical Section of Gas Engine	66
67.	Gas Engine Governor Mechanism	67
68.	Successive Stages of the Four Cycle Gas Engine Method	67
69.	Igniter Gear for Three Cylinder Four Cycle Gas Engine	68
70.	Igniter Body, Make and Break Igniter	68
71.	Pipe Fittings	71
72.	Tap Wrench	72
73.	Pipe Tap	72
74.	Pipe Union	72
75.	Pipe Cutter	72
76.	Pipe Threader	72
77.	Pipe Wrench	72
78.	Stoneware Lining—For Use in Copper Mantles Stoneware Pipe Connections Stoneware Stop-Cock	73
79.	Taper Flange Pipe	74
80.	Split Taper Collars for Pipe Joints	74
81.	Cast-iron Shell for Pipe	74
82.	Stop-cock for Blow-case	76
83.	Vessels Armored for Heavy Pressures	76
84.	The Plath Acid Elevator	77
85.	Air Lift	78
86.	Injector	79
87.	Pulsometer	79
88.	Plunger and Piston Pumps	80
89.	Centrifugal Pumps	81
90.	Construction of Crusher, End View	84
91.	Construction of Crusher, Top View	84
92.	Kennedy Gearless Standard Crusher	86
93.	Sturtevant Coarse Breaker	88
94.	Sturtevant Fine Crusher	88
95.	Traylor Crusher	89
96.	Rolls	91
97.	Diagram Illustrating the Angle of Nip of Rolls	91
98.	Krom's Method of Attaching Roll Shells	91

FIG.		PAGE
99.	Sturtevant Balanced Rolls 21 inches x 10 inches	92
100	Hardinge Conical Ball Mill, Showing Distribution of Balls	94
101.	Hardinge Conical Ball Mill, Showing Path Followed by Balls	94
102.	Abbe Ball Mill	95
103.	Pulverizer-Jar Mill, Mill Closed	96
104.	Pulverizer-Jar Mill, Mill Open	96
105.	Impact Screen with Covered Housing for Dry Screening	98
106.	For Wet Screening with Distributor,	99
107.	Screen Frame for Dry Work	100
108.	Screen Frame for Wet Work	100
109.	Setting for a Single 3 ft. x 4 ft. Impact Screen	100
110.	Vertical Section of Jeffrey's Swing Hammer Pulverizer	101
111.	Raymond Mill	102
112.	Raymond Mill	103
113.	Williams Mill	104
114.	Screw Conveyors	107
115.	Screw Conveyors	107
116.	Work Trucks	107
117.	Work Trucks	107
118.	Work Trucks	107
119.	Work Trucks	107
120.	New England Tank and Tower Co. Mixer	110
121.	John Johnson Co. Mixer	111
122.	Werner and Pfleiderer Co., Rapid Dissolver, Size 1	112
123.	Pachuca Mixing Tank	113
124.	Buff-Dunlop or Shanks Apparatus for Lixiviating	114
125.	Black Ash Lixiviating Tanks	115
126.	Improved De Laval Cream Separator	117
127.	Centrifuge	119
128.	Inner Bowl for Centrifugal Separators	120
129.	Centrifugals	121
130.	Centrifugals	121a
131.	Centrifugals	122
132.	Fletcher Centrifugal	123
133.	Fletcher Centrifugal	124
134.	Diagram Showing Work of the Settler	128
135.	Diagram Showing Work of the Settler	129
136.	Dorr Thickeners and Dorr Agitators	130
137.	Dorrco Pump	132
138.	Dorr Thickener	133
139.	Dorr Agitator	134
140.	Paper Filter	135
141.	Shimer Filter	135
142.	Cloth Filter	135
143.	Sperry Filter Press	136
144.	Shriver Filter Press	138
145.	Shriver Filter Press, Perforated Screen Surface	139
146.	Shriver Filter Press, Corrugated Surface	139
147.	Shriver Filter Press, Pyramid Surface	139
148.	Shriver Filter Press, Flap Cock Closed	139
149.	Shriver Filter Press, Flap Cock Open	139
150.	Shriver Filter Press, Thrust Block Quick Opening Device	139
151.	Shriver Filter Press, Ratchet Closing Device	140

FIG.		PAGE
152.	Shriver Filter Press, Ratchet Closing Device	140
153.	Shriver Filter Press, Tools Used and the Screwed Clip Nut Cloth Fastener	141
154.	Kelly Filter Press, End View and Section	141
155.	Kelly Filter Press	142
156.	Kelly Filter Press	143
157.	Kelly Filter Press	144
158.	Kelly Filter Press	145
159.	Kelly Filter Press	146
160.	Sweetland Filter, Open	147
161.	Sweetland Filter, Open	147
162.	Sweetland Filter, Closed	148
163.	Sweetland Filter Closed	149
164.	Sweetland Filter, Longitudinal Section	150
165.	Sweetland Filter, Cross Section	151
166.	Sweetland Filter, Cell	151
167.	Sweetland Filter, Rotatable Pressure	152
168.	Sweetland Filter, Lead Lined	152
169.	American Continuous Suction Filter	153
170.	American Continuous Suction Filter	154
171.	American Continuous Suction Filter, Single Cell	154
172.	American Continuous Suction Filter	155
173.	American Continuous Suction Filter, Valve Construction	156
174.	Oliver Continuous Filter	157
175.	Portland Filter	158
176.	Side Feed Wooden Chamber Filter Press	158
177.	Varnish Filter Press	159
178.	Wooden Tanks	164
179.	Wooden Tanks, Detail	167
180.	Stoneware Tanks	169
181.	Stop-Cocks to Be Used with These Tanks	169
182.	Atomizing Evaporator	175
183.	Steam Heated Seamless Cast Iron Pans	178
184.	Flanged Sleeve Screwed into the Inner Shell	178
185.	Outlet Placed to one Side of the Center	178
186.	Outlet is Fig. 184 with Boss on Bottom to which a Gate is Fitted	178
187.	Butterfly Valve Flush	178
188.	Other Styles of Pans	179
189.	Other Styles of Pans	179
190.	Bracket Type Agitator	179
191.	Propeller Screw Agitator	180
192.	100-Gallon Standard Type Vacuum Pan	181
193.	200-Gallon Vacuum Pan with Overhead Drive	182
194.	Zaremba Evaporator	183
195.	Buffalo Foundry and Machine Co. Evaporator	184
196.	Buffalo Foundry and Machine Co. Evaporator	184
197.	Buffalo Foundry and Machine Co. Evaporator	185
198.	Buffalo Foundry and Machine Co. Evaporator	186
199.	Multiple Effect	187
200.	Zaremba Crystallizing Evaporator	190
201.	Zaremba Crystallizing Evaporator	191
202.	Zaremba Crystallizing Evaporator	192
203.	Acid Proof Linings for Vacuum Evaporators	194

FIG.		PAGE
204.	Söderlund-Boberg Evaporator	195
205.	Crystallizing and Drying Pan	201
206.	Vacuum Crystallizing and Drying Pan	202
207.	Vacuum Shelf Dryer with Pump and Condenser	204
208.	Direct Heat Shelf Retort	205
209.	Details of a Single Shell Dryer	209
210.	Lowden Dryer	211
211.	Lowden Dryer	212
212.	Lowden Dryer	212
213.	Column Apparatus for Distilling Acetic Acids	216
214.	Benzol and Toluol Rectifying Still with Internal Reflux	217
215.	Benzol and Toluol Rectifying Still with External Reflux	218
216.	Apparatus for Distilling Acids	219
217.	Improved Apparatus for Distilling Acids	220
218.	Hart's Nitric Acid Condenser	221
219.	Enameled Condenser	222
220.	Hydrochloric Acid Condenser	224
221.	Stoneware Tourills	225
222.	Circular Stoneware Towers, Lunge-Rohrmann-System	226
223.	Hydrochloric Acid Plant	227
224.	Acid Condenser (Hydrochloric)	228
225.	Asbestos Mixer	231
226.	Vacuum Masticator	232
227.	Mixers Driven from one Countershaft	232
228.	Autoclave without Stirrer	234
229.	Autoclave with Stirrer	235

Chemical Engineering

INTRODUCTION.

(1) The field of chemical engineering is a very large one. To cover it properly requires the combined experience of many men. It is bound up with chemical technology and to be of real use, statements must be not only scientifically precise but keep in mind constantly the question of income and expense. Where works are already in operation it is not unusual to find that the practice has grown antiquated, but the young engineer should go at the task of improving cautiously. Those deriving a good income from existing operations are slow to see the necessity of spending money to improve the product. They are shy of too much theory, especially when propounded by young engineers. The beginner is urged to improve quality and output with existing apparatus and so inspire confidence before suggesting changes.

Improved processes should always be tried out in the laboratory, then on a small manufacturing scale before being introduced as a part of the large scale operation. Neglect of this precaution has led to serious loss.

CHAPTER I.

MATERIALS.

It is a well established fact that we can make anything if we have something to make it in. For small scale operations this causes little difficulty but often becomes serious when working on ton lots.

(2) **Iron**[1] is usually the cheapest material for containers. Means for casting all but very large pieces are available locally, thus enabling careful superintendence while casting, and avoidance of mistakes and heavy transportation charges.

Cast iron may be used as a container for sulphuric acid of over 60 per cent. strength at ordinary temperatures, or for 70 per cent.

[1] See also Fawsitt & Powell, *J. S. C. I.*, 1914, 234 and Fawsitt *Ib.*, 1920, 147T.

acid at 100° C.; the higher the temperature the more iron will dissolve. Cast iron resists fuming sulphuric acid better than mild steel, but alternate contact with acid and air develops cracks.

(3) **Mild Steel** of say 0.15 per cent. carbon such as is used for tanks, boilers, etc., is acted upon by sulphuric acid to a greater extent than cast iron. It is the best material for storing oleum, but prolonged storage of oleum containing from 100-107 per cent. H_2SO_4 (0-20 per cent. SO_3) should be avoided as it attacks steel much more rapidly than when above or below this limit.[1] Mild steel is also best suited for mixed nitric and sulphuric acids and may be used for all mixtures containing not less than 12 per cent. sulphuric acid with a total acidity of 90 per cent. at ordinary temperature. As the temperature rises the action on the steel increases, and as this action is exothermic, it may easily become dangerous. It may be bent into shape and melted together by the oxyacetylene blowpipe. Unprotected cast iron or steel can not be used as a container for ferric solutions, chromic acid or solutions of copper, mercury or silver. Solutions of the alkalies do not affect them.

HIGH SILICON IRON ALLOYS[2]

such as Duriron and Tantiron are resistant to dilute sulphuric and nitric acids. They suffer, however, from lack of strength, being easily cracked by a blow or by too rapid heating.

(4) **Composition.**—"Duriron, which is typical of these alloys is referred to throughout this article. Its approximate analysis follows:

		Per cent.
Silicon	about	14.00
Carbon	below	0.60
Manganese	"	0.50
Sulphur	"	0.10
Phosphorous	"	0.20
Iron	about	85.00

In a general way, other things being equal, the rate of depreciation will vary inversely with the silicon content, between the limits of 10 and 25 per cent.

[1] See Knietsch, *Ber.*, 34, 4108, 1901.
[2] See Kowalke, *Trans. Am. Electrochem. Soc.*, 31, 205.

"This does not, however, hold true for the lower ranges, as experiments show that alloys containing between 7 and 8 per cent. of silicon are much more readily attacked than is the case with grey iron having only 3 to 4 per cent., and furthermore white irons, with 1 per cent. or less, resist weak sulphuric acid much better than where the content is from 1-10 per cent.

"While alloys of 18 to 25 per cent. of silicon, or thereabouts, are so resistant as to withstand even hot hydrochloric acid—the presence of such quantities render them so brittle that they are practically useless for commercial purposes.

"An excessive manganese content, on the other hand, say from 1 to 2 per cent., adds to the strength of the casting and softens it to the extent of making it machinable, but has the drawback of lowering the acid resisting properties of the alloy.

(5) Physical Properties.—"Duriron is a cast metal extremely hard and close grained. It shows a white fracture, taking and retaining a better polish than nickel.

"It has a specific gravity of 7.00—is not as strong as cast iron—has a coefficient of expansion two and one-half to three times greater than that of cast iron or steel—a heat conductivity about that of cast iron and an electrical conductivity only about one-fortieth that of standard annealed copper. Contraction allowance for casting is three-sixteenth inch per foot.

"Duriron will not soften materially, nor lose its shape, at a temperature below its melting point, about 2500° F. It is very fluid in the molten state, permitting pouring into very thin sections when desirable, and shows practically no oxidation at even the highest temperatures.

"Owing to its extreme hardness it is highly resistant to *erosion* and cannot be machined with a cutting tool, but must be finished by grinding.

(6) Chemical Properties.—"Duriron is practically unaffected by any strength of nitric, sulphuric, acetic and most other acids or alkalies. The chief exception is commercial concentrated hydrochloric, which causes marked action; this lessens as the acid is diluted, until with 1 or 2 per cent. there is no loss even when

boiling. Samples of the alloy exposed continuously for five weeks to hydrochloric of different strengths, at temperatures ranging between 178° to 185° F. lost weight as follows:

In 25 per cent. acid (by weight)..... 1.72 per cent.
In 10 per cent. acid (by weight)..... 0.74 per cent.

with hydrochloric acid gas the resistivity is highly satisfactory.

"Phosphoric of certain strengths can be handled, others attack readily. Strong aqua regia and hydrofluoric cannot of course be withstood.

"The following laboratory tests, at room temperature, are interesting, as illustrating comparative resistivity.

In 25 per cent. sulphuric (by weight):
Duriron.....No loss in one year
Cast iron.....Completely dissolved in 16 days
Wrought iron.....Completely dissolved in 30 days
In 25 per cent. nitric (by weight):
Duriron.....In one year lost 11/1000 of 1 per cent.
Cast iron.....Completely dissolved in 63 hours
Wrought iron.....Completely dissolved in 58 hours

As a general rule Duriron is not suitable for fusions, though there are some exceptions.

(7) Design of Apparatus.—"Owing to the high coefficient of expansion and the various manufacturing difficulties encountered, careful attention to a number of points are necessary in designing apparatus that can be economically and successfully produced in this material.

"While great progress has been made in producing large and difficult castings, it is important to avoid extensive flat surfaces, abrupt changes in section and sharp angles.

"Curved surfaces are not only stronger than flat, but they are better able to resist temperature changes without cracking.

"It is not good practice to use chaplets in supporting cores, consequently all coring should be made as simple as possible.

"As the alloy is too hard to be economically drilled, holes should be cored.

"Hemispherical bottoms for kettles are best and should be used wherever possible.

"While covers for kettles, and similar apparatus, can be made almost flat, if not too large, it is far better practice to give them

considerable arch, 3 or 4 inches per foot of diameter not being excessive. Openings in covers should not be placed too close together or in direct line across the cover.

(8) Installation of Apparatus.—"While Duriron is more easily broken than cast iron, it will be found amply strong if properly handled and installed.

"Avoid unnecessary strain on every part.

"Line up and support all members carefully before tightening connections.

"Pipe lines should be anchored, especially at bends, and wherever attached to flanged apparatus.

"As expansion of Duriron is about two and a half to three times that of iron or steel, allowance must be made for this when installing.

"Draw up equally on every bolt and use only enough pressure to prevent leakage. If gasket is soft enough a 6-inch wrench held between thumb and forefinger will be sufficient.

"Hard gaskets must not be used. They should be fairly soft and preferably at least one-sixteenth inch thick. The selection of material for gaskets and packing should be based on kind of acid handled.

"Do not use hard cements for bell joints. These prevent expansion and may cause cracking."[1]

(9) "Resistal."—High alloy steels of unknown composition manufactured by the Crucible Steel Co. of America have recently appeared. A description of their properties will be found in *Chem. and Met. Eng.* for Oct. 26, 1921, p. 797.

(10) Nichrome contains 60 per cent. nickel, 25 per cent. iron, 12 per cent. chromium and 2 per cent. manganese. Some other alloys of similar composition contain also a small percentage of aluminum. These alloys are as strong as steel and resist acids fairly well. They have a high melting point.

(11) Atherite contains 60 per cent. copper, 27 per cent. zinc, 10 per cent. nickel and 0.5 per cent. antimony. This alloy is used for the organic acids, for sulfurous, sulfuric and hydro-

[1] This article on the properties of the iron silicon alloys I owe to the kindness of [illegible] of the Duriron Co.

fluoric and for the caustics except ammonia. It is made by H. M. Atherite Co., New York City. A similar alloy is Meco metal made by Midwest Engine Co., Indianapolis.

(12) Electron and Magnalium are very light metals containing magnesium and aluminum. The latter metal contains also a little copper. An enamel has been devised for this which adheres very closely and is said to resist acids. The unprotected metal is not seriously attacked by ammonia or caustic alkalies.

(13) Copper is largely used for stills, separating columns and vacuum pans. It is especially well adapted for crude acetic acid but air should be excluded. Copper vessels have been largely used also for tartaric acid and acid potassium tartrate and for citric acid. Copper should not be used for strong acids nor for ammonia nor ammonium salts.

(14) Nickel has been comparatively neglected as a material for chemical containers, but as now furnished to the trade it has many desirable properties. It is as strong and as malleable as steel; it is much stronger and stiffer than copper, with about the same specific gravity. It may, therefore, replace copper to advantage with pure acetic acid, since it need not be so heavy. It is about three times as strong as copper, and has a much greater scrap value. It may be welded or riveted and the seams can be calked as with steel.[1]

(15) Lead and Lead Lined vessels are very largely used in chemical apparatus as the metal is indifferent or nearly so to many chemical solutions. Many leaden articles such as pumps and fans are cast of hard lead, an alloy of lead and antimony, which is stiffer, stronger and harder than pure lead. Lead burning is an art by itself and large chemical works nearly always have several lead burners. Lead is soft, and when heated expands but has not sufficient tensile strength to resume its original form when cooled. As a result, lead linings often pucker or become covered with ridges and are rapidly destroyed. Lead lined pipe shown in Figs. 1 and 2 is cheaper and stiffer than lead pipe. Ordinary lead pipe of 1 inch diameter will sustain a pressure of say 60 pounds

[1] I am indebted to H. F. Whittaker for this and many other valuable suggestions contained in this edition.



Lead Lined Iron Pipe

Fig. 1.



Lead Lined Iron Valve

Fig. 2.

and may be used in evaporators. Lead may be used for all strengths of sulphuric acid up to 80 per cent. at all temperatures up to the boiling point. Above 80 per cent. it is attacked rapidly at high temperatures but not at ordinary air temperatures up to 98 per cent., over 98 per cent. it is rapidly attacked. Acetic acid in presence of air dissolves lead rapidly. In a vacuum the oxide on

the surface of the lead is removed, but the lead itself is not affected. Carbonic acid in presence of moisture corrodes it rapidly.

(16) **Aluminum**, cast or spun, can now be had in large sizes and will probably increase in use very rapidly. It dissolves very slowly in nitric acid, and if the acid be pure and free from chlorine and oxides of nitrogen the containers are not attacked. Sulphuric acid dissolves it very slowly. Acetic acid when pure does not act, but it dissolves rapidly in hydrochloric acid or with almost any acid containing chlorides, and in alkalies. The presence of formic acid in acetic acid, or of acetic anhydride, causes it to attack aluminum especially at high temperatures. Commercial sheet aluminum and vessels made of it when examined are found to have a thin covering of alumina which is protective. When a vessel filled with acid liquid is sharply struck so as to destroy this protective coating the metal often dissolves much more rapidly. Aluminum is very desirable because of its lightness which makes it easy to handle. Vessels made of aluminum are not so expensive as might at first sight appear because the metal is so light.

(17) **Silver** vessels are occasionally used for recrystallizing chemically pure chemicals or where great purity is essential. It serves well for dissolving sodium bicarbonate which has first been purified by treatment with limited quantities of cold water, and for drying the crystals so obtained. Lead is also used for this purpose but is much less desirable. It is, besides, easy to scrape off minute bits of lead in removing the contents which plays havoc with platinum crucibles. Silver may be obtained in the form of quite thin sheets for such purposes. These sheets are bent up on the edges to the required height and the projecting corner folds flattened against the sides. If carefully handled such containers will last a long time. When it becomes necessary to scrap them they still retain a considerable portion of the original value. Silver is not attacked by hydrochloric acid.

(18) **Gold vessels** have also been used to a limited extent but are far too costly for most uses. For the manufacture of a

few pure chemicals they are very desirable. Gold while much less valuable than platinum dissolves and melts more readily. It cannot be used with many acids, especially when chlorides or nitrates are also present.

(19) **Platinum**, because of its high price is excluded from most uses. It is used in the form of condenser tubes, for condensing pure hydrofluoric acid. The distilled acid is caught and distributed in ceresine bottles. In former times large platinum stills were used in concentrating sulphuric acid.

(20) **Illium** is an alloy of nickel, chromium, copper, aluminum and manganese discovered by Prof. S. W. Parr[1] and used as a substitute for platinum in the Parr calorimeter. An analysis gave

Cu	6.42	Al	1.09
Mn	0.98	Fe	0.76
Si	1.04	Cr	21.07
W	2.13	Mo	4.67
Ni	60.65	Total	98.81

(21) **Lead-Thallium Alloys** have recently been examined by Fink & Eldridge for use as anodes in the electrolytic deposition of copper from sulphate solutions. (Advance copy of paper read at September Meeting, *Am. Electrochem. Soc.*, 1921). Ferrosilicon alloys when employed dissolve at the rate of 5 to 6 pounds per 100 pounds copper deposited. A minimum loss of 1.2 pounds per 100 of Cu deposited resulted from using leaf anodes containing 10 per cent. Tl and 20 per cent. Sn as compared with 65 pounds loss for ordinary lead. The alloys with high melting points are most resistant to corrosion.

(22) **Copper Iron Alloys.**—Clevenger and Ray have found that copper added to steel in small amount has a marked influence upon the corrodibility of the resulting metal. Their paper is very full of detail and should be consulted (*Trans. Am. Inst. Min. Eng.*, Vol. 47, p. 528). The same subject is treated in detail by Buck and Handy in a paper published in the *Journal of Industrial and Engineering Chem.*, March, 1916. An alloy containing 0.25 per

[1] *J. Am. Chem. Soc.*, 37, 2515 (1915).

cent. Cu is now marketed by the American Sheet and Tin Plate Co.

(23) **Monel Metal** is an alloy of copper and nickel for which great resistance to corrosion is claimed. It is put on the market by the International Nickel Co., and being reduced directly from the ore without separation of the nickel from the copper is relatively cheap. (See *Trans. Am. Inst. Min. Eng.*, Vol. 49, p. 645; see also *Chem. and Met. Eng.*, **25**, 797.)

(24) **Bronze.**—The paper first above cited contains a variety of tests on protective paints and on the action of dilute sulphuric acid and copper sulphate solutions on bronze which are of considerable interest. The paper has to do with the leaching of copper ores. Bronze contains 90 per cent. copper and 10 per cent. tin. Manganese bronze contains zinc as do Tobin bronze, Sterro and Delta metal. Phosphor bronze contains 1 per cent. phosphorus. Bronze is the best metal for strong formic acid.

(25) **Glass** vessels are not available for large size apparatus. Glass tubing up to 3-inch diameter and test tubes up to 1½x18



Fig. 1.—Hart Evaporator.

inches may be had and these are used in the Hart boilers (Fig. 3) and condensers (U. S. Patents 603,508; 1,096,838; 1,254,689; 525,761 and 601,466). For larger apparatus the Pfaudler Co., of Rochester, N. Y., supplies glass-lined apparatus shown in Figs. 4-8. The Pfaudler Co. have supplied me with the following data under date of Oct. 31, 1921. They are based on actual test runs.

Heating: Coefficient of conductivity for enameled steel five-sixteenth inch thick, steam to water: 93 B. t. u. per square foot per 1° F. difference in temperature per hour.

Cooling: Coefficient of conductivity for enameled steel five-sixteenth inch thick, cold to hot water, direction of flow of cold water, counter current: 77 B. t. u. per square foot per 1° F. temperature per hour. For a description of the method of manufacture followed by this concern, see C. H. Jones, *Chem. and Met.*



Fig. 4.—Jacketed Open Mixing Tank.

Fig. 5.—Open Mixing Tank and Evaporator.

Fig. 6.—One-piece Jacketed Closed Mixing Tank.

Fig. 7.—Jacketed Closed Mixing Tank.



Fig. 8.—Glass Lined Ware made by the Pfaudler Co.



Fig. 9.—Three sizes of Enameled Vacuum Still.

Eng., Nov. 9, 1921, p. 883. The Elyria Enameled Products Co., Elyria, Ohio, also supply this ware upon a cast-iron base. This company states that their glass enamel has the resisting qualities of chemical glass. It is fused into the metal itself and will not crack, scale or craze. Fig. 9 shows three sizes of vacuum still. Stuart and Peterson, Burlington, N. J., supply enameled cast-iron ware for similar purposes.

(26) **Fused silica** is now being used to a considerable extent in the manufacture of chemical ware, taking the place of glass. It is rather more fragile but endures sudden changes of temperature much better than glass. It is furnished by the Thermal Syndicate, Ltd., 50 E. 41st St., New York City, Chas. Engelhard, 30 Church St., New York City, and the General Ceramics Co., 50 Church St., New York City.

(27) **Chemical stoneware** is supplied in great variety by the General Ceramics Co., 50 Church St., New York City, Chas. Graham, 986 Metropolitan Ave., Brooklyn, N. Y., U. S. Stoneware Co., Akron, Ohio, and Maurice A. Knight, E. Akron, Ohio.

(28) **Brick and Tile** linings are often used for wooden or steel vessels as a protection against acid liquids. Duro brick or other so-called chemical brick are preferred for this use. Tile is usually preferred for such linings because two or more layers may be applied in the same space. The cement used may be Pecora, Duro or Positive Seal. The inside of the vessel is first to be covered with Positive Seal cement. Where successive courses of tile are laid they should, of course, break joints.

(29) **Wood and Rubber** is largely used in the manufacture of tanks used for various operations as well as for storage. A special chapter is devoted to tanks and reference is made to this chapter for more complete information. For storing muriatic acid the B. F. Goodrich Co., Akron, Ohio, line wooden tanks with pure rubber. Cypress, free from knots, is preferred and must be carefully dried and kept under cover. The bottoms of these tanks have a lining of white pine and a fillet to avoid a sharp corner. The first coat is a special cement laid directly on the wood as a

primer. The second coat is a different preparation. Upon this is laid a coated canvas sheet tacked to the wood at 4-inch spacings with flat-headed staples or tacks. Over this goes a pure Para rubber sheet made 6 or 8 ply so that holes may not extend through the sheet. The sheets are 30 inches to 40 inches wide cut to fit with overlap of one-half inch for joints which are cemented. The tank has a cover made in the same way. The acid is siphoned with a 1½-inch pure rubber hose with vulcanized end.

The American Hard Rubber Co., New Brunswick, N. J., is developing a tank car for carrying muriatic acid according to the patent of S. Boyer, Feb. 1, 1921, No. 1,367,231.

Wood is rapidly attacked by sulphite solutions as well as by solutions which attack cellulose. Cumar, made by the Barrett Co., may be used for coating such tanks. It resists acid and caustic but not nitric acid. For dilute acids, asphalt base varnishes are sometimes used.

(30) **"Bakelite"**[1] is obtained by heating phenol or cresol with formaldehyde preferably in presence of ammonia or other alkaline condensing agents. In view of the fact that ammonia in presence of formaldehyde is immediately transformed into hexamethylenetetramine it is possible to use directly the latter chemical in part or in totality, instead of the usual commercial formaldehyde solution. Other substances which are the equivalent of formaldehyde as for instance its polymer paraform, or methylal may be used for the same purpose.

The resulting phenol condensation product is hard and transparent and has the appearance of amber; but its chemical and its other physical properties are decidedly different. For instance, if heated it does not melt and if carried at higher temperatures it chars and blackens without however liquifying. Furthermore it is insoluble in all organic solvents and withstands most chemicals which act upon amber or other resins. It is harder than amber and its tensile strength is much higher. It has some analogy with amber by being an excellent electrical insulator and this property in conjunction with its great strength as well as its chemical and

[1] This description of the properties of Bakelite was kindly contributed by Dr. Baekeland himself.

physical resistivity has led to endless technical applications where resinous substances, celluloid or rubber are unsuitable.

(31) **Bakelite Enamel** is a varnish which is applied with a brush in successive coats. After each coat is applied the solvent is removed with a current of warm air. It is then slowly heated to 150°.

(32) **Cements.**—Duro cement is furnished by the Harbison Walker Co., of Pittsburgh. It is a white powder and is mixed with sodium silicate and applied and then set with dilute acid. It resists muriatic acid very well but the expansion and contraction is apt to crack the joints. Glycerine and litharge cement is made by mixing the two ingredients to a paste. It sets slowly. The time of setting may be shortened by adding sodium silicate solution. Pecora and Tharco cements are more plastic than Duro, and are less liable to crack under temperature changes. Positive Seal cement has been used to a considerable extent for linings. It has an asphalt base and is furnished in several grades. Oxychloride cements, such as a mixture of magnesia and magnesium chloride or zinc oxide and zinc chloride may be used but are not acid resisting. The Anti-Hydro Waterproofing Co., New York City, supply a material to be mixed with concrete to make it water-proof and acid resistant.

(33) **Paints and Varnishes.**—These are used for the protection of iron and steel exposed to acid vapors and occasionally to protecting steel and wooden tanks against mild corrosive materials for a short time. Usually they must be carefully watched and frequently renewed. The best of them have an asphalt base. This is objectionable in some cases because the finish is black which absorbs all the light giving gloomy interiors. Some of these paints have a coal tar pitch as the base dissolved in naphtha. These give a coating which is brittle in cold and soft in hot weather. Water gas pitch used in this way gives better results than coal tar pitch

REFERENCES.

"Paint Researches and Their Practical Applications," H. A. Gardner, 1917.

"Protective Paints and Pigments," D. F. Leary, *J. Assn. Eng. Soc.*, Jan., 1914.

"Investigations of the Protective Value of Structural Steel Paints," J. S. Coye, Vol. 17, *Bull.* No. 49, Iowa State Agrl. Coll.

"Preservative Metal Coatings for Metals," *Am. Soc. Test. Mat.*, June, 1917.

"Enamels for Sheet Steel," R. D. Landrum, *Chem. Eng.*, Oct., 1912.

"Reading List on Vitreous Enameling on Iron and Steel," C. J. West, Vol. 4, No. 1, Jan., 1921, *J. Amer. Cer Soc.*

"Protective Coatings," W. Riddle, Feb., 1912, *Proc. Eng. Soc. of West. Pa.*

CHAPTER II.

CORROSION

(34) The deterioration of apparatus from whatever cause may be conveniently treated under the head of corrosion to which most of it is due. The theory involved has been summarized by Watts and Whipple, *Trans. Am. Electrochem. Soc.*, **32**, 257, from which I shall quote as follows:

"On account of the great economic interests involved, the corrosion of metals is one of the most important of the many technical problems which to-day engage the attention of electrochemists. The importance of galvanic couples in the corrosion and protection of metals received early recognition, but it is only in recent years that the whole problem of corrosion has been recognized as being electrochemical in its nature. It was formerly supposed that zinc dissolved in sulphuric acid because the affinity of this metal for the SO_4 radical exceeded that of hydrogen for the same; and that for the action to go on until either the zinc or the acid was exhausted it was only necessary that the product, zinc sulphate, should be soluble.

"Among the many natural phenomena to whose explanation the theory of electrolytic dissociation has been applied, is the corrosion of iron (W. R. Whitney, *J. Am. Chem. Soc.* (1903), 1, 394); according to this, the formation of a soluble compound is not a prerequisite to the dissolving of a metal by an acid, the metal going directly into solution as ions, and any compounds which may be formed being the result of combinations which occur after solution has taken place. From either the chemical or the ionic point of view, an electrolyte is like a room so crowded that no newcomer can enter unless some of those already present pass out to make place for them."

(35) It has long been known that the presence or absence of oxygen made a great difference in the rate of corrosion, and that in some cases absence of oxygen inhibited corrosion. This appears to be due to the fact that oxygen when present combines

with the hydrogen and thus acts as a depolarizer. It is well to remember in plating metals like lead upon those more liable to corrosion that electroplating coats are sure to be more or less porous because the metal is deposited as crystals. By burnishing such coatings this defect is partly remedied. It goes without saying that if a small section of such protective coating is removed from any cause, electrolytic action at once begins and the value of the coating is destroyed. This holds true of other coatings as well and is true of galvanized iron, tinned iron or copper, and enameled vessels of all kinds.

(36) **Arsenic Deposits.**—When metals of higher potential are deposited on a metallic surface its liability to corrode increases. Thus, if cadmium be immersed in dilute sulphuric acid it dissolves very slowly at the ordinary temperature, but if a little copper sulphate solution be added the copper will deposit in small crystals on the surface, we get a voltaic couple and solution takes place rapidly. In a few cases deposited elements inhibit or at least decrease the amount of corrosion. This is the case when arsenic is deposited on iron. "Since iron is electro-positive to arsenic, it displaces this element from solution, and a porous coating of arsenic is formed on the iron. In the voltaic cell thus formed arsenic is the cathode, and consequently it is on this that the hydrogen expelled by the dissolving of iron is deposited. The discharge potential of hydrogen on arsenic exceeds the potential of iron in dilute sulphuric or hydrochloric acid, and hence as iron dissolves, thereby causing an accumulation of hydrogen on the arsenic, the deposition of this gas becomes more difficult, and before enough hydrogen has been displaced to escape as visible bubbles, the potential required for its further deposition equals the driving force, the potential of iron, and action therefore ceases."[1]

(37) **Amalgamation.**—The effect of amalgamation is to decrease corrosion. The theory has been that the effect of amalgamation was to present a pure metallic surface to the action of the acid but this appears to be insufficient. It has been stated by the chemists of the New Jersey Zinc Co., for example, that up to a

[1] Watts and Whipple, *loc. cit.*

certain limit of purity zinc dissolves less readily in acids but above that limit as purity increases solubility increases.

(38) In the paper above quoted Watts and Whipple give a considerable number of actual determinations of the extent of corrosion of different metals which I have combined into a single table:

TABLE I.

Showing the solubilities of different metals in various acids.

Metal	Temp.	Time	Area	Reagent	Loss
Pb	37.5	45h	60 cm.	N. Acetic 190 cc.	0.2143
Pb	37.5	45h	60 cm.	N. " " " +0.25 g. Na_2AsO_4	0.0490
Pb	37.5	45h	60 cm.	N. " " " +2 g. $HgCl_2$	0.8529
Pb	37.5	45h	60 cm.	N. " " " " " " 5 cc. H_2O_2	6.5596
Pb	37.5	45h	60 cm.	N. " " "	0.2019
Pb	37.5	45h	60 cm.	N. " " " 5 cc. H_2O_2	6.4026
PbHg	37.5	45h	60 cm.	N. " " "	0.1515
PbHg	37.5	45h	60 cm.	N. " " " 5 cc. 30% H_2O_2	5.5071
Cu	38	19-22	60-64 cm.	N. HCl 180 cc.	0.1171
Cu	38	"	"	N. " " " +10 g. $KMnO_4$	4.6084
Sn cast	38	"	64 cm.	N. " " "	0.0947
Sn	38	"	"	N. " " " +10 g. $KMnO_4$	3.6160
Sn hamm'd	38	"	"	N. " " "	0.1155
Cu	38	19h	60-64 cm.	N. H_2SO_4 " "	0.0226
Cu	38	19h	"	N. " " " +10 g. $K_2Cr_2O_7$	2.8637
Cu	38	19h	"	N. " " " " " " $NaClO_3$	4.3084
Sn	38	19h	64 cm.	N. " " "	0.0373
Sn	38	19h	"	N. " " " +10 g. $K_2Cr_2O_7$	0.0171
Sn	38	19h	"	N. " " " " " " $NaClO_3$	8.3576
Ag	37.5	45h	60 cm.	N. " 190 cc.	0.0015
Ag	37.5	45h	60 cm.	N. " " " 5 cc. 30% H_2O_2	1.6953
Ag	37.5	45h	60 cm.	N. Acetic " "	0.0016
Ag	37.5	45h	60 cm.	N. " " " 5 cc. 30% H_2O_2	1.7997
Au	37.5	45h	24 cm.	N. H_2SO_4 " "	0.0017
Au	37.5	45h	24 cm.	N. " " " 5 cc. H_2O_2	0.0018
Au	37.5	45h	24 cm.	N. " " " 5 g. $NaClO_3$	0.0004
Au	37.5	45h	24 cm.	N. " " " 5 g. $KMnO_4$	0.0002
Au	37.5	45h	12 cm.	N. HCl " "	0.0008
Au	37.5	45h	12 cm.	N. " " " 5 cc. H_2O_2	0.0070
Au	37.5	45h	12 cm.	N. Acetic " "	0.0005
Au	37.5	45h	12 cm.	N. " " " 5 cc. H_2O_2	0.0005
Pt	37.5	45h	4 cm.	N. HCl " "	0.0000
Pt	37.5	45h	4 cm.	N. " " " 5 cc. H_2O_2	0.0006
Pt	37.5	45h	4 cm.	N. " " " 5 g. KNO_3	0.0002

(39) The Corrosion of Gold by various solutions has also been determined by Watts and Whipple as shown in Table II:

TABLE II.

Solution of Gold in Acids Plus Oxidizing Agents.

Acid	Temp.	Time	Oxidizer	Result
H_2SO_4 30%	90	15m.	CrO_3	Gold leaf remains
H_2SO_4 30%	70	10m.	$KMnO_4$	Gold leaf remains
H_2SO_4 30%	90	....	HNO_3	Gold leaf remains
H_2SO_4 30%	..	....	$NaNO_3$	Gold leaf remains
H_2SO_4 30%	..	....	KBr	Gold dissolved
H_2SO_4 80%	150	20m.	CrO_3	Gold remains
H_2SO_4 80%	Cold	24h.	CrO_3	Gold dissolved
$HClO_4$	80	....	HNO_3	Gold remains
$HClO_4$	95	....	$NaNO_3$	Gold remains
$HClO_4$	95	....	CrO_3	Gold dissolved
HBF_4	Hot	....	HNO_3	Gold remains
HBF_4	Hot	....	KBr	Gold dissolved
H_3PO_4	98	5m.	CrO_3	Gold remains
H_3PO_4	98	....	$NaNO_3$	Gold remains
H_3PO_4	..	....	HNO_3	Gold remains
H_3PO_4	..	....	KI	Gold slowly dissolved
H_3PO_4	..	....	KBr	Gold quickly dissolved
H_3PO_4	90	....	$KMnO_4$	Gold remains
H_3PO_4 + H_2SO_4 50%	115	....	CrO_3	Gold remains
H_3PO_4 + H_2SO_4 50%	142	....	CrO_3	Gold remains
H_3PO_4	130	30m.	CrO_3	Gold remains
H_3PO_4	Boiling	80m.	CrO_3	Gold remains
H_3PO_4	..	....	NaCl	Gold dissolved
HCl 15%	60	....	CrO_3	Gold quickly dissolved

(40) Corrosion by Caustic Soda.—The action of dilute caustic soda on tin, lead and zinc has been examined by the same authors, with the results shown in Table III:

TABLE III.

Temperature of bath 37.5 C.; Time 45 hours; Area of specimens 60 sq. cm.

Metal	Reagents used	Loss in grams
Sn	N. NaOH 190 cc	0.0302
Sn	N. NaOH " " 0.25 g. Na_3AsO_4	0.0292
Sn	N. NaOH " " 10 g. $KMnO_4$	0.6771
Sn	N. NaOH " " 10 g. KNO_3	0.0300
Pb	N. NaOH " "	0.1101
Pb	N. NaOH " " 0.25 g. Na_3AsO_4	0.1026
PbHg	N. NaOH " "	0.0850
Pb	N. NaOH " " 5 g. $KMnO_4$	0.0978
Pb	N. NaOH " " 5 g. KNO_3	0.0938
Pb	N. NaOH " " 5 g. $NaClO_3$	0.0642
Zn	N. NaOH " "	0.0363
Zn	N. NaOH " " 0.25 g. Na_3AsO_4	0.1016
ZnHg	N. NaOH " "	0.0326
Zn	N. NaOH " " 5 g. $KMnO_4$	0.3318
Zn	N. NaOH " " 5 g. KNO_3	0.7025
Zn	N. NaOH " " 5 g. $NaClO_3$	0.0856

(41) Paucity of Information.—It must be confessed that the above data are only partly satisfactory. Normal acid is entirely too dilute, and the temperatures too moderate to satisfy a man who knows much of practical requirements. We do not usually find it worth while to evaporate solutions as dilute as normal ones, nor at such low temperatures.

Watts and Whipple as well as other investigators seem to have been most concerned in determining the correctness of a theory, which is of course interesting but not highly important to people who are trying to find something to use in their work, with very limited time and library facilities. A really valuable study of corrosion is badly needed but to be valuable to the manufacturing chemist it must follow on the small scale actual working conditions.

(42) Obstacles to Publication.—Boards of Directors very often pursue the very silly policy of refusing to allow publication of information obtained in the working out of a process. The cry is that it has cost them much money and they are therefore unable to reveal it to competitors. This is true in some cases, but it is nevertheless true that many results whose publication could do no possible harm is forbidden in pursuance of a narrow policy which the directors deny in public and practice in private. As a result of this, research departments are often little better than information departments whose chief aim is to steal methods from competitors.

See also: "The Corrosion of Lead," R. H. Gaines, *Eng. Record*, June 21, 1913.

"The Relative Action of Acids on Enameled Ware," *J. Am. Cer. Soc.*, Jan., 1919 and July, 1920.

"Rate of Corrosion of Aluminum," G. H. Bailey, *J. Soc. Chem. Ind.*, May 15, 1920.

"The Action of Caustic Liquors on Steel Plates," C. E. Stromeyer, *Eng.*, Dec. 14, 1917.

"The Effects of Various Substances on the Rate of Corrosion of Iron by Sulphuric Acid," O. P. Watts, *Electrician*, July 11, 1913.

"The Corrosion of Cast Iron Reviewed," R. H. Gaines, *Iron Age*, June 5, 1913.

"Contributions to the History of Corrosion," A. Phillipps, *Eng.*, March 14, 1913.

"Experiments on the Corrosion of Iron and Steel," W. D. Richardson, *Trans. Am. Inst. Chem. Eng.*, Vol. 13, Part I, p. 169.

"Rates of Solution of Iron and Steel in Non-Oxidizing and Oxidizing Acids, *Ibid.*, p. 265.

"A Suggested Basis for an Index of Corrosion for Iron and Steel," *Ibid.*, p. 277.

"Corrosive Protective Action of Certain Colloidal Solutions," W. T. Huff, *Chem. and Met. Eng.*, Nov. 9, 1921, p. 865.

CHAPTER III.

LOCATION OF WORKS.

(43) Where a new plant is to be built the location is an important question. Many items enter into this problem. In the first place, it is desirable to have the plant located near a city of some size, so that minor supplies may be quickly obtained. This is also desirable because it is then easier to obtain and keep labor, and the heavy initial cost of company dwellings, clubs, etc., need not be met.

Where materials or articles manufactured come or go over seas, the factory should, if possible, be located on tide water so that vessels may anchor alongside the works. The same holds if they are best transported along the coast.

The plant should be so located that the raw materials may be obtained cheaply with low freight rates. In studying this part of the problem, all supplies including coal, water, gas, electricity, and most important of all, labor must be considered. Location on competing railroads is desirable, but can be obtained only in exceptional cases. Low cost of the land is a consideration which may sometimes be disregarded because of greater proximity to street car lines or other means of communication. One of the important considerations is proximity to markets.

After the location has been fixed, a topographical and profile survey should be made in order that the plans may be laid down directly on the blue prints.

(44) Laying Out of Plant.—It is desirable when possible to have the heavy substances unaffected by weather shipped in coal gondola cars, delivered on trestles, and dumped through the bottom. Two styles of car are made for this purpose. One with bottoms slanted the entire length and the other delivering only a part of the content, the remainder having to be shoveled out. The first are to be preferred when obtainable. Coal cars generally run light one way, and railroad companies will sometimes make a reduced rate when return freight is provided. Box cars require more labor in unloading.

The cheapest way to handle heavy low priced material is to locate the plant on a hillside and so arrange it that the crude material is delivered at the highest level, gradually passing to a lower as the result of each successive operation, until it reaches the warehouse whose floor should be on the level of the car floor.

Where the lay of the land permits, ore pockets may be provided under trestles. They are best made with sloping floor so as to deliver easily. They must be of such size as to hold easily not less than one carload. In low tracts of land where floods may be feared, the foundation walls of buildings are sometimes raised four feet above the surface and filled to raise the floor to that level. This brings the car floor on a level with the building floor, the car tracks being laid in wharves between the building 16 feet wide. Since the car is commonly only 8 feet wide, this seems like a waste of space. Four feet space on each side is necessary, however, for the safety of the railway employees in coupling and uncoupling. This space must not be encroached upon by stairways or other obstructions. Stairways are best built in the shipping platforms outside the buildings. Shipping platforms are best made of concrete; they should not be less than 9 feet wide. When it is necessary to provide wharves, the building should be carefully spaced so that when a second row of buildings is built, the ends may coincide, or nearly coincide, with those of the first row. If this is not looked after, it will be impossible to arrange track crossings for teams between the buildings. The shipping platforms should be covered from the weather by allowing the roofs to project over them. So far as necessary these projections may be supported by brackets fastened to the walls.

Not less than twenty feet space should be allowed between the ends of the buildings. If there are three or more rows of buildings, an occasional space of 60 feet should be allowed. This gives room for turning teams, for mixing concrete for repairs, etc.

On level ground reasonably safe from floods, the floors and railway tracks must be laid on one level and elevators and conveyors provided for transferring material from one place to another.

(45) **Railway Sidings.**—Minimum curves for standard tracks are 16 degrees for sidings and 3 degrees for main lines. Where the line is double tracked, facing point switches are not allowed.

(46) **Water Supply.**—In many operations the amount and quality of the water supplied is a matter of great importance. The water available should be carefully examined and the seasonal variations of supply and quality ascertained. Springs that dry up or are so located as to be flooded and supply only dirty water during part of the time are not satisfactory. Limy water or water loaded with organic matter may be altogether unsuitable. It is very desirable, where possible, to have an independent supply of water so located that pumping is not necessary.

(47) **Disposal of Waste.**—The disposal of waste is another serious problem. Where noxious vapors like hydrogen sulphide are likely to be liberated from the waste by accident or carelessness, works should never be located near houses nor so located that waste water will flow through thickly inhabited districts.

The disposal of solid waste is often a troublesome problem. Near or on tide water this as well as liquid waste may often be run into the ocean. Niter cake, residues from barium sulphide, calcium chloride mud with lime, and various other materials each offers a separate problem.

BUILDINGS.

The material to be used for buildings will naturally be largely determined by local conditions. In calculating, the price and freight rates are most important.

(48) **Concrete.**—A good cheap mixer for concrete is that made by the Waterloo Cement Machinery Corporation, of Waterloo, Iowa (Fig. 10). One form of this apparatus receives the materials in a scoop at the ground level, elevates and discharges into the mixer and when mixing is complete, it discharges into wheelbarrows. One of these mixers travels under its own power, climbing 20 per cent. grades; it is operated by an 8 horse-power gasoline engine. These mixers are built in sizes from 5 to 11 cubic feet per batch. Another mixer which gives good service is built by the Jaeger Machinery Co., of Columbus, Ohio. A third



Fig. 10.

mixer is made by the Municipal Engineering Co., of Chicago, Ill., etc.

(49) The Cement Gun.—The Cement Gun Co., of Allentown, Pa., claim that in order to get maximum strength the cement material must be applied at once on wetting so as to avoid disturbance after initial set begins. For this reason the mixed material is placed in a hopper and forced through a pipe by compressed air. At the moment of discharge it is properly wetted by water supplied through a special nozzle and auxiliary hose. The muzzle velocity of the material corresponds to a pressure head of 35 pounds (Fig. 11). This process is evidently specially useful for distributing cheaply thin layers of material on ceilings, walls, for building tanks, etc. It is also claimed that the material has a smaller percentage of voids and is therefore less permeable, that it has greater tensile strength and adheres better than the hand-made product.

(50) Brick.—Everything considered, brick is the best material for chemical buildings, as it is very slightly attacked by acid gases, is fireproof and usually costs little more than wood. For muriatic or nitric acid houses, it should be laid in cement. Where cranes are to be installed the walls may be strengthened by placing I beams vertically at intervals of, say 20 feet. The steel roof girders will then be riveted to the upper end. This construction makes a very attractive building but the ironwork must be carefully protected from acid fumes, by means of one or more coats of asphalt varnish. This must be watched and promptly renewed as soon as it shows signs of peeling off.



Fig. 11.—The Cement Gun.

(51) Hollow Tile have been much used recently in construction of chemical buildings. They make good buildings, are reasonable in price, and resist the attack of acids. Fig. 12.



Fig. 12.—Hollow Tile Construction.

(52) Framed Buildings of wood are much cheaper in many parts of the country. When used for acid houses they must be framed together; nailing will not answer. The timbers are to be mortised and tenoned and fastened with hickory pins. Siding is nailed on, but where much acid escapes, the nailing must be renewed from time to time. Zinc nails manufactured by the New Jersey Zinc Co., are said to last well. One of the many composition roofs now on the market seems to answer best for chemical buildings. Slate usually contains some calcium carbonate, and does not last. Flat slag and tar roofs are cheap and last well.

Good paving brick laid in sand, make about the best floors, but are expensive. Concrete floors will not stand acid. Concrete protected by a coating of boiled tar lasts well. The tar must be put on after the cement has been thoroughly dried.

(53) Foundations.—Much depends upon securing good foundations, but reliable data are nearly always hard to obtain. It is impossible, in most cases to determine with accuracy the resistance to deformation of the foundation and hence, this must be left to the judgment of the engineer. In a few cases, where heavy weights must be carried the bearing capacity must be determined. A description of the method used with the New York State Capitol at Albany will show how this may be done: A hole 3 feet deep was dug into the blue clay, 18 inches square at the top and 14 inches square at the bottom. Rows of small stakes were then driven in lines radiating from the center of the hole and the tops of the stakes carefully leveled. A timber post 12 inches square held upright by guys and with cross-staging on the top to hold the weights was placed in the holes. The level of the tops of the stakes remained unchanged until a load of 5.9 tons per square inch was applied.

(54) Safe Bearing Loads.—These are about as follows:

Hard solid rock	200 tons per square foot
Ordinary rock	20–30 tons per square foot
Hard gravel	6–10 tons per square foot
Sandy gravel	4–6 tons per square foot
Clay	3,500–4,500 lbs. per square foot

The New York building law allows for:

Soft clay	1 ton	per square foot
Ordinary clay	2 tons	per square foot
Loam, clay or fine sand	3 tons	per square foot
Coarse sand, stiff gravel or hard clay	4 tons	per square foot

A foundation should always be horizontal or stepped (Fig. 13),



Fig. 13.—Stepped Foundation.



Fig. 14.—Foundation Footing.

and where practicable should resist pressure equally throughout. Thus, it is undesirable to rest one side of a building upon solid rock and another upon hard clay, though this is sometimes unavoidable.

(55) **Footings.**—These are used to extend the area subject to compression and are especially desirable where the foundation is of doubtful rigidity. By giving the wall a greater width over the bottom surface, the weight upon unit area is decreased and likewise the danger of settling. In Fig. 14 the bottom course, usually of cement concrete, should be made so thick that no danger of fracture exists at A. The cement mass may be and often is re-enforced. It is always necessary that trenches for foundations reach below the frost line; in the latitude of New York to, say, 3 feet below the surface. If springs are encountered, drains must be provided to carry away the water. Foundation walls, being more or less porous, absorb and retain the surrounding moisture. They should extend, therefore, at least a foot above the surface so that this moisture may not be carried by capillary attraction into the wall above.

In soft ground piles must be driven. These are of wood where marine borers are not to be feared. They should be not less than 6 inches in diameter at the small end and straight. They will

sustain 10 tons and if kept under water will not rot. The *Engineering News* formula for determining the safe load is $L = 2wh(Cs + 1)$, where L = safe load in pounds, w = weight of hammer in pounds, h = fall of hammer in feet, s = penetration of last blow in inches. Piles should never be driven with centers closer than 2 feet, 3 feet is much better. Concrete piles are either (1) made in place and driven, when cushioned head must be used; (2) filled in a hollow casing which is allowed to rust, or (3) filled in a casing which is withdrawn as the filling proceeds. They will carry 30 tons each. Concrete piles usually cost three to four times as much as wood.[1]

(56) Materials for Foundations.—For chemical buildings limestone or other rock easily attacked by acids should be avoided. The best material is usually cement concrete, made of broken stone or cinders, Portland cement and sand. The proportions used vary widely. Merritt & Co.'s handbook[2] recommends the following method for determining the proportions to be used when the materials have been chosen: "The proportion of matrix should slightly exceed the voids in the aggregate, so that each particle of the latter may be entirely covered with mortar. It is, therefore, evident that the proportion of voids in the aggregate to be used in each particular case should be ascertained in order to secure the best results. This is simply done by filling a vessel of known capacity, level full, with the loose aggregate, having previously thoroughly wet the latter. Then pour in as much water as the vessel will contain, and divide the volume of the water poured in by the volume of the vessel, the quotient will represent the proportion of voids. The mixture may then be proportioned accordingly, which will not only produce a better grade concrete, but frequently effect a material saving over the common method of arbitrarily adopting one of the usual proportions, regardless of the nature of the ingredients. Proportions in common use are by volume, 1 part cement, 2 parts sand and 5 parts stone, crushed to pass a 2-inch hole and free from fine dust, and

[1] Patton's Practical Treatise on Foundations; Patton's Treatise on Civil Engineering; Cotell's Allowable Pressure on Deep Foundations; The U. S. Public Works; Reinforced Concrete by Chas. F. March; Dock Engineering by B. Cunningham.

[2] Page 63.

1 part cement, 2½ sand and 6 crushed stone. Where broken stone is not used, the following will give an idea of the proportionate amounts to be taken. These are the proportions used by the New York Rapid Transit Railway:

For brick masonry Column footing stones and rubble masonry..	1 portion Portland cement and	2 portions sand
Stone masonry	1 portion Portland cement and	2½ portions sand
Pointing	1 portion Portland cement and	1 portion sand

(57) Crushing Strength of Materials Used in Walls.—Walls are usually far stronger than is necessary. Where very heavy weights are to be carried, however, it is necessary that the engineer assure himself by calculation that they are sufficient. The following figures showing the crushing strength of materials commonly used will then be of assistance. Crushing strength of:

Brick, in lime and sand.....	8 tons per square foot
Brick, in cement.....	15 tons per square foot
Granite	75 tons per square foot
Sandstone	40 tons per square foot
Limestone	50 tons per square foot
Concrete	20 tons per square foot

(58) The Weight of Masonry in Pounds per Cu. Ft. is about as follows:[1]

Brick in mortar	100
Brick in cement.....	112
Concrete	120–155
Masonry, dry rubble	140–160
Masonry, dressed	140–180
Mortar	90–100

(59) Brick Walls.—For chemical work these should almost always be laid in cement mortar, since lime mortar is rapidly eaten

BRICK LAYING.

Fig. 15. Improper Method—daubing the corner.

Fig. 16. Proper Method—shoving up the brick.

out by acids and acid gases. The brick should not be softer than the grade known as hard-stretcher and for damp situations very hard bricks are best. Most walls should be laid solidly, without air space and conforming to ordinary dimensions will be either

[1] Kent's Pocket Book, p. 174.

8½, 13 or 17½ inches thick. Since workmen *will* add lime to cement if allowed, they must be carefully watched to prevent this and several other evil habits, which if allowed impair the strength:

(1) It is a common practice to lay the brick dry or if they are wetted, to do it imperfectly. Bricks laid wet make a much better wall. If the men complain of sore hands, gloves should be provided.

(2) It is a common practice in laying brick to spread the mortar and daub a small bit on the edge as shown in Fig. 15. This leaves a void in the wall. The proper method is shown in Fig. 16, the brick being laid flat in the mortar and pushed against the preceding brick. In this way the mortar fills the lower part of the opening, the filling being completed when the next mortar course from above is laid. This method is more expensive, because slower, but gives a better wall.



Fig. 17.—Corner Layout.



Fig. 18.—Plumb Board.

(60) Laying Out Buildings and Building Walls.—At each corner of a building to be built, stakes are strongly driven in and connected by a cross-piece on which grooves marking the inside and outside of the walls are cut (Fig. 17). Care must be taken that these are not disturbed until the walls have reached such a

height that they can be dispensed with. By measuring 8 feet on one line and 6 feet on the other and making the distance between these marks 10 feet we get a right angle. It is better where a surveyor's transit instrument is available to lay out corners and adjust levels and angles with it. The engineer in charge should insist that corners be kept perfectly plumb by application of a plumb board shown in Fig. 18. To insure accuracy, lines should be stretched on the inside and outside of the wall and the thickness be tested as often as the line is moved. Bricklayers unused to these rigid requirements are apt to grow restive and considerable tact is needed to secure compliance.

Bricks are usually laid in what is known as American bond, as shown in Fig. 19, in which every eighth course consists of headers, the intervening courses being stretcher courses as shown. In English bond there are alternate courses of headers and stretchers. Flemish bond has alternate headers and stretchers in each course, as shown in Fig. 20, and this is quite frequently used in office buildings. Here the headers may be slightly different in color to give variety. The pointing mortar used is sometimes colored to match the brick by adding iron ores; black, by adding charcoal or white by mixing lime and marble dust. Nowadays, stone masonry is little used except in foundations and retaining walls. It may sometimes be advantageously used where it is desired to dispose of excavated material. Stone with flat surfaces may be laid up rapidly by good masons. It is desirable, where much of this work is to be done, to keep a careful watch on the work done by each man, both with respect to the quantity and quality of his work, and to promptly lay off those who do not come up to the mark in either respect. Work not properly and carefully bonded should generally be torn down. Cement should be mixed in batches of moderate size and be used promptly before initial set occurs. All work of this character must be continuously watched. Illustrations of stone work with proper bonds and corners are shown in Fig. 21. Walls are often laid with brick or stone corners which must then be properly



Fig. 19.—American Bond.



Fig. 20.—Flemish Bond.



Irish Wall. —Fig. 21.— Rubble Wall

bonded as shown in Fig. 22, which also shows string courses and a window opening. This is built of Ashlar or dressed stone.

(61) **Hollow Tile** may be used for walls and floors as shown in Fig. 12a.[1] Wooden floors are laid as shown in Fig. 12b.[2] The Johnson floor system shown in Fig. 12c has been used on spans up to 25 feet. This is believed to be the strongest and lightest fire proof floor made. Segmental arch floors between I beams

[1] National Fire Proof Long Span Fire Proof Cons., p. 25, lower fig.
[2] Standard Fire Proof Cons. Nat. F. P. Co., p. 21, lower fig.

with or without tie rods which may be bare or protected may also be used. These are especially useful for long spans. The method of construction with tie rod protected is shown in Fig. 12c. The segmental arch construction makes the cheapest floor.

These blocks are laid in one part cement and three parts sand. Lime, not to exceed 10 per cent. by volume may be allowed in



Fig. 22.—Ashlar, or dressed stone wall, with string courses, (A), window opening, and brick corner.

the mortar. The stucco covering is for first coat: one cement, one-tenth lime, two sand; second coat: one cement, one-tenth lime, two and one-half sand; third coat: one cement, one-tenth lime, three sand. Before applying the first coat the surface must be wetted thoroughly and applied with force so as to form good keys. Last coat of slimes should be waterproofed.

(62) Safe Load for Hollow Tile.—A hollow tile wall or column thick enough to render danger of buckling negligible will sustain a load of 300 tons per square foot of area. With a factor of safety of five this will allow us to load to 60 tons per square foot.

(63) Pilasters are often used to strengthen a wall and to increase the bearing area under beams. When pilasters are used, the number of corners is increased and thereby the cost of laying the walls. This additional cost sometimes more than balances the brick saved. A wall built with pilasters is shown in Fig. 23.



Fig. 23.—Plan of pilaster, with bearing-plate of cast-iron, and steel floor-beam.



Fig. 24.—Elevation of 23.



Fig. 25.—Section of 23.

(64) Floors may be made of concrete, but should be supported by exposed steel beams, which must be frequently inspected and painted with asphaltum paint. Concrete makes an excellent floor except where exposed to acid laid upon the ground. The earth should first be excavated for a foot, and rammed, and a foundation of stone and cinders well rammed be first laid. Upon this, four inches of concrete and one inch of cement and sand (one cement, two sand) is spread. This must not be allowed to freeze.

For second story floors, steel or yellow pine beams well bridged may be used and as a covering, yellow pine flooring. The resin contained in this wood makes it resistant to acids and it has the advantage also of cheapness.

(65) Roofs should be laid nearly flat in most cases and covered with gravel asphalt by the Merritt system. Where composite (cement asbestos) tiles are used steel truss supports well painted may be used. Tin, slate and wooden roofs will not answer.

Fireproofing most chemical construction does not yet appear to be practicable because concrete is permeable to liquids and gases and the reinforcing steel rods might give way. This has not, however, had a sufficient test.

The tops of walls should be carried above the roofs and, when practicable, dividing walls should be without openings. The tops of walls should be covered with a coping made of overlapping tile laid in cement. Cement copings may also be used.

(66) Weight of Wood.

	Weight in lbs. per cubic foot of dry wood		Weight in lbs. per cubic foot of dry wood
Ash	39–45	Larch	35
Beech	45–46	Lignum vitæ	62
Birch	41–47	Linden	37
Cedar	31–39	Locust	42–46
Cherry	41	Mahogany	51
Chestnut	35	Maple	38–43
Cypress	29–33	Oak	45–59
Dogwood	47	Osage orange	48
Ebony	76	Pine, white	24–28
Elm	34–45	Pine, yellow	38
Fir	32–37	Poplar	29–30
Gum	37–57	Spruce	21–28
Hackberry	45	Sycamore	35–37
Hackmatack	37	Tamarack	46
Hemlock	24–26	Teak	51
Hickory	47–56	Walnut	36–38
Holly	47	Willow	34
Hornbeam	47	Redwood	26
Juniper	35		

(67) Beams and Girders.[1]—Safe load on Beams. Uniformly distributed load,

$$\text{Safe load in lbs.} = \frac{2 \times \text{breadth} \times \text{square of depth} \times A}{\text{span in feet}}$$

$$\text{breadth in inches} = \frac{\text{span in feet} \times \text{load}}{2 \times \text{square of depth} \times A}$$

The depth is taken in inches. The coefficient A is one-sixteenth the maximum fiber stress for safe loads, and is the safe load for a beam one inch square one foot span. The following values of A are given by Kidder as one-third of the breaking weight of timber of the quality used in first class buildings. The values for stones are based on a factor of safety of six.

VALUES FOR A COEFFICIENT FOR BEAMS.

Cast iron	308		
Wrought iron	666		
Steel	888		
American woods—			
Chestnut	60	Spruce	70
Hemlock	55	Poplar	65
White oak	75	Hudson River blue-stone flagging	25
Georgia yellow pine	100	Granite (average)	17
Oregon pine	90	Limestone	14
Red or Norway pine	70	Marble	17
Eastern white pine	60	Sandstone	8–11
Western white pine	65	Slate	50
California redwood	60		
Texas yellow pine	90		

[1] Kent's Mechanical Engineers Pocket Book, p. 1335.

CHAPTER IV.

INDUSTRIAL MANAGEMENT.

(68) **General Manager.**—In well managed plants of any size the works are in charge of a General Manager. The General Manager spends most of his time in the office or upon the road looking after the general interests of the concern. In some cases he also acts as purchasing agent and sells the product, depending upon the size of the plant. He attends to most of the correspondence, interviews applicants for positions, interviews members of the Board of Directors and consults with those outside the works who must be interviewed about new processes, or who have articles to sell to the concern. If he is wise he will take pains to cultivate the good will of everyone interested in the works, especially the Superintendent.

(69) **The Superintendent** has direct charge of operations and all Foremen report directly to him. He is responsible for results obtained and must see that operations are carried on with economy of time and materials and that waste is avoided. He is continually making the rounds of the plant to see that everything runs smoothly or if not to find and apply the proper remedy. He should know every workman by name and be acquainted with his family and his personal peculiarities. A good Superintendent will have the warm co-operation of his men; they will often work overtime for him without grumbling, and this spirit will do more to promote efficiency than any other one thing. Unless his interest in the men is genuine they will detect the counterfeiting. A good Superintendent must be born with the right qualities and then cultivate them assiduously in order to succeed.

(70) **The Foreman** has direct charge of one operation. He is responsible to the superintendent only. He should be humane and considerate with the men under his charge, fill out and return promptly all blank forms required by the management, see that the materials and time belonging to the company are not wasted and be on the watch to see that improvements in methods be suggested and carried into execution. These qualities are very sel-

dom found in one man. The filling of such positions with men who are competent is one of the most difficult problems of the management and upon its proper solution depends, to a large degree, the success of the establishment.

(71) **Chief Chemist.**—In chemical works the position of Chief Chemist is a difficult one to fill properly, and is of great importance. In small plants he must oversee quality of material and product as well as research work having in view improvement of quality or quantity or both. In large plants these functions must be divided and sometimes subdivided. The reports of quality should be made to the superintendent and of research to the general manager. In doubtful cases the chemist should insist that positive orders on these points be given. He must not interfere in any way between the men and their work; even in drawing samples it is best to consult foremen or superintendent. Small jealousies are almost everywhere latent and care must be taken not to arouse them. Unless his work be of great accuracy and precision he cannot long command the confidence of his superiors.

(72) **The Men** for continuous service must be carefully selected by elimination, and it is well to put a premium upon length of service. Depending upon the character of the help obtainable, it is sometimes desirable to withhold a small sum to cover depredations. This must be done by a contract signed at the time of employment. In all cases employees must be treated justly and kindly, and this irrespective of the response obtained. Any other course is very bad policy, to say the least.

(73) **Reports.**—Where two or more shifts are working each shift will have a different foreman, who must make a daily report to the office upon forms provided for the purpose. The superintendent must see that these are properly and promptly made out and handed in, first being careful to see that each foreman understands clearly what is wanted. Repeated neglect or refusal to do this work as directed must be punished promptly. These forms should be as simple as possible; complications of any kind are to be avoided as most foremen have very limited education. Two such forms are inserted here as suggestions. They must of course differ for different operations:

Nitric Acid House No. .....

Date ..... Shift ..... Foreman ..... Retort .....

Niter used	66° used	Acid obt'd		Niter cake	Time begun	Time ended	Total hours	Men	Remarks
		Strong	Weak						

Saltpeter House No. .....

Date ..... Shift ..... Foreman .....

Soda used	Potash used	Saltpeter used	Salt made	Men working	Total hours	Remarks

(74) Business Economics.[1]—There is a strong tendency in most businesses toward over-organization. By this is meant that there is a tendency to make the overhead charge heavier than the business is capable of supporting. It is often very nice to be able to say that the cost of this, that and the other is exactly so much, sometimes, indeed, it is necessary; but it is well to remember at all times that information costs money in one way or another, and that the object of the business is the production of dividends. For this reason overhead charges of all kinds must be carefully guarded, and the question continually asked: Is this innovation going to cost more than it will produce? New processes must be carefully threshed out before being put into operation, with all the factors of cost, quality, selling probabilities, and probable disposal points and freights worked out before any attempt is made to design apparatus or plant. It is nearly certain that two years will elapse between initial plant and dividend, and in many cases this period is longer.

[1] See also Industrial Leadership and the Manager by Sam Lewisohn, in *Atlantic Monthly*, Sept., 1920, p. 414.

CHAPTER V.

BOILERS.[1]

A great variety is to be found in boilers in actual use depending upon the water and the fuel available. Where fuel is cheap, boilers with few tubes are used and this is also necessary in some cases where the water scales badly. Three types will be described here:

(75) Internally Fired Upright Tubular Boilers.—These are generally used for small power and are constructed as shown in Fig. 26. The upper ends of the fire tubes, which are usually about two inches in diameter, project into the steam space and as a result the steam is slightly superheated. The tubes of this and other boilers are expanded into the crown and top sheets by means of an expanding tool, as shown in Fig. 27. Such boilers are much used by contractors and are often mounted on wheels with engine and pump attached. Upright boilers may be had from 24-54 inches diameter, 4-10 feet high and with a rated horse-power of 4-60.

(76) Horizontal Tubular Boilers.—Where fuel is cheap, single tube boilers like the Cornish (Fig. 30), or Galloway boilers (Fig. 31) may be used. With higher priced fuel for moderate sized installations some form of locomotive boiler is preferred.

A multiple fire tube boiler with furnace is shown in Fig. 28 and 29. They have 3- or 4-inch tubes, a diameter of 37-72 inches and a length of 8-20 feet, and a horse-power capacity of 15-200. In this boiler the products of combustion pass under the boiler from left to right, then through the tubes right to left, and then back over the boiler to the chimney. The man-holes shown are for cleaning and are 11x15 inches. Detail shown in Figs. 31 and 33. The best grate for hand firing is the herring bone shown in Fig. 34, and as applied to an upright boiler in Fig. 35. Figs. 36 and 37 show boiler settings and a furnace door. These doors are sometimes made with water jackets.

[1] Barr, Boilers and Furnaces; Hutton, Mechanical Engineering of Steam Power Plants, Steam, Its Generation and Use, and The Stirling Water Tube Boiler, published by the Babcock and Wilcox Co.

UPRIGHT BOILER.



Fig. 26.

A. Hand-hole for cleaning.
B. Water Gage.
C. Pressure Gage.
D. Hood.
E. Water line.
F. Safety-valve.
G. Grate.
H. Crown-sheet.
I. Fire-door.



Fig. 27.—Boiler tube expanded into top sheet and upset.



Fig. 28.—Horizontal Boiler.



Fig. 29.

A.A. Cast-iron lugs to support boiler.
C.C. Man-holes.
D. Cast-iron plate.
B. Steam dome.
E. Grate.

THE CORNISH BOILER.



Longitudinal Section A-A.



END VIEW

Principal Dimensions:

Diameter of shell	3'-6" to 6'-0"
Length	8'-0" to 22'-0"
Diameter of flue	2'-2" to 3'-6"

The Cornish Boiler consists of an outer shell within which is a flue of sufficient size to permit its being fitted with a furnace for the combustion of the fuel. The gases from the combustion chamber leave the flue at the rear, divide and return along the sides of the boiler to the front where they reunite and pass through a flue under the boiler to the rear of the shell and into the chimney.

THE ADAMSON JOINT.



THE ADAMSON FLANGED SEAM.

This seam insures sufficient longitudinal flexibility to prevent destructive strains within the boiler and the flanged ring makes it more able to resist collapse.

Fig. 30.

THE GALLOWAY AND LANCASHIRE BOILERS.



THE GALLOWAY BOILER.
Longitudinal Section.

The Galloway Boiler is fitted with two furnaces merging into a segmental combustion chamber. This chamber is fitted with tapered water-tubes which increase the effective heating surface, promote a better circulation of the water, and act as stays, thus greatly adding to the strength of the flue.



GALLOWAY BOILER.
End View.

THE LANCASHIRE BOILER.

This boiler is similar to the Cornish type, except that it is fitted with two furnaces and two flues. Thus lateral rigidity and stiffness are secured.

LANCASHIRE BOILER.
End View.

Fig. 31.



Fig. 32.—Detail of Fig. 28.
C. Man-hole. F. Boiler tubes.



Fig. 33.—Boiler Setting.
A. Cast-iron lugs supported by rollers on cast-iron plate D.



Fig. 34.—Herring bone grate.



Fig. 35.—Herring bone grate for upright boiler.



Fig. 36.—Boiler setting.

AA. Boiler doors. C. Fire door.
B. End of boiler. D. Ash door.



Fig. 37.—Furnace door.

(77) **Water Tube Boilers** of which the Babcock and Wilcox is shown in Fig. 38. This consists of a series of 4-inch seamless steel tubes expanded into serpentine shaped cast iron or wrought steel headers according to the pressure to be carried. A header is shown in Fig. 39 and in detail in Fig. 41. Proper circulation in such boilers is essential both for safety and economy. These boilers have one or more longitudinal or cross drums above the tubes and a small mud drum below and in the rear. They are specially fitted for high pressures.

Boilers are tested under hydraulic pressure and the strain put upon them should never be allowed to exceed more than half the tested limit. They should be inspected after running 1000 hours and tested whenever this seems necessary, especially after having been used for some time or after extensive repairs. A good boiler will evaporate 10 pounds water for every pound of fuel burned and sometimes exceed this, depending upon the quality of the fuel and the skill of the firemen. Boilers are rated at 1 H. P. per 10 sq. ft. of heating surface.

Fig. 42 shows the water gage and gage cocks. Fig. 43 shows detail of the glass gage and Fig. 44 of the gage cocks.

Boilers are also provided with a steam gage, shown in Fig. 45, and a safety gage in which the safety valve is held down by a weighted lever as shown in Fig. 46, or by a spring, as shown in Fig. 47. Check valves (Fig. 48) are inserted in the feed water pipe to prevent the water being forced back by the steam pressure, and blow-off valves (Fig. 49) are provided to allow the removal of mud and scale. Some of the necessary qualifications of a boiler are as follows:

1. The boiler must have sufficient capacity for the work to be done so that neither the supply of steam nor its pressure shall fluctuate seriously. At the same time the water may be kept at constant level.

2. Enough surface to the water so that foaming need not occur.

3. Thorough circulation. Water is a poor conductor of heat and good circulation spells economy in coal, and prevents local over-heating which injures the metal; it also reduces boiler incrustations.



Fig. 38.—Water Tube Boiler.
A. Drum. B. Tubes. C. Mud drum. D. Combustion Chamber.
E. Headers. F. Deflector. G. Blow Off.



Fig. 39.—Detail showing position of Drum and Headers.



Fig. 40.—Detail showing Front of Drum and Headers.



Fig. 41.—Detail of Hand Hole in Headers.



Fig. 45.
Steam Gage with Siphon.



Fig. 46.—Combined Safety and Stop Valve.
A. Lever. B. Weight.
C. Valve.



Fig. 48.—Check-Valve.



Fig. 47.—Safety Valve.
A. Lever. B. Spring. C. Case



Fig. 49.—Plug-cock.

4. A combustion chamber where the gases attain high temperature ensuring freedom from smoke and maximum economy. A brick lined combustion chamber with step or Siemens grate or automatic stokers is best for large boilers burning bituminous coal.

Water tube boilers are best for economy, since they present a large heating surface and are less liable to cause serious explosions, but they cost more. The chief cause of scale in boilers is either calcium carbonate or sulphate or both. The substances mostly used in purifying and softening water for boiler purposes are lime, soda ash and tribasic sodium phosphate. Concerns are now in existence which analyze boiler water and furnish mixtures of chemicals guaranteed to stop scaling. Magnesium chloride is a very troublesome constituent of boiler water, as it is apt to cause pitting. As the dissolved substance in water remains in the boiler, such residues soon contain a concentrated solution of dissolved salts; boilers in constant operation should, therefore, be blown off at least once a week and frequently oftener depending upon the purity of the water supply. To blow off the fire is drawn and the plug cock opened. The pressure of the steam will drive the water and loose scale from the boiler.

The feed water may, in small boilers, be supplied by means of injectors; but these are apt to be troublesome, since small pieces of refuse will clog them. It is more expensive, but much more satisfactory and in the long run probably cheaper, to install a direct acting steam pump. This should not be one of the smallest sizes made, which not only look but often act like a toy. For gritty feed water plunger (Fig. 50), and for ordinary clear water the Worthington piston pump, shown in Fig. 51, is well adapted.

It is worth considering whether it may not, in some instances, be desirable to use forced draft fans actuated by electric motors for supplying air to boilers? Such positive regulation, while adding to the cost of operation, is economical of coal since the draft is under complete control and the amount of air passing through the fuel may be so regulated as to supply just the amount of oxygen needed for complete combustion. Operating in this way the cost of tall chimneys may often be avoided. A carbon dioxide analyzer installed in the flue and a bonus paid to firemen often bring good results.



Fig. 50.—Worthington Pump. Plunger and Ring Pattern.





Fig 51.—Worthington Pump. Piston Pattern.



(78) Surface Combustion Boilers.—Bone has shown[1] that gas and air mixed in proper proportions and burned in contact with refractory materials give an almost flameless combustion and produce a large amount of radiant heat. This radiant heat is rapidly and almost completely absorbed by metal surfaces, such as occur in ordinary boilers. Boilers constructed on this principle have been introduced which give very high efficiency and very rapid rates of evaporation. The most recent discussion of this boiler is contained in "Coal and Its Scientific Uses," London, 1919, to which the reader is referred.

(79) Heat Transmission in Boilers.—The heat transmitted through the tube of a boiler is of three sorts: (1) radiant heat, (2) conducted heat and (3) heat of convection. The radiant heat is greatest in amount when flameless combustion is produced [see (78)]. The amount of heat conducted is greatly decreased by the formation of a "dead film" of gas on the one side and a similar film of water on the other side of the boiler tube. These films greatly decrease the conductivity and are the cause of heavy loss; their effect is best decreased by a high velocity of the gas on one side and of water on the other. This rapid motion also greatly increases the absorption of heat due to convection.

(80) Composition and Temperature of Chimney Gases.—Bone has calculated that 1 pound of a coal containing 80 per cent. C, 5.5 per cent. H, 1 per cent. S, 1½ per cent. N, 5 per cent. O and 7 per cent. ash will require 135.2 cu. ft. of dry air, and the cooled products will contain 18.25 per cent. CO_2.

Kershaw and Booth have shown that with chimney temperatures of 600° F. = 315° C., the heat losses correspond to the following percentages of carbon dioxide in the gases:

Percentage of CO_2 in chimney gas	Percentage of chimney losses due to sensible heat of burnt products and excess of air at 315° C.
12	17.1
10	20.2
8	24.0
6	32.8
5	40.0

[1] Bone, *Proc. Amer. Gas Inst.*, VI, 565; *J. Frank. Inst.*, 178, 161; *Ber. der Deutsch. Chem. Ges.*, 46, 5.

It is, therefore, evident that the chemical engineer should see that the boiler plant is provided with a carbon dioxide recorder, and that an occasional check should be made of its indications by means of an Orsat's apparatus. In addition, a continuous record of chimney temperatures must be kept. A graphical method for showing results obtained has been devised by Howarth (*J. Soc. Chem. Ind.*, **39**, 329T).

(81) **Radiation.**—With the greatly increased fuel cost of recent years the necessity of decreased radiation losses has also increased. For steam and other pipe and for boilers this has long been provided for by asbestos, magnesium carbonate and other insulating coverings. The use of Sil-o-cel brick for preventing furnace radiation is a more modern development. This material is almost pure silica with great porosity, well fitted for this purpose. It has been much used for coverings for the electric furnace, and for other furnaces with lesser temperature range. It comes in the form of brick with a proper cementing material to be used as a mortar.

CHAPTER VI.

PRIME MOVERS.

The source of power may be either a water wheel or turbine, steam or gas engine or electric motor. The latter is indeed not a prime mover since the current is usually produced by one or the other of the two first named.

(82) The Steam Engine.—When steam under pressure is admitted behind a piston (Fig. 52), the piston is driven before it until the other end of the cylinder is reached. By means of the piston rod working through the stuffing box, C, and attached to the cross-head, D, and connecting rod, E, this motion is communicated to the fly wheel, F. If at the end of the stroke, the supply of steam is cut off and another port opened into the air, the momentum of the wheel, F, will carry the piston back to its original position when steam may be again admitted.

(1) The above described engine is a SINGLE-ACTING, NON-CONDENSING ENGINE. If the steam escaping from the cylinder is passed into a vacuum chamber cooled by a water spray, we have a

(2) SINGLE ACTING CONDENSING ENGINE. If the steam is applied alternately to either end of the piston, we have, if the exhaust steam escapes into the air, a

(3) DOUBLE ACTING NON-CONDENSING ENGINE, and if into a cooled vacuum, a

(4) DOUBLE ACTING CONDENSING ENGINE. In this engine the working parts are actuated by an eccentric on the main shaft, and serve to allow the steam to enter and escape at the proper moment automatically. This is illustrated in Fig. 53.

(83) Expansive Working.—When high pressure steam is used it is not necessary to allow steam to enter during the entire stroke. By adjusting the slide valve, the supply may be cut off during any part of the stroke, and the expansive action of the steam will carry the piston to the end of the cylinder. In this case, however, the pressure in the cylinder must decrease after the steam is cut off. The horse-power of a given engine is always less when it works expansively and the economy of steam greater.



Fig. 52.—Steam Engine.

A. Piston.
B. Piston Rod.
C. Stuffing Box.
D. Crosshead.
E. Connecting Rod.
F. Fly Wheel.
G. Eccentric.
H. Packing Rings.
I. Oil Guard.



Fig. 53.—Slide Valve.

A. Left Port.
B. Right Port.
C-D. Lugs on Valve.
E. Exhaust Port.
F. Rod.
G. Piston.



Fig. 54.—Crosby Indicator.

A. Cap.
B. Linkage.
C. Cord.
D. Drum.
E. Spiral Spring.
F. Piston.
T. Thread.

(84) Horse Power.—This is a unit devised by James Watt, the inventor of the steam engine, to measure its performance in terms comparable to that of the source of power then most commonly used. As Boulton & Watt manufactured engines, they desired that the unit should be fully equal to the performance of a powerful horse. It was found that a heavy draft horse could do work corresponding to the lifting of 33,000 pounds one foot in one minute, and this was the unit chosen. The French unit "force de cheval" = 0.95363 English horse-power or one English horse-power = 1.0163 "force de cheval."

Horse power[1]	Eng. ft. lbs. per minute	French kil. meter per minute	Austrian ft. lbs. per minute
English and American...	33,000	4,572.9	25,774
French	32,4704	4,500	24,561
Austrian	33,1342	4,5495	25,800

One kilowatt hour = 1.34 H. P. One English H. P. = 746 watts.

(85) The Work Done By an Engine[2] is equal to the area of the piston in square inches multiplied by the mean effective pressure per square inch multiplied by the length of the stroke in feet multiplied by the number of strokes per minute.

(86) Heat and Work.—Joule, and later Rowland, have determined that the amount of heat produced by 778 foot-pounds is equal to the amount of heat required to raise one pound of water at 39° F. to 40° F. or the British thermal unit. This theoretical relation is never attained in practice.

(87) Indicator Diagrams.—If we call the pressure on the piston P, the length of stroke L, the area of the piston A, the number of strokes per minute N, then PLAN will be the work performed and $\frac{PLAN}{33,000} = H.P.$ In any one engine working normally L and A are fixed and, if the pressure in the boiler does not vary rapidly, N will be nearly a constant. During each stroke, however, P may change rapidly and a very clear idea of the engine's performance may therefore be obtained by a study of indicator cards.

[1] From Hutton.

[2] Ganot's Physics, Section 482.

(88) The Indicator Piston invented by James Watt and shown in Fig. 54, is put into free communication with the engine cylinder by means of the thread T, so that variations in the pressure as well as the motion of the piston are recorded on the cylinder covered with paper. The area of the diagram obtained in this case represents the actual work done at each stroke and the form, to the practical eye, is a sufficient measure of the efficiency of the engine. Fig. 55 shows such an indicator diagram. This may be divided into a number of equal parts by drawing perpendiculars through it. The average height of each part which is determined by a perpendicular through the center is measured; the total divided by the number gives the average pressure which, multiplied by the area of the piston, length of stroke and number of strokes per minute gives the work done.

(89) Economy of the Engine.—The British Thermal Units evolved in the burning of a pound of average coal are, say, 12,000. The theoretical equivalent of 1 horse-power hour in British thermal units equals $\frac{33{,}000 \times 60}{778} = 2545$. One pound of coal should, therefore, produce about 5 horse-power hours. The usual consumption of coal is from 1.25 to 3 pounds per horse-power hour so that only about one-sixth to one-fourteenth of the theory, say 17 to 7 per cent., is attained in practice.[1]

(90) The Piston.—A modern form of piston is shown in Fig. 56, which shows the connection with the piston rod and the piston rings. These are made of steel and are divided by the cut shown in Fig. 57 or 58, that they may spring against the cylinder when in use so as to make a steam tight joint. This is further ensured by so placing the joints on the piston head that the small leak through the first ring is opposite a solid portion of the second ring.

(91) The Stuffing Box.—This is made as shown in Fig. 59, and properly packed. Its operation is understood by inspection of the drawing.

[1] See also an article by Alex. Dow, *Trans. Amer. Electrochem. Soc.*, 32, 65, 1917.



Fig. 55.

a. The steam is expanded about seven times and as the engine is a condensing one the back pressure is about 5 pounds, the pressure during admission being about 75 pounds.

b. A non-condensing engine, the back pressure being slightly above atmospheric, here the steam is cut off at about ¾ of the stroke.



Fig. 56.—Steel-plate Piston.



Fig. 57.—Piston Ring.



Fig. 58.—Piston Ring.



Fig. 59.—Packing Box.





Fig. 60.—Cross Head.



Fig. 61.
Connecting Rod.



Fig. 62.—Governor.

(92) The Cross Head and Connecting Rod with pin to take up lost motion are shown in Figs. 60 and 61.

(93) The Governor.—If an engine subjected to a varying load is left to itself when the load is removed, the speed will increase and become so rapid as to result in its destruction. Watt's governor had the form shown in Fig. 62 in which the shaft is revolved. As the speed increases the balls fly out and raise the collar which cuts off steam through a series of adjustable levers YZ. Governors in which springs are used and shaft governors fastened to the flywheel have taken the place of this early, imperfect apparatus.

Many matters of great importance in connection with the steam engine cannot be treated here. It will be necessary for the student to consult special treatises for such subjects as compound engines, the Corliss trip valve and the steam turbine.

THE GAS ENGINE.[1]

(94) With the development of the automobile, the gas or vapor engine has become of commercial importance. The gas engine is a much more economical machine for many purposes than the steam engine and this has led to its introduction as rapidly as the various mechanical difficulties could be met and overcome. Within recent years large engines working on blast furnace gases have been used. A modern form of isolated power plant working on producer gas is shown in Figs. 63 and 64, with details in Figs. 65-70. The type of engine here shown is the three cylinder or marine type. Plants up to 150 horse-power and over are now of frequent occurrence and give a duty of three-fourths pound of coal to 1 B. H. P.

(95) The Diesel Engine.—The familiar experiment in physics, in which a little tinder in the end of a piston barrel is ignited by rapidly compressing and so heating the contained air to the ignition point, is the central idea of the Diesel engine. The pressure may be as high as 900 or as low as 300 pounds. The fuel may be almost any inflammable liquid which is injected as a fine

[1] See Hutton, The Gas Engine, and Carpenter & Diedrich's Internal Combustion Engines.



Fig. 63.—Reeves Producer.



Fig. 64.—Sectional Elevation of Suction Gas Producer and Gas Engine.

A. Gas Generator.
B. Evaporator.
C. Scrubber.
D. Receiver.
E. Gas Engine.
F. Automatic Continuous Feed.
G. Coke resting on a Grating.
H. Exhaust Manifold.
K. Mixing Chamber.—Air and Gas.
L. Water Spray.



Fig. 66.—Vertical Section of Gas Engine.

42A. Piston Bushing.
43A. Cross Head Wedge.
75. Relief Valve.
76. Cylinder Head.
77. Cylinder Cover.
78. Exhaust Manifold.
79. Water Entrance Plate.
80. Relief Cam Lever.
81. Relief Cam Lever Quadrant.
82. Relief Cam Shifter.
83. Subbase Cover.
84. Center Bearing Adjusting Bolt.
85. Center Bearing Wedge Bolt.
86. Gas Manifold.
87. Mixing Valve Chamber.



Fig. 67.—Gas Engine Governor Mechanism.



Fig. 68.—Successive Stages of the Four Cycle Gas Engine Method.



Fig. 69.—Igniter Gear for Three Cylinder Four Cycle Gas Engine.

34K. Igniter Gear Body.
34M. Extension Coupling.
34N. Igniter Trip Rod.
34P. Trip Rod Spring.
34Q. Trip Rod Guide Nut.
34R. Igniter Pinion.
34S. Igniter Gear.
34T. Gear Housing.
34V. Gear Pin.
34W. Gear Cover.
34X. Trip Rod Cams.
71A. Governor Shaft.



Fig. 70.—Igniter Body.—Make and Break Igniter.

34. Igniter Body.
34A. Moveable Electrode.
34B. Stationary Electrode.
34C. Igniter Pawl.
34D. Electrode Spring.
34E. Electrode Nut.
34F. Insulation.
34G. Point of Contact.
34H. Bushings.
34N. Igniter Trip Rod.

spray at the proper moment. With the heavy oils commonly used, the ignition is followed by a slow explosion which imparts a much less violent blow to the piston than in a gasoline engine. The cost of operating, with crude petroleum and gasoline at present prices, is about one-third that of a gasoline engine. The first cost of such engines is very heavy because of the number of parts, the exact fitting necessary and the high pressures to be withstood. Quite recently small engines of this type, moderately priced, have been sold and efforts are now being made to so simplify the engine that the cost may be reduced to a more moderate figure.

(96) **A New Variable-Speed Power-Transmission System** is described in *Chem. and Met. Eng.* for Nov. 2, 1921, as this edition goes to press. Since an apparatus of this sort is often needed attention is here called to it.

CHAPTER VII.

PLUMBING.

The ordinary fittings for steel and wrought iron pipe are shown on Fig. 71. In fitting such pipes for carrying chemical solutions, elbows and couplings should be made as nearly as possible of the same material as the pipe line, otherwise corrosion will occur. The tools for cutting and threading pipe are shown in Figs. 72-77.

(97) **Lead Pipe** is frequently used for conveying liquids and gases; acid tanks are lined with lead for acid storage. The pipe lengths are connected by wipe joints if of small diameter. If of large diameter the sheets of lead are melted with a hand blowpipe fed with hydrogen and air under pressure. Where vertical joints must be made, as in large tanks, the lead burner begins by applying the flame at the bottom and proceeding upward. The surface of such a seam consists of small droplets of melted and solidified lead running the length of the seam. Lead burners acquire great skill and command high wages. Because of this and the heavy first cost of the metal, lead work is expensive. Sheet lead is quoted as 3 lb., 10 lb., etc., = lbs. per sq. ft.

(98) **Stoneware Pipe** made of salt glazed stoneware is very often used. For nitric acid under a moderate head cylindrical sockets are used. These are connected using a plastic, acid proof cement. Where the pressure is greater the taper flange illustrated in Fig. 79 is used, the sections being joined together by means of split taper collars, shown in Fig. 80. The flanges are ground and are assembled with a gasket of asbestos soaked in silicate of soda or molten paraffin wax. These joints are good for pressures up to 60 pounds. Where the pipe line is exposed to a great range of temperature or rough usage it may be enclosed in a cast-iron shell as shown in Fig. 81.

For muriatic acid the same piping is used but for the cement one having an asphalt base is used and for the flanged pipe rubber gaskets or rubber sleeve connections, Fig. 78, are substituted.

PIPE FITTINGS



American Standard Pipe										
Size in Ins	1/8	1/4	3/8	1/2	3/4	1	1 1/4	1 1/2	2	2 1/2
Thds per In.	21	18	18	14	14	11 1/2	11 1/2	11 1/2	11 1/2	8
Size in Ins	3	3 1/2	4	4 1/2	5	6	7	8	9	10
Thds per In	8	8	8	8	8	8	8	8	8	8

Fig. 71.



Fig. 72.—Tap Wrench



Fig. 73.—Pipe Tap.



Fig. 74.—Pipe Union.

Fig. 75.—Pipe Cutter.

Fig. 76.—Pipe Threader.



Fig. 77.—Pipe Wrench.

STONEWARE LINING.—For Use in Copper Mantles.



	Inches I.	II.	III.	IV.
Outside Diameter of Supporting Rings	6¾	16	17	21¾
Diameter of Sieve	5¾	15	16	20
Height of Supporting Rings	4¾	4¾	4¾	4¾



	Inches I.	II.	III.
Outside Diameter of Supporting Rings	16¾	17¾	19¾
Diameter of Sieve	14¾	16¾	17¾
Height of Supporting Rings	4¾	4¾	4¾

STONEWARE PIPE CONNECTIONS.



STONEWARE STOPCOCK.

Inside Diameter—Inches . . . . . ⅜ ¾ 1 1¼ 1½ 2 2½ 2¾ 3½ 3½ 4 4¾



Fig. 78.

Fig. 79.

Fig. 80.



Fig. 81.

For the first few months such lines must be carefully watched, and if the sockets leak they must be cleaned and filled again. Asbestos gaskets have to be replaced occasionally, as well as rubber sleeves. Lines up to 4, 6 or even 8 inches diameter are used. For small lines under 1 inch heavy glass tubing is preferred, and this is preferred to fused silica which is more easily broken. For making impervious joints the Harbison Walker Co. furnish a so-called "Duro" cement which gives good service.

(99) **Silica Tubing** has been proposed for conveying liquids. It is very durable, stands rapid changes of temperature and may be had up to 12 inches in diameter. It is fragile and expensive.

CHAPTER VIII.

PUMPS.

(100) **The Blow-case,** or Acid Egg as it is commonly called is the apparatus most commonly used for elevating acid liquids. It is operated by compressed air. The liquid is admitted through the stop-cock shown at the right of Fig. 82. This is then closed and compressed air admitted through the tubulure on the left. The pressure forces the liquid through the middle tube. A socket for pressure gage is shown on the left of this central tube. This apparatus is made of stoneware by the General Ceramics Co. in sizes from 15 to 525 gallons. Up to and including 80 gallons the vessels are spherical; above that they are ellipsoidal. Where heavy pressures are necessary these vessels may be armored as shown in Fig. 83.

Fig. 82.

Fig. 83.

(101) **The Plath Acid Elevator** operates on the same principle but is automatic in operation. This is also made in stoneware and is shown in Fig. 84. "The operating device consists merely of an accurately ground hollow stoneware ball which has an apparent specific gravity less than 1.0 and will therefore float in practi-



Fig. 84.

cally all the ordinary acids. This ball moves freely in a cylinder provided with an upper and lower valve seat ground to fit the ball. When the apparatus is empty the ball rests on the lower seat and by its weight closes the small compressed air inlet. The liquid enters through a check valve (on the right of the illustration) and fills the apparatus to the level of the large ball which then floats up to the upper valve seat at the same time releasing the compressed air supply. The pressure closes the check valve on the inlet side and also keeps the large ball tight against the upper seat, forcing the liquid up the discharge pipe. Part of this liquid fills the branch pipe leading to the upper valve seat. When the contents of the apparatus have been discharged the air passes up the discharge pipe, relieving the pressure and allowing the ball to drop again on to the lower valve seat thus cutting off the compressed air supply. The weight of the small column of liquid in the

branch pipe above the upper valve seat accelerates this movement of the ball. The pressure in the apparatus now having been removed, the acid is again free to enter through the check valve and the operation is repeated until the supply of acid or air is cut off."

The great disadvantage of an apparatus such as those described in the preceding sections is that when the acid has been forced out of the blow case and the air follows it, the released air coming over is accompanied by a shower of acid in drops which are thrown in all directions around the exit pipe so that it becomes necessary to provide a catch box to do away with this nuisance. It is evident that when large quantities of liquid are to be moved blow cases of steel or iron lined with lead may be used instead of stoneware. In most cases blow cases are buried in the earth but this is perhaps a bad plan since large quantities of acid may escape before being detected.

(102) The Air Lift.—If a tube be sunk in a column of liquid, the liquid will of course rise to the same level inside the tube as



Fig. 85.—Air Lift.

in the column of liquid outside; but if by means of another tube we cause bubbles of air to pass into the inside tube we shall soon

have a tube containing small sections or plugs of liquid separated by bubbles of air. The mean density of the fluids in the inside tube will now be much less than before and the column will rise to a corresponding height in the inside tube. If we provide an overflow at or near the top of this column and continue to pass up air we shall have a pump transferring a liquid from a lower to a higher level. This is the principle of the air lift. Apparatus of this kind is evidently applicable in the chemical industries and has been recently introduced to a considerable extent.[1]

(103) Jet Pumps may be actuated by compressed air, by water or by steam. The most common form is that of the steam injector used for feeding boilers. In this case it gives a high efficiency; but injectors can hardly be considered economical for a variety of reasons. Ejectors for transferring liquids to a higher level are frequently used. If actuated by steam the liquid elevated is increased in bulk by the condensed steam.



1. Steam Nozzle.
2. Combining Tube.
3. Feed Water Entrance.
4. Delivery Tube.

Fig. 86.—Injector.

(104) Pulsometers are used for transferring muddy and sandy water or other turbid liquid to a level only a little higher. They



Fig. 87.—Pulsometer.

[1] On this subject I am indebted to the Ingersoll Rand Co. for information. See also *Eng. and Min. J.*, 112, 806, Nov. 19, 1921.

are not well adapted to high lifts. In excavating for foundation work they are of great value because they can be hung from a beam and rapidly transferred to a new location. They should not be used to elevate for more than 20 feet by suction or pressure. They are of low efficiency.

(105) **Plunger and Piston Pumps** have been illustrated in Figs. 50 and 51. They may be either wet or dry pumps, *i. e.*, they may either be used to pump such liquids as do not corrode or they may be used to compress air which in turn is used for forcing liquids to a higher level by means of a blow case. Plunger pumps of stoneware are used for raising moderate amounts of liquid. The one shown in Fig. 88 is by the General Ceramics Co. The valves are stoneware balls accurately ground to fit.



Fig. 88.

(108) Centrifugal Pumps for raising large quantities of acid liquids to moderate elevations are used. One made of stoneware by the General Ceramics Co. is shown in Fig. 89. The impeller is of stoneware. It is better to place such pumps at a level slightly lower than the liquid to be raised.

CHAPTER IX.

CRUSHING.

(107) The coarse crushing of hard materials, such as quartz, limestone, feldspar, barytes, fluorspar, etc., is usually effected by means of some form of so-called rock breaker or crusher. The material to be crushed must, of course, be of such size that it can pass between the jaws of the crusher. If very large amounts of material are to be crushed it will pay to build very large crushers, so that large pieces may be taken into the jaws, but if smaller quantities only are needed, it will sometimes pay best to give the preliminary crushing by means of sledges. It is quite impossible to effect complete grinding of such material in one operation. The material must first be coarsely crushed. It should then be finely crushed and then ground to the size of powder wanted.

In all grinding problems it is first necessary to know exactly what is to be done, in order that an economical layout may be arranged. If only a few tons a day are to be crushed, the arrangement will be vastly different from that to be employed if many hundreds or thousands of tons are wanted. Where large capacity is needed, an expensive installation pays large dividends.

The wear and tear caused by materials being crushed vary greatly with their nature, but in general the wear on crushers is very heavy.

The substances to be crushed may be classed as follows, according to their hardness:

1. Soapstone and talc.
2. Rock salt, gypsum, graphite, soft coal.
3. Calcite, burnt lime, marble, chalk, barytes, soft limestone.
4. Fluorite, magnetite, soft phosphate, dolomite.
5. Apatite, hard phosphate, hard limestone, chromite.
6. Feldspar, magnetite, hornblende.
7. Quartz, granite, sandstone.

The machines used for this crushing may be divided as follows: First, the dry grinding, consisting of crushers, rolls and tube mills; second, the wet grinding, consisting of stamps, ball and tube mills.

(108) "Jaw crushers are built in a number of designs, but in all standard machines the jaw action or motion is identical, although there are several ways of transmitting this motion to the crushing members. The Blake design uses the Pitman construction which is probably the oldest mechanism and is a good machine to-day. During the last fifteen years, however, cam and roll crushers have entered the market and are rapidly replacing the Blake type."

(109) **The Blake Crusher.**—This crusher has an eccentric shaft with bearing surfaces above and below which are adjustable to take up wear. The motion is transmitted to the swing or moving jaws by toggles. The swing jaw is pivoted at the top; therefore the greatest motion of the jaws is at the discharge or bottom opening. This design has proven good but the difficulty with inexperienced or cheap labor is in keeping the eccentric boxes tight, for, if allowed to get loose and pound, this bearing soon begins to heat and to cause trouble, especially if the jaws are set too close and undue pressure is brought to bear upon these parts. This part is sometimes water jacketed to prevent heating. The friction of this bearing requires more power than is actually needed to break the rock. The cam and roll design was built to obviate these faults.

"In all standard coarse crusher designs the greatest motion of the jaws is at the bottom, ranging from five-eighth inch to three-fourth inch, according to the size of machine and work to be accomplished. This motion becomes less and less as the top jaw is approached, and when the receiving opening is reached, it is reduced to about one-eighth inch. Thus the greatest power and leverages are brought to bear at the first nip on the largest piece of rock going to the machines which fractures and breaks it partially, allowing it to slip further down by gravity between the jaws where it is again nipped, and again and again with increasing strokes until by this gradual reduction process it reaches the discharge opening where it escapes, the discharge being free and rapid on account of the maximum motion at this point. With the small motion at the receiving opening these crushers have much larger capacity than at the discharge, for at the top the rock is

cracked allowing the greater part of the work to be accomplished as the material approaches the discharge. It is a great mistake to undertake to crush to less than 2-inch size in a coarse crusher. If this is attempted, packing results which clogs the crusher and puts excessive pressure on the various parts of the machine." The original Blake crusher was of cast iron. Plate steel is now often used, and Figs. 90 and 91 show how it is put together.



Fig. 90.—End View.

Fig. 91.—Top View.

Fig. 90. Is the end view showing the method of fastening the outer and inner casing together. The bolts are relieved from undue strain by means of the rabbeting rr.

GYRATORY BREAKERS.

(110) Gyratory breakers are of great capacity and large first cost. The crushing motion is obtained by a long eccentric shaft to which the crushing cones are attached, driven by gear and pinion. The case or frame is very heavy and has replaceable liners opposite the crushing head, which forms a circular receiving opening for the rock to be crushed. The shaft has a gyratory motion, causing an advancing and receding action of the crushing head nearly identical with that of the jaw crusher. These gyratory crushers are only suitable for large capacities; for smaller outputs the jaw crusher is preferred. See Fig. 95.

(111) For fine crushing the Kennedy-Van Saun Mfg. & Eng. Corp., New York City have designed and operated a recrushing gyratory crusher without gears. The following description of this crusher is taken from *Mining and Metallurgy* for October, 1921:

"This is a highly developed secondary or recrushing unit, designed to produce finely crushed rock at a rapid rate and at low cost. Proof of the soundness of the direct-drive principle led the Kennedy engineers to study its application to standard or primary gyratory crushers of large size and the development of the Kennedy gearless standard gyratory crusher has been on the same lines that proved so successful in the secondary gyratories of all sizes, from the smallest up to and including the No. 60, crushers. It is the application of the direct-drive principle to standard the largest size of gyratory rock crusher yet built. With the changes necessary for the application of the principle to very heavy machines, the gyratory crusher is advanced to a new stage of perfection.

"The bottom plate sleeve acts as a support for the packed lower dust collar, and as this sleeve does not revolve, the wear on the collar is reduced to a minimum. This bottom plate sleeve acts also as a support in which the eccentric sleeve and ball are contained and for supporting the driving dogs, and forms a journal for the driving pulley, which is equipped with ball bearings. The bottom plate sleeve is shouldered on the inside to prevent the eccentric sleeve from moving upward. At the bottom it has a groove and shoulder for receiving the bayonet lock that supports the ball race and pulley.

"The eccentric sleeve is made in two parts and is joined by bolts passing through at top and bottom. It has a pocket on the thick side for receiving the locking pin that connects the ball and socket bearing to the eccentric sleeve. This pin is flattened on the sides for providing ample bearing in the pocket, preventing wear. At the bottom, where the eccentric is joined together, it forms a male driving dog for fitting into the female seat.

"The driving power is applied through a universal device that eliminates all friction and side strain due to the driving of the eccentric and relieves the grinding and side thrust common to all gyratory crushers. The thrust due to pressure against the eccentric is delivered to the eccentric sleeve at the middle of the ball, and thus the eccentric sleeve floats without pressure from top to bottom. One of these machines was run continuously for 36 hours at a speed about 100 per cent. beyond normal, on a test, and at the end of this time the eccentric had barely reached blood temperature.

"The pulley is supported by the bayonet lock method, and is keyed in position. The eccentric is driven by a double male and female connection cast integral with the bottom plate. The bottom plate is bolted to the pulley and the joint is packed to prevent oil leakage. When the pulley



Fig. 92.—Kennedy Gearless Standard Crusher.

turns, both the bottom plate and driving dog move, turning the eccentric directly, eliminating pull and side thrust on the eccentric.

"The oiling system is unique. Oil from the eccentric chamber can flow freely between the balls, over the top of the pulley hub into the oil well inside the pulley. From this reservoir it is scooped up by centrifugal force and delivered to the top of the eccentric and ball and sleeve. This scoop acts on the principle through which a locomotive scoops water from a canal between the tracks while it is in motion. The system is simple, automatic and free from troubles.

"An important improvement is made in the design of the bottom shell. The base is made square so that stone may be spouted in any direction, which enables the operator to set the machine in any position. Thus the crusher may be driven from a line shaft by belt or rope drive, universal rope sheaves or pulley for belt drives being supplied for leading belt or ropes from pulley or motor to the crusher. The drive pulley can be above, below, or on the same horizontal plane with the crusher."

INTERMEDIATE CRUSHING.

(112) The Dodge Crusher may be used for intermediate crushing from 2 or 3 inch to 1 inch. The largest size, 11x15, has a capacity of five or six tons per hour to 1 inch size.

The Sturtevant Rock Smasher has the jaws so arranged that the pivot at the bottom of the moving jaw is placed well back and below the discharge point. Thus the moving jaw surface has a divided downward stroke which gives the material a rolling crush causing it to break down more easily than with strain pressure and also hastens the discharge. Therefore, it is less likely to clog with soft rock.

"It is to be noted that the output of a crusher depends upon three things: the setting of the jaws, the length of the discharge opening and the stroke. As the stroke is small on intermediate crushers and the jaw settings close, large outputs can be obtained only by increasing the size or length of the discharge opening. This has been accomplished in smashers by building them of multiple jaw construction. Therefore, a single machine having a jaw opening of 6x15 inches, in duplex form would have a jaw opening of 6x30; in triplex, 6x45, etc., and, as each jaw is crushing independently of the other, the strength of the entire machine resists the crushing strain of a single set of jaws. As the jaws crush alternately, the movements are balanced and these crushers run very steadily."

STURTEVANT PLATE STEEL JAW CRUSHERS.



Fig. 93.—Sturtevant Coarse Breaker.



Fig. 94.—Sturtevant Fine Crusher.



Fig. 95.—Traylor Crusher.

Sectional View.

1. Spider cap.
2. Spider.
3. Hopper.
4. Adjusting nut key.
5. Adjusting nut.
6. Sleeve.
7. Bushing.
8. Wearing ring.
9. Sleeve key.
10. Bushing key.
11. Oil feed suspension.
12. Bolts for hopper.
13. Spanner nut.
14. Bottom spanner nut.
15. Head.
16. Concaves.
17. Top shell.
18. Bolts for spider.
19. Bolts for top shell.
20. Top dust collar.
21. Lower shell.
22. Spindle.
23. Diaphragm lining.
24. Chute.
25. Lining for chute.
26. Lower dust collar.
27. Gear.
28. Key for gear.
29. Steal pinion.
30. Key for pinion.
31. Bottom.
32. Eccentric bushing.
33. Bolts for bottom.
34. Eccentric bearing.
35. Oil feed pipe.
36. Oil reservoir.
37. Double countershaft bearing.
38. Countershaft bearing cap.
39. Oil well cover.
40. Door.
41. Drain.
42. Drain for bearing.
43. Countershaft.
44. Driving pulley.
45. Key for pulley.
46. Outboard bearing.
47. Wearing ring.
48. Washer.

(113) Figure 93 shows a Sturtevant coarse crusher of the modified Blake type. Fig. 94 shows an intermediate crusher of the Dodge type. Fig. 95 shows the gyratory crusher made by the Traylor Engineering Co., of Allentown, Pa. Figs. 90 and 91 show the construction of a crusher made of plate steel.

(114) **The Power** required to drive crushers varies, of course, with the material to be crushed, but with the Blake crusher is about as follows (Richards' Ore Dressing):

11-12 tons per h. p. per 24 hours crushed to 1½ inch.
15½–19 tons per h. p. per 24 hours crushed to 2 inch.
18-22 tons per h. p. per 24 hours crushed to 2½ inch.

(115) **The Cost of Crushing** varies with the size and character of the pieces to be crushed and the reduction accomplished from 3 to 12 cents per ton. The cost of fine grinding, as, for example, in grinding cement rock or feldspar, varies from 50 cents to $1.00 or even more per ton depending upon the fineness wanted, the amount of rejection allowed, the hardness of the material, etc.

ROLLS.

(116) Rolls are usually employed for intermediate grinding or crushing. The size of pieces which a given pair of rolls can crush depends upon the angle between the tires which must be the same as in crushers, otherwise the pieces will dance and fail to pass through. If a 36x16 inch roll is used, the maximum sized piece is 2½ inches. The maximum reduction a roll can make from this size would be three or four to one, that is, from 2½ inches to ¾ inch. The capacity of such rolls would be about 30 tons per hour. Corrugated tires are sometimes used on rolls to grip larger pieces of rock.

Rolls give less fine dust than any other method of reduction. As the above example shows, they have large capacity.

(117) **Cornish Rolls** have slow speed up to say 300 feet periphery speed per minute. Fast running rolls may quadruple this. The slower, the smaller the capacity for a given size. In order that tools or other unbreakable material accidentally dropped in may not destroy the rolls, heavy springs hold one set of journal boxes in place, or some other equivalent device is employed.



Fig. 96.

Rolls consisting of two iron cylinders, revolving on the shafts BB in the direction of the arrows and acting on the lump of ore C; one shaft in fixed, the other in movable boxes. The ore is compressed and broken and the pieces fall between the rolls.



Fig. 97.

Fig. 97.—Diagram illustrating the angle of nip of rolls. The angle of nip is one-half the angle made by the tangents to the rolls at the points of contact as between the ore e and the rolls C, D; these tangents form the angle 2n, half of which is called the angle of nip. If e is as large as the opening, n = 0, increasing until the rolls cannot nip the rock which will dance upon them as they revolve. The standard angle of nip is 16°. (Richards).



Fig. 98.

Fig. 98.—Krom's method of attaching roll shells. The core is in two parts, each a little less than half the face of the roll shells. They are slightly conical, having their lesser diameter inwards. One part is shrunk on permanently to the shaft. The other is drawn into place by four bolts.

STURTEVANT BALANCED ROLLS 21" x 10".



Fig. 99.

1. Bed.
2. Stand.
3. Shaft.
4. Bearing box.
5. Stand cap.
6. Bearing oil covers.
7. Spring plate.
8. Springs.
9. Upper spring stud.
10. Lower spring stud.
11. Stay bolt nut.
12. Stay bolt.
13. Stay bolt gear.
14. Stay bolt collar.
15. Worm.
16. Worm shaft.
17. Top case.
18. Flywheel.
19. Lower case.
20. Tire.
21. Solid head.
22. Split head.
23. Shield.
24. Bolts in head.
25. Shaft collar.
26. Shaft collar caps.
27. Bearing box plate.
28. Feeder base.
29. Top
30. Sweep.
31. Trough.
32. Bearing cap.
33. Regulating block.
34. Connecting rod.
35. Pulley.

(118) **Shafts** are usually of mild steel; the cylinders are of soft iron in two pieces as shown in Fig. 98. The tire is made of tough hard material, such as chilled iron, cast steel, chrome or manganese steel and is held in place by the cylinders, as shown. The Taylor Iron and Steel Co., of High Bridge, N. J., furnish manganese steel tires bolted on in sections. Chilled iron costs 3-5¢ per pound, cast steel 8¢, chrome and manganese steel 12¢.

(119) **Feeders** are necessary to prevent clogging where no other method of regulation exists. A variety of devices are used such as rollers, pusher blocks, shakers and stirrups swinging to and fro in the ore current.

(120) **The Hardinge Mill** is a device for medium fine grinding. Silica lining blocks set in cement are commonly used and the ore is broken by the fall of silica pebbles, which rise up the side and drop. For medium fine grinding this apparatus, shown in Figs. 100 and 101 has been found very economical and has large capacity.

(121) **The Ball Mill** is likewise used for medium fine grinding and is shown in Fig. 102.

(122) **The Tube Mill** has a siliceous lining, is long in proportion to its diameter and is charged and discharged intermittently. It is used for very fine grinding.

(123) **A Pulverizer Jar Mill** suitable for laboratory is also shown in Figs. 103 and 104. This is suitable for small operations on a semi-manufacturing scale.

(124) **The Progress of a Grinding Operation** is tested by sifting the product through nested sieves down to 200 meshes to the linear inch and weighing the siftings. To grind material so that most of it will pass through a 100-mesh screen with, say 3 per cent. rejection, is comparatively easy. It is much more expensive to so crush that 100 per cent. shall pass such a screen.

(125) **Uniformity of Grain** in finely ground material is often of great importance; this is especially the case in the grinding of pigments, and sometimes in the preparation of ceramic materials. In the *Journal of the American Ceramic Society* for Oct., 1921, p. 812, H. G. Shurecht describes a method for determining the

HARDINGE CONICAL BALL MILL.



Fig. 100.—Showing distribution of balls.



Fig 101.—Showing path followed by balls.

The conical mill has a stepped plate lining. It is charged through A. The partly crushed material passes successively to zones of smaller balls as it is reduced in fineness until discharged through B. The forward motion thru the mill is the result of a slight inclination of the axis of the mill from the horizontal. The pebbles are of flint or round charcoal-iron slugs.



The material is fed into the mill thru A. It is then subjected to the grinding action between the balls and against the stepped lining. When it reaches the perforated plate B, the finer material passes out into a small chamber C, falls to the bottom, where, at each revolution of the mill a certain amount enters upon the screen through D. Arranged in a convolute outside of the screen is the spiral partition upon which the sifted material falls, is carried to the center and discharged through E. The coarser material remaining upon the screen is also carried to the center, enters the tube F at G, and by means of a spiral is automatically returned to the mill. H, is the tire running on wheel bearings. K, is a wheel bearing. L, is the driving gear.

Fig 102.

PULVERIZER—JAR MILL. Abbe Engineering Co., N. Y.



Jar Outside,
14¾" x 16½".

Flint Pebbles,
45 pounds.

Floor Space,
3'6" x 2'4".

Speed,
40–50 revolutions
per minute.

Charge,
25 pounds.

Weight,
500 pounds.

Fig. 103.—Mill Closed.



Fig. 104.—Mill Open.

rate of sedimentation of clays by measuring the suspended weights of a glass plummet suspended in a clay slip at different intervals of time. The specific gravity of the slip remaining in suspension may be calculated as follows:

$$S = \frac{P_d - P_s}{P_d - P_w}$$ where S is specific gravity

of the slip, P_d is dry weight of a plummet in grams, P_w is suspended weight of plummet in distilled water and P_s is suspended weight of plummet in clay slip. The average weight of clay per cc. is calculated as follows:

$$C_w = \frac{D(S-D)}{D-d}$$ where C_w is average

weight of clay per cc., D is the specific gravity of slip and d is the specific gravity of water.

It is impractical to separate by elutriation, clay particles smaller than 0.003 mm. which constitute 50-100 per cent. of many clays. *It is possible to classify particles as small as* 0.0001 *mm. by the plummet sedimentation method* and the results are more uniform than those obtained by elutriation.

(126) An Impact Screen for sizing large amounts, made by the Colorado Iron Works Co., is shown in Figs. 105-109. This is intended for sizes between one-half inch and 80 or 100 meshes to the inch. "The motion of this screen is perpendicular, or at right angles to the plane of the screen surface, while in all flat screens the motion is nearly in the same plane in which the material is traveling. The motion of the impact screen, combined with the impact or vibration given to the screen cloth at each stroke, prevents small particles of ore from lodging in the meshes. By thus keeping the screen cloth open, its capacity is enormously greater than any form of revolving screen.

"A vibrating frame of wood is flexibly supported within the main frame by a pair of elliptical springs which force it against four adjustable stops. To this vibrating frame, motion is imparted by two ratchets, operating as multiple cams, keyed to a revolving shaft, upon the end of which is the driving pulley; the shaft being journaled in bearings carried on the main frame.

"For convenience in replacing the wire cloth when worn, it is fastened by means of wood strips, small wire nails or screws to a frame provided with slats placed parallel with the travel of the ore, stiffened by a cross piece one-half inch below the screen surface. This frame serves to support the cloth in a true plane. It is fitted within the vibrating frame and held in place by means of clamps with thumb nuts, permitting its removal in a few minutes without the use of tools. The screen frame and the vibrating



Fig. 105.—Impact Screen with Covered Housing for Dry Screening.

frame which carries it act as one piece, are light in weight and constitute the only moving parts. There are no eccentrics nor reciprocating parts to cause trouble and annoyance. The screen is furnished with a steel housing, made open top for wet screening and with a wooden top for dry screening.

"When used for wet screening, a series of shallow pans is carried by the screen frame just below the surface of the wire cloth as shown, and serves to furnish the water necessary to keep the meshes open.

"For use in the impact screen, wire cloth is used with oblong meshes, to be so placed on the frame that the longest dimension of the openings will be in the direction of the travel of the ore,

the 'size mesh' being the greatest number of meshes per lineal inch. This is to overcome the effect of the inclination of the screening surface.

"For dry screening, steel wire cloth up to and including 24 mesh, and brass wire cloth in the finer sizes are used. For wet screening, steel wire cloth up to and including 14 mesh, and brass



Fig. 106.—For Wet Screening with Distributor.

wire cloth in 16 mesh and finer, except under conditions where it will not answer, as where it will be subject to the action of cyanide solution are used."

(127) Other Crushing Apparatus.—The most efficient apparatus for most purposes have been described above. For special purposes Chile or Chaser mills, stamp mills, roller mills, buhr mills and beaters of a great variety of design are often employed. For coarse grinding of material like salt cake the Jeffrey Swing Hammer mill (Fig. 110), has large capacity and does the work well. Special forms of this apparatus have been designed for grinding



Fig. 107.—Screen Frame for Dry Work.



Fig. 108.—Screen Frame for Wet Work.



Fig. 109.—Setting for a Single 3' x 4' Impact Screen.

JEFFREY'S SWING HAMMER PULVERIZER.



Fig. 110.—Vertical Section of Pulverizer.

A. Throat Opening into which Material is Fed.

B. Hard Steel Hammers revolving at a high rate of Speed in direction indicated.

C. Hard Iron Liners.

D. Breaker Plate adjustable to shear close to Hammers.

E. Screen Bars (any mesh) to prevent egress of oversize Material.

F. Drop Bottom to eject tramp iron or to clean out Machine.

limestone for fertilizer, glue, alfalfa, bark and a great variety of other substances.

(128) Raymond Mill.—In the Raymond Mill, Figs. 111 and 112, the substance after grinding is subjected to a blast of air which carries away the finest particles, leaving the larger, heavier pieces for further grinding. Here, also, special forms are built for each purpose, and in making enquiries, the mill builder should have full details of the material to be ground and the duty required. When practicable this method of separation of fines is preferable to screening. For beating material like dry barium carbonate into a fine powder the Mead Mill answers very well and has large capacity. Pulverulent material like this must be carefully dried or it will choke the mill.



Fig. 111.—Raymond Mill.

(129) **Williams Mill.**—Fig. 113 shows an impact mill built by the Williams Co., St. Louis, Mo., for pulverizing bark. It has a capacity of three to four cords per hour and requires 30-35 horse-power.

Fig. 112.—Raymond Mill.



Fig. 113.

Williams Patent Crusher and Pulveriser Company, Engineering Dept. St. Lous, Mo.

CHAPTER X.

MECHANICAL HANDLING OF MATERIAL.

(130) As common labor becomes more costly the moving of material from place to place likewise becomes more and more expensive. It is often necessary to move many tons of material in order to produce one ton of finished product. In recent times for this reason increased attention has been given to mechanical handling in order to save costs. The solution of any problem of this sort must pay careful attention to the amount of material to be moved since it will not pay to put in expensive machinery where the amount to be moved is not large.

It is also desirable to have one installation take care of all the transfer work to be done. For instance, unless it can not be avoided motor trucks run by electric motors and by gasoline engines should not be installed in the same works. The question of repairs and upkeep should also have careful examination in the selection of equipment.

For the transfer from boat to wharf or to cars of coal, limestone, iron ore, etc., the equipment now used in the iron industry on the great lakes should be studied. For the transfer system within the works the engineer should study the arrangement of a modern flour mill, or a good ice plant, or both. The practice in the best of such plants is highly developed and worth careful study. In foundries and machine shops the overhead traveling crane has been widely adopted, and for storage of crude material in rough yards a traveling crane mounted on a caterpillar tractor gives promise of usefulness. The variety of appliances now on the market is so great that proper apparatus can almost always be had from stock. In making the selection care must be taken to ascertain that parts for replacement can be had promptly and at reasonable cost and that the concern turning out the apparatus has a reasonable chance of survival so that these repairs may be available during the life of the machine.

Where trolley or track lines are to be installed a careful study of the work to be done should first be made to see whether all

transfer problems to be met cannot be solved by one installation. Following this idea A. E. Marshall has shown[1] that it is possible to so design a plant for sulphuric acid from pyrites that a monorail trolley with a 3000-pound bucket may be arranged to transfer 100 tons pyrites from the cars or boat to the burners or to storage, to load the 70 tons of cinder produced into cars and to unload and put into storage the necessary nitrate of soda as well as to convey any coarse pyrites to and from the crusher.

He has also shown that for acid phosphate plants the best solution is an overhead crane such as is used in foundries.

(131) **Screw Conveyors** are illustrated in Figs. 114, showing a cast iron continuous flight conveyor[2] and 115, showing a ribbon conveyor. These conveyors operate in troughs usually provided with removable covers. They are commonly applied only for short flights.

(132) **Spiral Chutes** are often an aid in transferring filled bags. The screw conveyors shown are from the H. W. Caldwell & Son Co., Chicago, Ill.

(133) **Work Trucks**[3] operated by storage battery or by man power are best adapted to the solution of some transportation problems within the works. Such a truck with side dump either way is shown in Fig. 116. These cars are furnished up to 54 cu. ft. capacity. When properly balanced they can be tipped by one man. This hopper may be lifted off and we have a flat car suitable for carrying material in sacks, boxes, etc. Another type of car mounted on wheels with gable hopper for discharging on either side is shown in Fig. 117. This is well adapted for elevated tracks where the material is to be discharged in piles on either side. A third form which discharges on either end and either side is shown in Figs. 118 and 119. This has a turntable under the hopper. The speed of such trucks within the works should not exceed six miles per hour.

[1] Symposium on Bulk Handling of Materials, N. Y. Section Society Chem. Ind. Meeting held April 22, 1921.

[2] An Article on Screw Conveyors as applied to the charging of copper smelting furnaces will be found in the *Engineering and Mining Journal* of Jan. 29, 1921, p. 226.

[3] For the cuts to illustrate this section and for information furnished I am indebted to W. E. Farrell, of the Easton Car and Construction Co., Easton, Pa.

Fig. 114.

Fig. 115.



Fig. 116.

Fig. 117.



Fig. 118.

Fig. 119.

(134) Tracks for Works roads are made in a great variety of gauges of which 24-inch is perhaps most common. The rails used are about 16 to 20 pounds or heavier according to the weight to be carried. These tracks are furnished in sections with steel ties and for many purposes need no fastening. For permanent work the tops of the tees may be laid flush with the top of the concrete floor with a slot to admit the wheel flange.

A switch is *right handed* when in standing facing the point it turns to the right; *left handed* when it turns to the left; *symmetrical* when it turns both ways and *three way* when the track is continuous with a switch on either side.

(135) The lay out of tracks depends upon the work to be done and differs in almost every case. Before any plans for this purpose are made the engineer who is to build the cars should be consulted. It is a great mistake, and one frequently made, to undertake general layouts of any sort without such consultation of specialists, which usually costs nothing and often furnishes information not otherwise obtainable. Sneering remarks about specialty engineers and their catalog statements are badly misplaced. These men often carry better brains than their clients and have been through a hard school of elimination.

Further detailed information upon material handling equipment may be obtained from the catalogs of the Jeffrey Mfg. Co., Columbus, Ohio, or from an article in the *Chemical Age* of Oct. 19, 1921, Vol. 29, p. 427, by R. H. McLain of the General Electric Co.

CHAPTER XI.

DISSOLVING.

(136) The act of bringing substances into solution appears so simple as to require no comment. A little experience shows this to be wide of the mark. In some cases it is difficult to obtain cheaply and rapidly a saturated solution of the material wanted and, inasmuch as a partly saturated solution means more evaporation, it is to be avoided.

(137) Salt solutions are almost always heavier than the solvent. If, then, we place the substance to be dissolved in the bottom of the tank, the heavy saturated solution will form and remain just around and over the solid, while the upper part of the tank will contain only solvent with no or only very little dissolved material. If the material to be dissolved is placed in the upper part of the tank in an open sieve or other appropriate support, as fast as the solution forms, it drops to the bottom of the tank and fresh solvent takes its place until the whole amount of liquid becomes saturated. The rapidity of solution and hence the amount of saturated solution to be made in a given time depends upon several factors.

1. Solubility: The more soluble the substance, the more rapidly solution takes place.

2. Surface exposed: The larger the surface, the more rapidly solution takes place.

3. Temperature: Usually, the higher the temperature, the more rapidly solution takes place. Solution is sometimes complicated by reactions which take place when the solute is brought in contact with the solvent. For example, dry sodium carbonate and sulphide in fine powder combine with water with a rise in temperature to form lumps which have much less surface than the original material.

(138) **Stirrers** are frequently employed to hasten solution. They may be made of steel, or when necessary of steel covered with lead, or entirely of wood. The New England Tank and

Tower Co., of Everett, Mass., build the "Nett-Co" Direct Connected Drive, (Fig. 120), consisting of a motor either a. c. or d. c. up to 1½ H. P. This is placed on a cast iron shelf which is prolonged sideways into a frame work for the agitator shaft. The apparatus may be readily moved and gives direct drive, avoiding shafting. The John Johnson Co., of Brooklyn, N. Y., make a tur-



Fig. 120.

bine mixer shown in Fig. 121. Solution may be hastened by coils or jackets on the bottom or around the inside of the tub, heated by open or closed steam. The material is shoveled or dumped in at the top. It is best dumped in from an automatic trip weighing scale, as in this way more uniform results are obtained.

(139) Power Requirements.—For water or similar liquid the power requirement with a stirrer of the above type run at 100 r. p. m. varies with the size of tank in use about as follows:[1]

4×4	tank	using	18	inch	turbine	.....	1	to	1½	H.P.
6×6	"	"	24	"	"	.....	3	"	5	"
8×8	"	"	30	"	"	.....	7½	"		"
10×10	"	"	36	"	"	.....	10	"		"

[1] Conrad Pennucci.



Fig. 121.

With heavy viscous or pasty liquids the power requirements are greatly increased.

With ordinary arm stirrers run at 25 r. p. m. the power requirements are:

4 × 4	Tank	½	H.P.
6 × 6	"	1	"
8 × 8	"	1½	"
10 × 10	"	3	"

(140) A dissolver made by the Werner and Pfleiderer Co., of Saginaw, Mich., is shown in Fig. 122. This is made in varying sizes from 2.65 to 1250 gallons working capacity. The makers

state that one customer has reported that they dissolved 750 pounds of borax in 9000 pounds of cold water in from 10 to 12 minutes in the largest size dissolver, 5 horse-power being required. This machine may also be used as a mixer for preparing thin pulp. As an illustration, one concern with a 500-tank dissolver using 300 gallons of lukewarm water to 1500 pounds of clay per batch, finished the operation in 1½ hours with 2½ to 3 horse-power. This includes the power required to drive a pump which pumps the mixture from the machine to the coating room where it is used for coating wall paper.



Fig. 122.—Rapid Dissolver, Size 1.

(141) **Compressed Air** is often used for stirring, and answers very well with Pachuca tanks (Fig. 123). In some cases, as in dissolving raw sugar, the material is dropped into the tank, water run in and open steam blown through until solution takes place.

PACHUCA MIXING TANK.



Fig. 123.

(142) Where obstinate setting takes place, as with barium sulphide, the dry material may be fed with warm water in regulated streams through the trunnion of a ball or Hardinge mill. The rotation of the apparatus, with the grinding action, gives rapid and perfect solution. The solution also heats considerably, due partly to the heat of combination and partly to the conversion of motion into heat.

(143) **The Buff-Dunlop or Shanks Apparatus.**—In this apparatus fresh material meets a nearly saturated solution, after this a

progressively weaker liquor and finally water is employed. This apparatus has been employed for lixiviating black ash for many years. Four tanks are used as shown in Fig. 124. Each tank is 7x7x5 feet and will hold black ash from 6000 pounds salt cake. Such a set can wash the ash from 12,000 pounds salt cake in 24 hours. The tanks are made of five-sixteenth to three-eighth inch boiler plate properly stiffened by angle irons. Each tank has two overflow pipes, one, *FFFF*, for strong (Fig. 125), the other, *EEEE*, for weak liquor. The weak liquor pipes allow the weak liquor to flow from one tank to the next in the series, while the strong liquor pipes empty into the strong liquor launder, *I*, emptying into the strong liquor well, *D*. Those for strong liquor have the outlet and plug placed lower than in those for weak liquor. These pipes terminate below the false, perforated bottoms of the tanks which are covered with three inches of sifted cinders to act



Fig. 124.

as filters. Three tanks, *L, M, N*, are in operation (Fig. 124), while the weak liquor in *K* is being discharged through the cock *G* into the launder *H* and weak liquor well *C*. The waste in *K* is then shoveled out and the tank charged with fresh ash. The weak liquor is pumped from the well *C* upon the surface of the nearly exhausted charge in *L* through the pipe *B*. This liquor passes down through the charge in *L*, gaining in strength continually, and up through the second pipe *E* into *M*. It flows down through the charge in *M* and up through the third pipe *E* into *N;* then down through the fresh charge in *N* and up through the fourth pipe *F*, now entirely saturated, into the launder *I* and strong liquor well *D*. By means of the pipe *J* weak liquor from *N* may be discharged upon the surface of the charge in *L*, thus making any tank first, second, or third in the series. Instead of using

cocks on the ends of the strong liquor discharge pipes *F*, a short piece of pipe is screwed into the elbow. When this is turned down at a right angle the liquor discharges into the launder *I*.

BACK ASH LIXIVIATING TANKS.



Fig. 125.

A. Steam Pipe.
B. Water or Weak Liquor Pipe.
C. Weak Liquor Well.
D. Strong Liquor Well.
E. Overflow Plugs for Weak Liquor.
F. Overflow Plugs for Strong Liquor.

CHAPTER XII.

FILTRATION.

(144) The simplest method of filtration is that of filtration by decantation. The solution is allowed to stand in a tank, and the clear solution run off. Sometimes a bag is tied over the end of the discharge pipe to catch floating straws, etc. In such cases the bag must be removed periodically, turned inside out and carefully washed. Where color is a criterion of value, as, for example with blanc fixe, too much care to obtain bright, clear solutions cannot be taken.

In some cases clarification may be aided by adding a little albumin and heating, or by adding fine asbestos and stirring thoroughly, or by causing the formation of a precipitate, as by adding a trace of alum or calcium chloride, or some fullers earth, or precipitated silica. The nature and amount of material added must depend in each case upon the nature of the solution and must be ascertained by preliminary experiment. I cannot impress too strongly the desirability of trying earnestly to get the desired result by settling if this be possible. It is nearly always necessary to filter the last part of the solution, but filtration is always tedious and expensive.

(145) **Separators.**—If a stone be tied to a string and rapidly revolved by the hand and arm and the string and stone released, the stone will fly in a line tangent to the circle described at the moment of release. It may be shown that the force exerted is $F = \frac{mv^2}{r}$ where m = mass, v = velocity and r = radius of the circle described. The force necessary increases directly with the mass and velocity and decreases as the circle increases in radius. If we suppose the velocity and radius to be constant, the force necessary will vary directly with the mass.

Mass is the product of density into volume, or mass = Vd.

If we assume that V is constant it becomes evident that as the density increases or diminishes, the mass will increase or dimin-

ish, and the force required will proportionately increase or diminish. We may write this $F = \frac{Vdv^2}{r}$, or, assuming r, V and v^2 to be unity,

$$F = d.$$

That is, as the body grows in density the centrifugal force increases. This is the principle of the cream separator (Fig. 126), in which the whole body of new milk is revolved. The fat or



Fig. 126.—Improved De Laval Cream Separator
(From Vulté & Vanderbilt's "Food Industries," p. 169)

cream having a lower density than the milk, flows to the center, and the heavier skim milk flows toward the periphery. The ap-

paratus is provided with an inlet tube at one end and two outlet tubes at the other. By means of proper valves the volume of each outflow may be regulated, and a cream of the desired fat content obtained.

Milk is an emulsion of two liquids and the same method may be applied to the separation of other emulsions. In these cases we have the separation of two liquids.

The same method may be applied to the separation of a solid from a liquid, as in filtration. Thus, Gore[1] has shown that cider which contains considerable solid material is best clarified by means of a cream separator. He has shown that when a separator capable of delivering 450 pounds of milk per hour is employed, 45 gallons of fresh cider may be clarified in an hour.

Three forms of apparatus constructed on this principle were described in 1911 by the De Laval Separator Co., 165 Broadway, New York City.[2]

(146) It must not be forgotten that in order to effect separation, it is necessary that there must be a difference in density. Where no difference in density exists, the liquid will remain cloudy. Thus Gore found it impossible to get a perfectly clear cider with the separator even after passing twice through the apparatus and De Laval's practically acknowledged the same thing to be true of some mixtures, the apparatus described in the second citation being a separator and filter combined.

(147) Separation is often very desirable as a preliminary to filtration, thus at the Fleischmann yeast plant at Peekskill, N. Y., the yeast after 18 hours growth in a wort is run through De Laval separators resulting in a thick paste of yeast cells and a clear filtrate. The thick paste is then run through a center feed filter press, result: a dry cake such as we find on the market.

(148) **The Sharpless Super Centrifuge** is shown in Fig. 127. The smaller size for laboratory use operates at 40,000 r. p. m. and the largest at 17,000 r. p. m. In this apparatus therefore the force of gravity is multiplied by these figures. The laboratory size is

[1] H. C. Gore, Unfermented Apple Juice, Bull. No. 118, Bureau of Chem., U. S. Dept. of Agriculture, Page 15.

[2] *Met. & Chem. Eng.*, 9, 147, 159, 283.


CENTRIFUGE
1. Bowl Barrel
2 Steam Lid
3. Steam Wheel
4. Cone Bearing
5. Ball Cup Cap
6. Ball Cup Race
7. Ball Cup Plate
8 Ball Cup Spring
9. Sight Oiler
10. Oil Shedder
11. Oil Guard
12. Bowl Spindle
13. Speed Indicator
14 Bowl Neck
15 Density Screw
16. Bowl Shell
17 Coverlid
18. Cover—upper
19. Cover—lower
20 Bowl Bottom
21 Rubber Joint Ring
22 Bowl Base
23. Drag Shell
24. Drag Bushing
25 Drag Washer
26. Drag Spring
27. Feed Nozzle
28 Feed Tube
29. Feed Tube Rubber
30 Float
31 Supply Can
32 Holder
33 Faucet
34 Steam Valve
35 Steam Gauge
36 Feed Cup
37 Lag Screw
38 Coupling Wrench
39 Bowl Bottom Wrench

Fig. 127.

provided with an inner bowl shown in Fig. 128. The theory of centrifugal separators has been considered by Eugene E. Ayers, Jr. (*J. Soc. Chem. Ind.*, **35**, 676).



Fig. 1.



Fig. 2.

Fig. 128.

The Inner Bowl is a device for the clarification or filtration in batches of 50 cc. or less of a liquid. It is non-continuous. By disconnecting top (C) from the bottom (D) by means of the screw (E) the lower chamber (A) may be filled with the liquid to be clarified. The top is again screwed on and the device placed in the regular Laboratory Super-Centrifuge bowl as in Fig. 1. As the bowl starts to revolve, the liquid is almost instantly drawn into chamber (B) where clarification takes place—the solids being firmly packed by centrifugal force generated against the walls of the upper chamber. When the bowl is stopped the liquid will again collect in the chamber (A) from which it can be removed for examination. The solids can then be removed from the upper chamber. In most cases quantitative results may be secured.

This device is valuable for any clarification work where only small amounts of liquid are available, but will be appreciated in handling serum or bouillons.

CENTRIFUGALS.



Fig. 129.

(149) Centrifugals are a special form of separator used for rapidly separating crystals from their mother liquor, as in the separation of sugar crystals in the preparation of granulated sugar. In this case the masse-cuite, consisting of syrup mixed with sugar crystals to form a paste, is discharged into a revolving



Fig. 131.

perforated drum. This may be under- or overdriven. Suspended overdriven centrifugals built by the Tolhurst Machine Works, Troy, N. Y., are shown in Figs. 129 and 130. In operating, the masse-cuite or other material is discharged into the machine which for this size should run at 1000 r. p. m. When operated by an induction motor with 60 cycle current this must be operated either at 900 or 1200 r. p. m. of which the higher speed is prefer-

able. A little water sugar solution is then sprayed on the sugar crystals. In a short time this passes through leaving the crystals pure and nearly dry. They are then dropped and carried to the drier by a conveyor. The entire cycle of operations requires less than ten minutes for granulated sugar. With molasses sugar more time is needed. The Tolhurst Co. also make an apparatus for drying small metal articles in the centrifugal shown in Fig. 131. This is used in plating plants, etc.

(150) Fig. 132 shows a centrifugal made by the Fletcher Works, formerly Schaum & Uhlinger, Philadelphia. This like Fig. 131 is underdriven. In Fig. 131 the countershaft is placed overhead while in Fig. 132 it is mounted on the machine. Fig. 131 has



Fig. 132.

a belt shifter while Fig. 132 has a friction clutch. Fig. 133 shows another underdriven centrifugal made by the Fletcher Works. In this cut 3 is the basket into which the material is placed. The machine is then started and the centrifugal force acting on the material causes it to climb up the sides of the revolving basket, forming a wall on the inside. The crystals are prevented from passing over the top of the basket by the top ring 21.

The drum 27 is perforated and inside the drum there is a woven wire screen and inside the screen another finer woven screen, filter cloth or other filtering material according to the nature of the material to be dried. When the required degree of dryness



Fig. 133.

is obtained, the machine is stopped and the valve 4, removed by means of the combined handle and locking device 15. The wall of material is then broken down and the crystals scraped through

the opening 14 in the basket bottom 20, and flows out of the machine through the trough 12.

The liquid is thrown by centrifugal force against the inside of the curb 2, whence it runs into the gutter 25 and out through 13.

In commercial centrifugals the centrifugal force is 200 to 600 times greater than gravity.

"In practice the load can not be evenly distributed, or may not remain so due to the moisture content having been greater in one portion than another. As the centrifugal force is hundreds of times that of gravity it requires but a few pounds more on one side of the basket than on another to cause an unbalanced force of great magnitude. To avoid excessive strains on the bearing the basket is held flexibly by the ball 16 and the springs 9. With an uneven load the basket spins about its center of gravity and oscillates about the ball joint 16. In other words the basket runs out of true to an amount depending on how much the load is out of balance. The springs 9 do not affect the amount of oscillation to any appreciable extent, after the basket has acquired considerable speed, as the effect of the centrifugal force is too great to be overcome by the springs and their purpose is to relieve the bearings of excessive pressure. These springs are necessary in an underdriven machine to prevent the basket from falling over to one side. In an overdriven machine they are principally necessary to overcome the friction at the point of suspension.

"While the springs must be sufficiently strong to maintain the basket in an upright position, if excessively strong they introduce a disturbing element which is often encountered in high speed machinery, and is known as a "critical" speed. Under the influence of the springs, if the basket were thrust to one side and released, it would have a tendency to swing back and forth like an inverted pendulum until brought to rest by friction. The beat, or period of oscillation would depend on the stiffness of the springs on the one hand, and weight of the basket and its moment of inertia about the point of oscillation on the other.

"When the revolutions of the basket are such that they correspond with two beats of the basket as a pendulum, with an uneven load, we have the condition which produces a 'critical' speed.

Under these conditions the heavy side of the basket is revolved in synchronism with the swing of the basket about the spherical seat and the force which is stored in one spring when the heavy portion of the basket was on that side is given up just in time to be added to the effect of the heavy side of the basket on the spring directly opposite. The swaying of the basket would then increase until the conditions were changed or the swinging parts struck the stationary parts of the machine. As the speed is increased the revolutions and swinging of the basket no longer synchronize, and the basket begins to 'spin.'

"After passing the critical speed the heavy side moves in toward the center of revolution, and a piece of chalk held so as to just touch the outside of the basket would mark it on the most lightly loaded side. This phenomenon is rather difficult to understand, because the effect of centrifugal force is outward, and it would naturally be expected that the heavier side would swing the farthest from the axis of revolution. If it is considered, however, that the whole mass is being revolved without restraint, it will be seen that the inertia of the heavier portion will tend to cause the lighter portion to be revolved about it as a center. The result is that the center of gravity becomes the center of revolution, which explains the phenomenon.

"For chemical work, the parts of the centrifugal which come in contact with the chemicals must be of a material which will withstand chemical action. A variety of constructions are, therefore, necessary to meet different conditions. Baskets are made of iron, steel, bronze, monel metal, aluminum, etc. They are often coated with rubber, galvanized or tinned. The outer casings, likewise, are often lined with lead or rubber.

"When drying material in a centrifugal machine, centrifugal force is opposed to the capillary attraction of the solids for the liquids, and also to the adhesiveness of the liquids. The viscosity tends to make the drying slower. Owing to the capillary attraction becoming greater as the voids become smaller, we find the drying action to be slower and less complete with fine solids in a viscous liquid. With a liquid of low viscosity and solids of the degree of coarseness of ordinary granulated sugar and upward,

the 'purging' of the liquid is very quickly and completely performed."[1]

(151) On account of the high speeds and the varying conditions under which centrifugals are operated, the greatest care should be taken to see that a machine is selected which is suitable for the particular purpose for which it is required. In a number of cases centrifugals intended for drying textiles, of which, owing to their bulky nature, but a comparatively small weight could be put in the basket, have been used for heavy chemicals, with the result of a serious accident.

Where subject to corrosion the machine, particularly the baskets, should be frequently examined to ascertain that they have not become weakened.

(152) Centrifugals are commonly used for drying cane, beet and milk sugar, common salt, ammonium sulphate, naphthalene, carbolic acid crystals, picric acid crystals, nitrocellulose, starch, soda crystals, di- and tri-nitrotoluol and for chemical crystals generally.

(153) **Settlers.**—The Dorr Co., of 101 Park Ave., New York City have applied an agitator and settler to the problem of separating solids from liquids. Their first work was in the treatment of gold ores with cyanide solution. This has been followed by other applications such as the manufacture of caustic soda from lime and sodium carbonate, the washing of sodium nitrate crystals, etc. A description of the caustic soda process will make this clear. The interaction involved is: $Ca(OH)_2 + Na_2CO_3 = 2NaOH + CaCO_3$. In order that this may reach completion from left to right it is necessary that the solution contain not to exceed 1 pound NaOH to 5 pounds water.

(154) "The areas of the rectangles shown in Fig. 134 represent the comparative dissolved content of the solutions used in the following description: The materials in the proper proportions are mixed with weak caustic solution (available from previous washing) in a tank so that after agitation the tank will contain 3 tons of precipitated calcium carbonate (dry) and 4000 pounds of caustic soda dissolved in 10 tons of water (400 pounds

[1] Leslie Griscom.

NaOH per ton of water). This mixture is allowed to settle until 7 tons of water (containing 2800 pounds of NaOH) together with the precipitate, remain in the tank in the form of a sludge.



Fig. 134.

"To this sludge is added a dilute solution available from washing a previous batch, consisting of 10 tons of water and 100 pounds of caustic soda (10 pounds of NaOH to a ton of water). The resulting mixture, after thorough mixing, contains the 3 tons of precipitate, 13 tons of water, and 1300 pounds of caustic soda (100 pounds per ton of water). Settling again takes place, and 10 tons of clear water (containing 1000 pounds NaOH) is decanted. There remains in the tank the 3 tons of precipitate and 3 tons of water containing 300 pounds of caustic soda.

"By means of further steps along this line as above described, this sludge may be washed until practically all of the caustic is separated from the precipitate.

(155) "Considering this now from the standpoint of the continuous counter current flow sheet (Fig. 135), assume that the soda ash and lime mentioned in the preceding paragraph are agitated as above described, producing 3 tons of calcium carbonate (dry) and 10 tons of water containing 4000 pounds of caustic soda. Assume, too, that similar batches are produced at regular intervals of, say, 2 hours. At this rate there will be produced

during 24 hours 36 tons of calcium carbonate and 120 tons of water containing 48,000 pounds of caustic soda, the whole of which mixture will be fed to thickener No. 1 at a uniform rate throughout the 24 hours. If the thickener were charged with a quantity of this mixture from previous batches, there would be overflowed, during each two hours operations, 7 tons of water containing 2800 pounds of caustic soda, while 3 tons of water containing 1200 pounds of caustic soda would leave the thickener mixed with calcium carbonate in the form of a sludge, exactly as was the case in the operation of the intermittently operated tank above mentioned.



Fig. 135.

"Now this 3 tons of water containing 1200 pounds of caustic soda, which leaves thickener No. 1 as part of the sludge during each two hours, is continuously transferred in like time to a second thickener, in which a wash is being continuously given the sludge by mixing it with 10 tons of water containing 100 pounds of caustic soda (the overflow from a third thickener). As in the case of the intermittently operated tank, the solution produced by this mixture consists of 3 tons of precipitate and 13 tons of water containing 1300 pounds of caustic soda. Of this mixture, 10 tons of water containing 1000 pounds of caustic soda will be decanted or overflow, going to the agitators to be used in making up a new batch, while 3 tons of water containing 300 pounds of caustic soda passes out in the overflow to be transferred to thickener No. 3 for a second wash.

(156) "From the above, the conclusion might be drawn that the same washing efficiency could be expected from the intermittent system as from the continuous counter-current decantation sys-

tem, and theoretically this is true. In practice, however, this theory seldom holds good. In the manufacture of caustic soda, for instance, it is safe to say, that few of the operators using the intermittent system make an average recovery to exceed 96 per cent. or 97 per cent. of the caustic when using two washes. A plant using continuous counter-current decantation with Dorr equipment has shown a recovery of 99.5 per cent. to 99.6 per cent. over a period of several months' operation. This plant is producing a 15° Bé solution, and employs two washes.

(157) "In the continuous counter-current decantation system as generally installed to-day, the sludge coming from the thickener in the system is passed through a trough or launder, in which it is thoroughly mixed with the overflow from the subsequent thickener in the washing system. This mixing is one of the important features in the system and is responsible for the close approach to the theoretical washing efficiency made possible by it.

(158) "Fig. 136 represents a typical installation of Dorr thickeners and Dorr agitators in a system using continuous coun-



Fig. 136.

ter-current decantation and continuous agitation, suitable for the majority of chemical operations to which the system is applicable. The various machines are installed at the elevations shown so that the solution will flow from the overflow launder or trough of the one preceding. The overflow from thickener No. 2, which is the strongest wash water in the system, flows to the first of the series of Dorr agitators, where it is used as 'make up' water for the reaction which takes place in the agitators. The mixture in

which the reaction is taking place flows through each of the agitators in the series and finally to thickener No. 1. The overflow, or thickened sludge, from thickener No. 1 is transferred by means of a diaphragm pump, *DP*, to the feed launder of thickener No. 2 in which it is mixed with the overflow from thickener No. 3, as above described. The overflow from thickener No. 1, consists of the strongest solution in the system and is carried away for use or further treatment, as subsequent parts of the process may demand.

"It will be noted that the flow of the solution is accomplished entirely by gravity and that the only pumps required are used to control the rate of discharge from the various thickeners and at the same time transfer the thickened sludge from one thickener to the following one in the system.

(159) "One of the most vital points in the continuous countercurrent system is the control of the moisture content and thereby, the amount of dissolved substance which leaves each thickener with the sludge. There is, of course, for each individual material a ratio of solution to solids below, which the material will not further separate by settlement, but it is essential that the underflow from each thickener have a consistency approximating this ratio as nearly as is practicable. Several methods have been used to obtain this control of the underflow, but the use of the Dorrco pump (Fig. 137) has proven most satisfactory. The pump is connected with the thickener underflow and is located just above the side of the tank. This pump presents the advantage of a positive displacement through which an automatic regulation feed of discharge is approached, with a regular and definite feed to a thickener in a definite time. This pump is regulated by hand to give the displacement necessary for handling this volume. Since the volume of the solids is a definite quantity, the amount of solution which passes out with them in the above mentioned period is also very nearly definite in spite of any slight variations which may occur in pulp density. That such control is impossible with a valve or nozzle discharge is at once apparent. An air lift connected to the discharge pipe has been used in some installations, but a uniform density of discharge cannot be maintained with it.

The body of the ordinary diaphragm pump is constructed of ordinary cast iron for use where such construction is permissible, but for acid solutions it is cast of Duriron or antimonial lead.



Fig. 137.

(160) "**The Dorr Continuous Thickener** consists of a slow moving mechanism made up of a central vertical shaft driven by a worm gear and worm, the shaft having radial arms attached to its lower end. These arms carry plow blades set at an angle which, through the rotation of the mechanism, move the thickened material to a discharge opening at the center of the tank. The mechanism is usually placed in a comparatively shallow, flat-bottomed tank into which the feed enters continuously at the center and from which the clear decanted solution overflows and is collected in a peripheral trough or launder. The overflow containing the solids is taken off at the center of the tank bottom and is usually controlled and elevated by a diaphragm pump.

(161) "The Dorr Thickener, Fig. 138, may be most simply termed a continuous settling tank, the action of the rakes or arms being so slow that in no way does it hinder settlement.

"The mechanism is so arranged that the shaft and arms may be raised by means of a lifting yoke attached to the top of the shaft, thus preventing the arms from being imbedded in the thickened material at the bottom of the tank in case the power should be shut off. The shaft may be gradually lowered while the machine is in operation, until the arms assume their normal position in the tank.



Fig. 138.

"The Dorr continuous thickener is usually equipped with an overload alarm which indicates the relative amount of power being taken off at any time, and, when the machine becomes overloaded, rings an electric bell. Immediate attention can then be given thereby preventing breakage.

(162) "The capacity of a thickener depends entirely upon the physical nature of the material handled and is governed largely by the area of the tank bottom. For each individual material there is a minimum area which must be available for each ton of dry solids to be continuously settled per 24 hours.

"The Dorr thickener may be built of acid resisting material where required.

(163) "**The Dorr Agitator,** Fig. 139, can be operated in a flat or conical-bottomed tank, and consists of a central vertical cylin-

der carried by a shaft supported from the top of the tank, and equipped with two arms carrying plows, as in the Door thickener, which travel around the bottom of the tanks and move the pulp to the center. The arms are hinged so that they may be raised to a sharp angle, thus obviating the trouble that might be experienced in starting up even in a sandy sludge, after which the arms can be lowered slowly to their normal position. The sludge or pulp is raised through the cylinder by means of compressed air and distributed uniformly over the surface of the mixture in the tank by means of suitable revolving launders.



Fig. 139.

"It is possible under certain conditions for the coarser particles in the tank to be given a longer period of agitation than the finer material by regulating the discharge point for the solids in the revolving launders."

(164) Filters.—The most familiar filter is the paper filter supported in a funnel, shown in Fig. 140. If *ABC* be the precipitate left in the paper and we wash it by pouring water on the surface,

the water will take the path of least resistance which is the shortest path, and travel from *A* to *B* and not from *A* to *C* so that no matter how often we wash it, the precipitate at *C* will be very poorly washed.

If we use the Shimer filter, shown in Fig. 141, consisting of a horizontal layer of paper felt supported by piano felt, and pour a precipitate upon it, we shall have a much better filter, capable of easy washing with a very small amount of wash water.



Fig. 140.

Fig. 141.



Fig. 142.

A third form of filter is shown in Fig. 142, which is a perforated cylinder covered with filter cloth, suction being applied at *V*. The liquid then passes through the cloth and the solid forms a cake on the outside. As all suspensions are densest at the bottom, even when stirred, the mass *P* is thickest at the bottom.

The mass is washed by lifting it into a vessel of clean water and again applying suction. The water again seeks the path of least resistance, and the precipitate is more perfectly washed at the top than at the bottom.

(165) Filter Presses are constructed on two separate principles; they are run either by pressure or suction; an example of the first type which may be built either of wood or metal is shown in Fig. 143. This is one of the oldest types of filter press. It is rather slow working and requires considerable labor, but


FEED INLET
WASH INLET
CLEAR LIQUOR
CLOUDY LIQUOR
FIG. 1
FIG. 2
SWITCH COCK CAN BE DIVERTED TO EITHER SIDE
CLEAR LIQUOR.
CLOUDY LIQUOR
FIG. 5.
FIG. 4.
FIG. 3.
SPERRY 42" FILTER PRESS.
D. R. SPERRY & CO.,
BATAVIA, ILLINOIS.

Fig. 143.

gives a dry cake containing from 10 to 25 per cent. moisture according to the nature of the material which may be pumped in until the press is full, by means of a pump or by forcing it through by compressed air. The last is the slower process, but necessary where the material acts on the pump. The pulp is first pumped in until the cells are properly filled and the cake is then washed by forcing water through it. The amount of wash water needed is relatively small, but depends upon the purity required in the insoluble material. Where very careful washing is required, it may be necessary to pulp the cake with water and filter and wash a second time.

(166) The press shown built by D. R. Sperry and Co., contains 50 recessed plates 42 inches in diameter, and has sufficient capacity to filter 24 tons blanc fixe (precipitated $BaSO_4$) in 24 hours, or at the rate of 1 ton per hour, leaving the pulp with a moisture content of 30 per cent. which is required in the trade. This would take eight cycles, the press taking 3 tons at one operation. The labor of two men would be required for 1¼ hours during each cycle in opening and closing the press. This press costs at this writing (1918) about $2300 f. o. b. Detroit, Michigan. Each complete set of filter cloths of No. 10 duck will cost about $167 purchased in rolls and cut in suitable lengths by the press attendants. In running on blanc fixe the first runnings will be cloudy and must be run over again. Power required is that necessary to operate the steam pump 7x4½x6.

(167) **Shriver Press.**—Various forms of the Shriver Press are shown in Figs. 144-153. The perforated screen surface is shown in 145, corrugated surface in 146 and pyramid surface in 147. Shriver presses use the pyramid surface for which 70 per cent. efficiency is claimed. The flap cock used is shown in 148 closed and 149 open. The thrust block quick opening device is illustrated in 150, the ratchet closing device in 151 and 152. For the center feed press the tools used and the screwed clip nut cloth fastener are shown in 153.



T. Shriver & Company,
Harrison, N.J.
36" C.F.O.D. 36 Ch. Press.—Capacity 23.3 Cu. Ft.

Fig. 144.



Fig. 145.



Fig. 146.



Fig. 147.

Fig. 148.

Fig. 149.



Fig. 150.



Fig. 151.



Fig. 152.



Fig. 153.

(168) In the Kelly filter, Figs. 154-159, the leaves are contained in a horizontal cylinder into which the liquid is pumped



f. 154.



Fig. 155.—The Kelly Filter Press.

The Kelly Filter Press consists of a pressure cylinder "A" for containing the mixture to be filtered; a traveling filter-carriage "B" mounted on four wheels and carrying the filter frames; the filter frames "C" covered with bags of filter fabric; a quick locking device "D," mounted on the head of the pressure cylinder; and a trussed iron frame "E" supporting the entire filter press.

To operate the filter press, the carriage "B" is run into the pressure tank "A" and locked by means of lever "3" which forces locking-rods "4" into U-bolts "5." The mixture to be filtered is then admitted through slime valve "10" and rapidly fills the cylinder, entirely submerging the filter frames "C." Owing to the pressure at valve "10," the liquid is forced through the filter cloths, depositing thereon a cake of solid material, through which all remaining liquid must pass. The filtrate now continues through outlet valves "6" to the storage tank. As the thickness of cake *increases*, the rate of filtration *decreases* until an *economical cake thickness* is reached. At this point, filtration is stopped, the locking lever "3" is reversed and the added weight of the cake causes the filter-carriage to return down the inclined tracks to the position shown. The cakes may now be removed by steam, compressed air, or in any desired manner.

The advantages possessed by this press are: ease of operation, uniformity of cake, and clarity of filtrate.

for which purpose a montejus or centrifugal pump is preferred. When the cakes are of the proper thickness the liquid remaining



in the cylinder is discharged and the wash water introduced. After washing, the cakes are run out on a carriage and the mate-

Fig. 157.

rial pushed off with a paddle. If a cloth is perforated, that leaf is closed by a cock provided for the purpose. The bag is then cut off and a new one slipped over the frame.

At present the Kelly filter is not used for acid liquids.

(169) Sweetland Filter.—In the Sweetland filter the leaves are first filled; the wash water then forces the excess sludge out and then washes the cake. This press requires more wash water and is more expensive to install, but because of ease of opening, dis-



Fig. 158.

charging and closing, is more economical to operate. This filter is supplied with all parts lead lined or of bronze but not in wood. Steam jackets are supplied for hot filtration.

The body is cylindrical in form, divided on the horizontal center line into two halves. The two halves are hinged together. The hinge shaft has eccentric bearings to receive the hinges of the lower half. Since the bearings of the lower half are eccentric and those of the upper ones are not, the compression on the

gasket at the back may be varied by simply turning the shaft. The front of the filter is closed and locked by means of a series of swing bolts mounted upon an eccentric shaft which rests in babbetted bearings along the front of the upper half of the filter body. This eccentric shaft tightens or loosens all swing bolts simultaneously by being turned through an arc of 90° at the same time the bolts are swinging outwardly. Figs. 160 and 161 show this filter open and 162 and 163 closed.



Fig. 159.

The main feed connection is at the center of one end (see Figs. 164 and 165), and a passage in the bottom casting distributes the feed uniformly. There are no flexible connections. An internal manifold pipe (see Fig. 165) with a series of nozzles opposite each leaf allows the operator to wash off any valueless precipitate and slide it out without opening the press.

The construction of the leaves is shown in Figs. 165 and 166. The sludge is forced into the filter at a pressure of 40 pounds, more or less, by means of a gravity pump or a montejus. The sludge rises in the press filling it completely and the valves which have been opened to allow air to escape are closed. The liquid now passes through the filter cloth and escapes through the outlet glass tubes, when the efficiency of each leaf may be continually watched, into the discharge pipe. The precipitate forms a nearly uniform coating on the cloth and then water is forced through until the cake is washed sufficiently. The cake is discharged by opening the filter and forcing air into the filters. When the precipitate settles rapidly it is better to use the



Fig. 160.



Fig. 161.



Fig. 162.

Sweetland rotatable filter shown in Fig. 167, in which the discs revolve constantly. A section of bronze trimmed lead lined filter is shown in Fig. 168.

(170) In the Moore filter the leaf is either flat or round and is dipped into the sludge. As suction is applied the liquid passes through the cloth while the precipitate forms an adhering cake.



Fig. 163.

This is washed by lifting it into a tank of clear water. Two waters are necessary as the first soon becomes fouled. Unless the sludge is stirred vigorously, it is densest in the bottom layers and the cake bridges over at the bottom layers of the tubes or plates. This causes incomplete washing and is one of the serious drawbacks of this type. The cake is also decidedly moist containing



Fig. 164. Sweetland Filter. Longitudinal Section.

one-third to one-half its weight of water. In this, as in the Sweetland filter, discharging is effected by admitting compressed air behind the cake when it slides off.



Fig. 165. Sweetland Filter. Cross Section.



Fig. 166. Sweetland Filter Cell.



Fig. 167



Fig. 168. Lead-Lined Sweetland Filter.

AMERICAN CONTINUOUS SUCTION FILTER



TYPE & SQ.FT.	DIA OF LEAVES	NO OF LEAVES	LEAF SPACING	FLOOR SPACE	SHIPPING WEIGHT	A	B	C	D
100	40 IN.	3	11 IN.	8X6 FT.	3000	5-9 1/4	3-3	6-2 1/2	4-11
150	40	6	11 "	9X6 "	4600	8-0 7/8	6-8 3/4	6-2 1/2	4-11
199	40	8	11 "	12X6 "	6300	10-3 1/2	8-11 3/4	6-2 1/2	4-11
250	40	10	11 "	15X6 "	8000	12-6 3/8	11-3 3/4	6-2 1/2	4-11
300	48	8	14 "	10X7 "	8300	10-7 1/2	8-11 3/4	7-1	5-7
400	48	10	14 "	12X8 "	11000	12-11 1/2	11-3 3/4	7-1	5-7
500	48	12	14 "	15X8 "	14000	15-3	13-8 3/4	7-1	5-7
600	48	13	14 "	20X8 "	17000	20-0	17-6 3/4	7-1	5-7

BOTH TYPES 8 & 6 LEAF FILTERS ARE FURNISHED WITH TWO SUCTION VALVES





Fig. 160



Fig. 170. American Filter.



Fig. 171. American Filter. Single Cell.



Fig. 172

(171) In the American Continuous Suction filter, Figs. 169-173, which like the Kelly and the Sweetland filter, is manufactured by the United Filters Corporation, each disc or wheel is made of eight segments clamped to the shafts by rods. The shaft has eight longitudinal shaft compartments (Figs. 169-171). At one end of the shaft is the driving mechanism for rotating the discs, at the other the valve (Fig. 173). The shaft revolves clockwise viewed from the valve end. The valve is conically ground and has eight ports corresponding to and connected with the longitudinal shaft compartments. Port No. 1 on the underside connects with the four submerged leaf sections. No. 2 connects with the wash water suction and dumping line accommodating the three upper left hand leaf segments. No. 3 admits compressed air into each segment as it passes the port. The precipitate in the sludge deposits as the segment moves through the pan. The filtrate discharges through the same opening from four segments in the sludge. As any given section lifts, the filtrate port closes and a wash water port opens and wash water is sprayed over the surface of the cake in very fine spray, the wash water having a pressure of 60-70 pounds.

The spray nozzles are adjustable and are placed near the periphrey of the moving discs. The washing is continued through 45 degrees. The moisture is then sucked out and the cake discharged by air pressure and deflectors shown in Fig. 165.

(172) In the Oliver filter shown in Fig. 174 the material is likewise formed into a cake by suction. The cake is washed by a water spray and then scraped off as the drum revolves. This apparatus gives a drier cake than the Moore filter and since it is continuous in operation has large capacity. It is expensive to install.

(173) The Portland filter, Fig. 175, resembles the Oliver filter

(174) Filter frames are of two types, the flush and recessed. The cake produced varies in thickness from 1 to 6 inches according to the material, being thicker as it is more permeable.



Fig. 173. American Filter.

(175) In the recessed type of filter the material is pumped in through an opening sometimes in the center, sometimes in a corner of the plate which may be either round or square. The cloth is held in place by a lock nut screwed down over the open-



Fig. 174.

THE OLIVER CONTINUOUS FILTER.

The vaccuous space 1, is covered with canvas protected by a wire winding on the outside. This space is connected with the air-pump by means of the pipes 28 and 29. The drum is slowly turned, in the tank 2, containing the pulp to be filtered, by means of the worm 14. The cake is washed by a water spray at 38, and is scraped off at 25.

1. Vaccuous space.
2. Steel filter tank.
3. Cast-iron pedestals.
4. Steel I-beam frame.
5. Manhole.
6. Cast-iron spider rim.
7. Channel steel arms.
8. Hollow trunnion.
9. Steel shaft.
10. Main bearings.
11. Stuffing boxes.
12. Worm drive gear.
13. Worm shaft.
14. Oilwell for worm.
15. Filter drive pulleys.
16. Highspeed wiring pulleys.
17. Filter drum.
21. Wood stoves for drum.
22. Section division strips.
23. Filter medium.
24. Wire winding.
25. Steel scraper.
26. Tailing apron.
28. Vacuum pipes.
29. Compressed air pipes.
30. Regrinding valve seat.
31. Automatic valve.
32. Adjusting lever for valve.
33. Vacuum connection.
34. Comp. air connection.
35. Discharge spray pipe.
38. Wash-water pipes.

ing. The pulp is forced in through the head of the press and the liquid passes through the filter cloth upon which the solid deposits

Fig. 175. Portland Filter.



Fig. 176. Side Feed Wooden Chamber Filter Press.

out through a cored opening into a side trough until a proper thickness has been attained. In some cases the recess is filled

LATEST IMPROVED VARNISH FILTER PRESS.



Fig. 177.—Varnish Filter Press.

full of material and the cake is not washed, as in compressed yeast manufacture. In other cases the supply of pulp is discontinued and is followed by wash water which displaces the mother liquor. The course to be pursued depends upon the material operated on.

(176) In the flush type the plates having a filtering surface alternate with the open frames filled from a cored lug at one side or at one or two corners. The discharge is through cored openings in the closed frame. The filtering surface may consist of a perforated screen or a corrugated or pyramid surface. Where acid liquids are to be filtered a press with wooden frames of the flush type shown in Fig. 176 must be freed. Fig. 177 shows a press used for filtering varnish.

Where wax or tallow is to be filtered cored openings for the circulation of hot water or steam through the frames are provided and where the liquid must be kept cold, as in filtering castor oil, cold brine is the circulating medium.

The capacity of filter presses is small compared with their cost and the labor charge high. They are commonly regarded as a dirty, sloppy necessity.

(177) Prominent makers of filter presses of the types enumerated are:

T. Shriver & Co., Harrison, N. J.
D. R. Sperry & Co., Batavia, Ill.
United Filters Corp., New York City.
John Johnson Co., 39th St. & 2nd Ave., Brooklyn, N. Y.
The Albright-Nell Co., Chicago, Ill.
Roberts S. Refield, 327 S. LaSalle St., Chicago, Ill.
Wm. R. Perrin & Co., Old Colony Bldg., Chicago, Ill.
Oliver Filter Co., Market St., San Francisco, Cal.
Industrial Filtration Corp., 115 Broadway, New York City.
Colorado Iron Works Co. (The Portland Filter), New York City.

(178) The amount of water remaining in the press cake varies from 10 to 50 per cent. according to the apparatus used, the pressure and the nature of the material. The closed pressure usually

gives the best results in this respect.[1] In a suction filter not more than 16 pounds at the best can possibly be obtained. In the positive pressure this is often increased to 120 pounds or even more.

(179) A material called Filtros, consisting of silica grains of various sizes cemented at 2600° F. with a fusible silicate has lately been put upon the market as a filtering material by the General Filtration Co., of 326 Cutler Bldg., Rochester, N. Y. This is supplied in plates and tubes of various sizes and grades. The proportion of voids in the material is claimed to be from 33 to 40 per cent. It is insoluble in acids and unaffected by chemicals which do not act on silica. It is manufactured with varying porosity to suit different conditions and has sufficient strength, a plate 12x12x1½ inches supporting a weight of 400 pounds without fracture.

(180) The same company manufactures a filtros wheel composed of filtros plates. This is divided into eight segments each having two compartments. Each compartment is completely isolated from the others. This is operated as a vacuum filter while the compartments are immersed. One revolution in 3 minutes is about the rate best suited for a lime sludge with 36 per cent. solids and in this time about a ¾-inch cake will be formed. As the cake emerges from the sludge it may be washed and is then discharged by about 3 pounds air pressure upon an apron above the tank. About 4.5 tons per hour of dry solids are produced, the cake containing about 40 per cent. moisture. The Kieselguhr Co. of America, manufacture a similar material called Filter-Cel.

(181) The exact method to be used in separating precipitates must in each case be a special study. What answers in one case will not do in another. Sugar crystals and like material goes direct from the centrifugal to the drier. With precipitated calcium sulfate a better method would be to partly dry on a vacuum filter followed by the use of the centrifuge.

"As a general proposition, the centrifugal is the most economical device for extracting and washing crystals which form a por-

[1] A recent paper by E. Hatschek is noted (*J. Soc. Chem. Ind.*, 39, 226T) as a good illustration of the dogmatic method. Some, at least, of the statements made appear to be incorrect. (See also *Chemical Age*, 3, 67, 1920.)

ous mass. Slimy materials which filter slowly and require a high pressure can usually be handled more economically in a filter press for the following reasons: A moderate sized press may have 200 sq. ft. of filtering surface, where a large size centrifugal would have but one-tenth of this. The pressure per sq. in. of a wall of liquid on the inside of the basket of a large centrifugal is low, say 30 pounds per sq. in. The pressure in the centrifugal basket is caused by running the machine at high speed. In a filter press much higher pressures can be maintained with a slow moving pump and the expenditure of a small amount of energy.

"While these two classes of apparatus have rather distinct fields there are exceptional conditions to be met which determine the type of apparatus to be used. In the case of some fine slimy materials which cannot be filtered a centrifugal with a solid bowl has proved to be a successful means of precipitating the solids quickly. One of the materials treated in this way is fine clay used in the manufacture of lead pencils. Such solids can be washed by diluting and reprecipitating.

"The amount of moisture remaining after centrifuging slimy materials varies over very wide limits. After running for a half hour or more some materials will remain a thin slime, so that it is necessary to make a test in practically every instance to determine what results can be expected. Then the same materials made by different processes, or under different operating conditions give different results in the centrifugal. An instance of this is the so-called "false grain" in sugar which sometimes makes the drying of sugar difficult as explained under Section 224."[1]

The November, 1921, number of the *Journal of Industrial and Engineering Chemistry* contains a symposium on filtration which the student should read carefully.

[1] Leslie Griscom.

CHAPTER XIII.

TANKS.

Containing vessels in the chemical industry are commonly spoken of as tanks and may be made of various materials, the cheapest being made of wood.

(182) Wooden Tanks.—Large round wooden tanks should always be placed vertically so that the bottom pressure is supported by the foundation. With a tank of, say 12 feet diameter, placed horizontally and filled with liquid, the pressure will force the ends out of the croze and finally destroy the tank. The ends may in such cases be supported by braces across the ends tied together by rods through the tank, but this is expensive and not very satisfactory. Tanks are best made round as the heavy pressure can be perfectly supported by hoops as shown in Fig. 178.

(183) Cypress gives no taste to cider vinegar or fruit syrups and is best for hot acids and liquids. Douglas fir is used in vinegar plants. Poplar is best for whiskey, as it is close grained and lasts well. It does not last well with other liquids. Yellow pine containing as much resin as possible is best for strong cold acids and chemicals. White pine is best for water, brine and pickle.

It is well known that strong acids and some salt solutions act on wood. Weak acids are less vigorous and attack first the lignin so that the cellulose fibers are set free and the wood disintegrates. At high temperature this action is more rapid. (See also *Met. & Chem. Eng.*, 18, 528.)

SIZES OF TANKS AND PARTS THEREOF.

A. Thickness in rough.....	1½"	2 "	2½"	3 "
B. Finished thickness of staves.....	1⅜	1¾	2¼	2¾
C. Depth of croze.....	⅜	½	⅝	⅝
D. Width of croze.....	1⅜	1⅜	2	2½
E. Length of chime.....	3⅜	3⅜	3½	3⅝
G. Finished thickness of bottom.....	1⅜	1⅞	2⅜	2⅞
H. Thickness of beveled edge.....	1"/₁₆	1"/₁₆	2"/₁₆	2"/₁₆
J. Thickness of bevel.....	⅞	⅞	⅞	⅞
K. Length of bevel.....	1⅜	1⅜	1⅜	1⅜



Fig. 178. Wooden Tanks.

Capacity in Gallons		Taper 1 inch to 1 foot	
No.	Inside diam. ft.	Inside depth ft.	No. of hoops
1	3	2½	3
8	4	3	3
16	5	4	4
23	6	4	4
40	7	8½	7
55	8	8½	7
67	9	8½	7

Large tanks are shipped knocked down and must be set up where they are to be used. They should have concrete or post and wooden sill foundations and since there is sure to be some leakage, this should be collected in a sump. One cement floor with one sump provided with a proper pump answers for a number of tanks. Where acid liquids are in use, the collecting floor should be covered with 1½ inches of Johns-Mansville acid proof mastic or some similar material.

(184) Hoops for Tanks.—Hoops for wooden tanks are almost always made of round steel. This form has the great advantage that the side next the tank can be inspected and painted when needed. Flat hoops may rust very badly on the inside before this is detected and must be taken off entirely before being painted. If the tensile strength of the steel used is 60,000 pounds per square inch, the allowable strain is 15,000 pounds. The allowable strain for

½	inch	hoops	1,650 pounds
⅝	"	"	3,315 "
¾	"	"	4,230 "
⅞	"	"	6,090 "
1	"	"	8,355 "
1⅛	"	"	10,350 "

To show how the hoops should be put on let us suppose we have a tank 12 feet in diameter and 24 feet high with hoops of ¾-inch steel with tensile strength and factor of safety as above.

(185) The pressure exerted by water is due to its weight or 62.425 pounds per cubic foot. On the bottom of a 24-foot tank the pressure would be $62.425 \times 24 = 1498.2$ or for a 12-foot

(188) **Rectangular Tanks or Vats** are troublesome since they cannot be kept as tight as round ones. When it is necessary to use them they must be drawn up in all directions by means of bolts run through the wood as shown in Fig. 179. A cheaper clamp, fastening on the outside of the wood is also shown in Fig. 178.

(189) In 1902 I saw a large number of cheap tanks at Daggett, Cal., used for the evaporation of boracic acid solutions by means of solar heat. Since these tanks may be useful occasionally in other localities, I have thought it well to describe them: A level piece of ground was chosen which was cleaned of stone and rubbish, covered with a few inches of sand carefully leveled. This was divided up into squares or rectangles of the size of tank wanted by stout stakes driven into the soil. Upright rough boards 1 foot wide were then nailed inside the stakes. A layer of tar paper with the edges overlapping was then spread on the floor and the ends and edges carried up over the sides and tacked fast. A layer of hot pitch was then painted over the tar paper and another layer of tar paper laid over it so as to break joints. When three or four layers of tar paper had been put on in this way the tank was pronounced finished and the liquid run in. Such tanks can probably in some cases be used for crystallizing, but must, of course, be carefully tested in each case before laying out expensive installations. In some cases it is necessary to shovel out the crystalline contents of such tanks. To protect the bottom, gratings of wood, perforated metal or coarse wire cloth may cover and protect the floor. Concrete tanks usually require no such protection.

(190) **Stoneware Tanks** like 180 are furnished of capacity from 130-1050 gallons and stoneware pots with straight sides up to 1125 gallons.

A safety device for preventing sticking in stoneware stop-cocks to be used with these tanks is shown in Fig. 181.

Fig. 180.



Fig 181.

(191) **Concrete Tanks** are more desirable for crystallizing, where it is possible to use them, since they lose heat more rapidly than wood. They are best made with round reinforcing, inside a rough wooden frame with steel hoops on a concrete floor provided

with a sump and pump. Inside this another frame of ½-inch stuff is placed. About 6 inches on one side is left open, having wooden reinforcements on each side. Across this opening stretch turnbuckles. This frame is so dimensioned that a 3- to 6-inch opening is left between the inside and outside frame, which is filled with *carefully rammed* concrete made of sharp sand and cement. The opening on the inner frame is closed with a removable board. When the cement has set, say in three or four days, the board is taken out; by turning the turnbuckles the inner frame is drawn together and may be removed and again used. The outer framework is also removed.

(192) Rectangular concrete tanks may also be built, but are not very strong unless braced on the outside. Where running water is available, crystallization may be hastened by using pipe as the reinforcement in such tanks, placed near the inside, and running water through these pipes. Crystallizing tanks of whatever material are best made with hopper shaped bottoms provided with a drain pipe and drop door so that the crystals may first be drained and then shoved through the open door into a centrifugal. This decreases handling materially. Browne[1] calls attention to the fact that concrete tanks should be built of slow setting cement, which must stand the pat test. It is best mixed with crushed granite. A tank 3 feet wide, 9 feet long and 2 feet deep costs about $12. It may be built on a wooden floor on tar paper and should have a 6-inch bottom and 4-inch sides. The inner frame of such a tank is made by putting square pieces in the corners and fastening the side boards with angle irons. When these are unscrewed, the boards drop in and are removed. Caustic or chloride does not act on cement nor does chlorine. It may be coated with hot paraffine, tar or asphalt varnish or mastic to prevent action by acid liquids.

(193) A good method for constructing cement tanks is to build a framework of expanded metal pipe or rod and then cover this with cement as plastering is done. This makes a cheap and efficient tank. Such tanks may be used, for example, as containers for nitric or sulphuric or mixed acids. Dr. Arthur Lackman,

[1] *Electrochemical Industry*, Vol. I, p. 723, Apr., 1903.

(*Trans. Amer. Inst. Chem. Eng.*, 8, 110) describes a method of making cement tanks only 2 inches thick which are, however, very expensive. A form is first made of iron bars, spaced approximately 1 foot apart and covered with wire cloth. The paste made of three sand and one cement is then plastered on in layers about one-half inch thick, first inside then outside until proper thickness is used. The tanks were 10 feet by 10 feet and were used for fermenting wine. Wine has a tendency to make cement waterproof. Seepage may be corrected by soaking with lime and water and allowing carbonation to take place. Attention is also called to two papers on the building of cement tanks using the apparatus controlled by the Cement Gun Co., of Allentown, Pa., which appeared in the *Engineering News* of November 9, and the *Engineering Record* of October 21, 1916. In this way the tanks of large diameter subject to considerable heat may be built with very thin walls. It is stated that a new material especially adapted for this purpose has recently been put on the market by the Trussed Concrete Steel Co. It consists of rods netted together with wire on the order of expanded metal with larger longitudinal members which have the effect of hoops.

(194) Wooden, cement or steel tanks lined with brick laid in melted sulphur or in Duro cement are often used. The latter cement seems to consist of silicate of soda blanc fixe and silica. It is washed with 60° Bé. sulphuric acid to set it properly, applied with a spray or rubber brush.* Duro brick and the Duro cement are supplied by the Harbison-Walker Co., of Pittsburgh.

(195) **A Pachuca or Precipitating Tank** is shown in Fig. 123. It is made of wood the bottom being filled with cement to form an inverted cone, which may be lined with wood if necessary. The air jet is used for mixing the precipitating liquids. One or both the materials may be added in the dry state. For example, if dry lead acetate and sodium sulphate be mixed with the proper amount of water in the pachuca and properly blown, a paste of any desired thickness consisting of a strong solution of sodium acetate and a precipitate of lead sulphate may be obtained. This method often enables us to get strong solutions and avoid evaporation.

(198) The Hauser-Stander Tank Co., of Cincinnati, Ohio, have published a catalog containing a large number of tests on the action of various substances in solution upon wood. It will be impossible here to give all the information to be found there, to which the student is referred. In part the tests also included the action of the wood upon these solutions. The following summary of results may prove useful:

(1). "All woods expand in cold aqueous solutions. This increase in dimensions is partially lost when the wet wood dries in the air. Some woods, with nitric acid and the alkalis, show shrinkages after drying. With hot solutions there is a marked tendency toward shrinkage, but usually this does not occur until after the wood has dried. This tendency is least shown by cypress, pine and redwood.

(2). "The cold organic liquids produce neither swelling nor shrinkage, but the hot liquids cause a shrinkage in all woods, and this takes place while the woods are still in the fluids.

(3). "In cold aqueous solutions the permanent swelling is greater than in water.

(4). "Redwood shows the greatest expansion and oak the least. Oak and maple show shrinkage very frequently. Cypress, pine and fir show intermediate expansions. Cypress and pine never show shrinkage in cold aqueous solutions and only seldom in the hot solutions. The following table gives briefly the result of some of the tests:

In this Table SS means slightly soft; S, soft; V, very; H, hard; B, brittle; P, pliable; SP, slightly pliable; Sh, shrunken; Ex, expanded; Cl cracked lengthwise; W, warped; Di, distorted; Gr, grain raised; Fz, fuzzy; CH, charred and Shd, shredded.

TABLE.

PHYSICAL EFFECTS OF CHEMICALS UPON WOOD

(After one month in cold and eight hours in boiling liquids)

	Cypress		Fir		Pine		Redwood		Maple		Oak	
	Cold	Hot	Cold	Hot	Cold	Hot	Cold	Hot	Cold	Hot	Cold	Hot
H_2O (Water)												
CH_3COOH (Acetic Acid) 5%												
25%												
50%	SS		SS				SS					
glacial	SS		SS				SS					
HCl (Hydrochloric Acid) 5%				S								
10%	SS	SS	SS	S			SS,VB	VS,B		SS		
25%	SS	VS,VB	SS	VS,VB	SS	S	SS,VB	VS,B		S		SS
50%	S,Cl,SB		SS,Cl		SS		SS,VB	VS,VB,Ch	S,B	VS,VB	SS,SB	VS,VB
conc. (a)	VS,B,Cl		VS,B,GR		VS,B,Cl		S,VB		S,B		S,B	
							VS,VB		VS,B,Sh,Cl		VS,B,Di,Hx,Cl	
H_2SO_4 (Sulphuric Acid) 1%	SS	S	SS	S			SS,B	VS		SS		W
5%	SS	S	SS	S	SS	SS	VS,B	VS.B		S	SS	Ss
10%	SS	VS,P	S	S	SS	VS,VB	VS,B	VS,VB	SS,B	S	SS,SB	SS
25%	SS,SB	VS,VB	S,B	VS,VB	SS		VS,VB	VS,VB,Ch	VS,VB	VS,VB	SS,B	VS,VB
HNO_3 (Nitric Acid) 5%		S	SS	VS		S,Shd	VS,VB	VS,VB	SS	VS,Shd	SS,GR	S,Cl,Shd
10%		VS,Shd	SS	VS,Shd	SS	S,Shd	VS,VB	VS,VB,Cl,Shd	SS,SB	VS,Shd	S,B,GR,Sh	S,Cl,Shd
25%	S,B	Shd,VS	VS,B	VS,Shd	SS,B,Cl	S,Shd	VS,VB	VS,VB,Cl,Shd	S,BB,Sh	VS,Shd	VS,VB,GR,Sh,Cl	S,Cl,Shd
NaOH (Sodium Hydroxide) 1%		SS		Sh,GR			VS,W,SB,GR	S	Cl	Sh	Sh,Vh,Di	Vh,Sh,Di
5%		SS	SS	Sh,GR			VS,SB,GR	S	Sh	Sh	Sh.VH,Di,GR	Vh.Sh,Di
10%		SS	SS,GR	Sh,GR	SS	VH,Sh,Di,GR	VS,GR,P	S,Sh,Di,GR	Sh,GR,W		Sh,Vh,Di,GR,W,P	Vh,Sh,Di,GR
25%	SS,P	SS	SS,GR,P	GR	SS	Vh,GR,W	SS,GR,P	S,Sh,Di,GR,B	Sh,GR,SS,P	W,GR	SS,GR,W,P	WH,GR
Na_2S (Sodium Sulphide) 5%	SS		SS									
20%	SS		SS				S,P,B					
$NaHSO_3$ (Sodium Bi-Sulphite) 10%							S,P,B				SS,GR,P	
25%											SS,GR,P	
Na_2CO_3 (Sodium Carbonate) 5%							SS					
20%		SS		GR			SS					
$Ca(OH)_2$ (Calcium Hydroxide) filtered					GR			S				Sh,GR
10% susp								S				Sh,GR
$Ca(ClO)_2$ (Bleaching Powder) filtered	SS,FZ,GR		SS,FZ,GR		FZ		GR		GR		GR	
5% susp	SS-FZ		SS,FZ		FZ		SS					
NaCl (Sodium Chloride) 10%							S,GR,B,Sh,FZ		SS,FZ,Sh		GR,FZ	
25%				SS			S,GR,B,Sh,FZ		SS,FZ		GR,FZ,SP	
$CaCl_2$ (Calcium Chloride) 10%				SS			SS,SB	SS,SB				
25%							SS,SB,GR	SS,SB				
Turpentine	SS		SS				SS					
Linseed Oil	SS						SS					
Cottonseed Oil Fatty Acids				SS			SS	SS				
				SS			SS	SS				

(a) Effect of concentrated hydrochloric acid was recorded after only one week's exposure.

CHAPTER XIV.

EVAPORATION.

(197) The simplest and cheapest evaporation is that brought about by the sun and wind. Illustrations are found in the separation of salt from salt water, as in Solomon City, Kansas (*Univ. Geol. Survey of Kansas*, Vol. VII, p. 68, 1902); Salt Lake City, Utah (*Sc. Amer.*, Vol. CXV, p. 550, 1916), and San Diego Bay, Southern California (*Met. & Chem. Eng.*, **16**, 317, 1917). At the place last named the gross annual evaporation is 60 inches, the precipitation 10 inches, and the net evaporation 50 inches. At Solomon City the gross annual evaporation is much less and the precipitation heavier. The vats are therefore provided with movable covers which shed the rain and are run off in fair weather.

(198) At Nauheim, Dürrenberg, Rodenberg and Schönbeck, Germany, and at Moutiers in France, where somewhat weak salines occur, Gradirhauser consisting of scaffolds filled with thorn wood (*Prunus spinosa*) and built in the direction of the prevailing wind have been in use for many centuries for evaporating the salt water. In good weather about 60 kilos of water are evaporated in 24 hours for every square foot of surface (*Thorpe's Dict.*, Vol. V). At Nauheim 2000 tons of salt are made annually from salt water concentrated in this way.

(199) Brush racks for evaporating a dilute solution of boracic acid have also been in use at Daggett, Cal. (See *The Saline Deposits of California, Sacramento*, 1902, p. 57). High winds, high temperature and low humidity prevail here and the surface evaporation sometimes amounts to an inch in 24 hours.

(200) Fig. 182 shows an arrangement for evaporation of sprayed salt solutions. A considerable part of the evaporated salt deposits at *H* and is removed through side doors not shown. Success with such an apparatus can only be obtained by careful preliminary study of a small model apparatus. In general it may be said that it is much easier to create such a salt dust than to settle it. The motor *A* should be a steam turbine since this admits of accurate speed regulation, and the air should be driven through

ATOMIZING EVAPORATOR.



A. Compressor motor.
B. Rotary air compressor.
C. Air pressure tank.
D. Montejus tank for solution.
I. Atomizing tower.
J. Cover for tower.
K. Down shaft to salt chute.
L. Collecting flume.
E. Heater.
F. Fan.
G. Hot air duct.
H. Spray nozzle.
M. Conveyor belt for gathering salts.
N. Air pipe to spray nozzle.
O. Solution pipe to spray nozzle.
P. Air pipe to mounting.
Q. Pipe from solution storage.

Fig. 182.

a fire, the hot gases being used directly after settling, or producer gas or oil may be burned.

(201) The same idea may be used, minus the spray, in a tower filled with chemical brick checker work, the hot gas passing up and the liquid down the tower.

(202) The simplest direct evaporator is a cast iron pot supported over a fire, one or more pots being used over each fire. It is better always to have a brick combustion chamber and then lead the fully burned gases under the pots, since metal surfaces chill the gases and give incomplete combustion. Instead of pots we may use shallow rectangular pans made of sheet iron and the hot fire gases may be lead over the surface or first under the pan and then over the surface of the liquid to be evaporated. Large flues like those of a Cornish boiler may also be built into the evaporating pan. Where direct heating of this sort can be used much less fuel is needed but the efficiency of the fuel, obtained in this way, even under the most favorable conditions seldom exceeds 80 per cent. of theory.

(203) In many cases the evaporation must be carried out in lead lined vessels further reducing the efficiency and often preventing the use of top heating. A serious difficulty often encountered is the formation of adhering crusts which are troublesome to break off and cause heavy additional expense for operation and repairs. For these reasons it is often necessary to resort to indirect heating by means of steam lead in pipes through the liquid to be evaporated or through steam jackets surrounding the vessels.

(204) The best results that can be expected from direct heating are about eight water evaporated to one of fuel used, but nothing like this efficiency is usually obtained. Thus in the salt manufacture as carried on in 1892 (See *Mineral Industry* for that year, p. 418), the consumption of fuel per barrel of salt (280 pounds) was one-fifth to one-fifteenth ton. If we allow three parts water to one salt we get an evaporation of 3-1 to 5½-1. In steam boiler practice it is customary to call 10 square feet of heating surface the equivalent of 1 horse-power, which under normal condi-

tions is supposed to be able to evaporate 34.5 pounds of water per hour from and at 100° C.

(205) The evaporating capacity of any apparatus depends upon a number of factors. In ordinary evaporation from a surface exposed to the air, evaporation is much more rapid if a current of air passes over the liquid, and the drier the air, of course, the more rapid the evaporation. Where the liquid to be evaporated is not corrosive, the best practice is to heat it to the boiling point in boilers or pipe manifolds placed next to the stacks and discharge from the boilers or manifolds into open evaporating pans or upon revolving drums with scrapers. The particular practice to be followed must depend altogether upon the properties of the substance in solution.

(206) The arrangement of the pans for the finishing operation is best in cascade, the liquid passing from the upper pan by overflow spouts into those lower down and the finished salt being lifted from the lowest pan into a drainer or run into crystallizers. Since this apparatus is liable to develop leakage it is imperative that all parts be easily accessible for repairs. Cast iron pans or pots suitable for such evaporation are made for caustic or other liquids, and for muriatic acid pans up to 12 feet in diameter. For high temperature work they should be supported by the rim so that they may be free to expand and contract. A supporting central pedestal is sometimes necessary when the kettles are very deep. The making of such large castings should be entrusted only to experienced hands. These pots are also supplied with pot and jackets cast in one piece.

(207) For shallow pans of sheet iron or steel, the car building works have machinery capable of pressing them of any desired size and shape. Smaller shops can build them out of sheet metal by cutting square pieces from the corners and bending up the sides and melting the edges together with oxyacetylene torch.

(208) Steam Heated Seamless Cast Iron Pans are made by the Sowers Mfg. Co., of Buffalo, N. Y. Fig. 183 shows such a kettle with legs made in sizes of 5 to 125 gallons. The same kettle cast with lugs may be had in sizes of 150-800 gallons. These

Fig. 183.



Fig. 184.



Fig. 185.





Fig. 186.

Fig. 187.



A	B	C	D	E	F	G
2"	2"	4½"	11⅛"	13⅜"	6½"	5"
3"	3"	4½"	12⅜"	15⅜"	8"	5"
4"	4"	5½"	14⅜"	17⅜"	9"	10"
5"	5"	6"	15⅜"	19"	10	10"
7"	7"	7"	18⅜"	22"	11½"	10"

Fig. 188.



A	B	C	D	E	F	G
2"	2"		6½"	9⅜"	2½"	5"
3"	3"		7⅜"	10⅜"	3"	5"
4"	4"		7⅜"	12⅜"	4½"	5"
5"	5"		13⅜"	19"	5½"	10
7"	7"		13⅜"	20⅜"	7½"	10

Fig. 189.



Fig. 190.

kettles are fitted with outlets to suit different uses. In Fig. 184 a flanged sleeve is screwed into the inner shell of the kettle and the joint between the bottom of the kettle and the top of the outlet flange is machined to fit tightly at 150 pounds pressure. In Fig. 185 the outlet is necessarily placed to one side of the center. Fig. 186 outlet is Fig. 184 with boss on bottom to which a gate is fitted. This is not suitable for thin liquids. Fig. 187 has a butterfly valve flush with inside of kettle and is used only in kettles equipped with bridge type mixers. Figs. 188 and 189 show other styles to be had.



Fig. 191.

Fig. 190 shows a bracket type agitator, and Fig. 191 a propeller screw agitator. Fig. 192 shows a 100-gallon standard type vacuum pan and Fig. 193 a 200-gallon vacuum pan with overhead drive, sweep agitator save all and jet condenser pump.

(208) Vacuum Evaporator.—"If steam at five pounds pressure is introduced into the steam tubes of an evaporator in which the liquid is allowed to boil at the atmospheric pressure the temperature difference between this steam and the boiling liquid (if the latter has the boiling point of water) is about 16° F. If, how-



Fig. 192.

ever, a vacuum of 25 inches is maintained above the liquid to be evaporated the temperature difference is about 95° F. Thus for a given vessel six times the evaporation can be accomplished in a given time, or for a given amount of evaporation the heating surface in the vessel may be one-sixth the size." (*J. Franklin Inst.*, **166**, p. 249, 1908). With a Dopp cast iron 300-gallon vacuum pan

with heating surface of 17.34 square feet the following evaporation was obtained in an hour:

FEED AT TEMPERATURE OF VACUUM.

Vacuum	Steam pressure in jacket 80 lbs.	120 lbs.
24 in.	44.37 gal.	51.59 gal.
26 in.	49.50 gal.	56.89 gal.



Fig. 193.

Where copper or brass is the heating surface a higher rate prevails and with lead a lower. Thus with round copper tubes into

which the steam is led the coefficient of transmission of heat in calories per square meter per hour for steam and water is $K = \frac{1900}{dl}$, where d is the diameter of the tube and l the length in meters. For wrought iron pipe this value is multiplied by 0.75, for cast iron and for lead 0.45 (Viola, *Met. & Chem. Eng., X*, 31, 1912).



Fig. 194.

(210) A single effect vacuum evaporator such as the Zaremba evaporator, shown in Fig. 194, has essentially the same construction as a tubular boiler except that steam is passed through the



Fig. 195.



Fig. 196.

tubes instead of fire gases. The Buffalo Foundry & Machine Co., build a horizontal tube evaporator shown in Figs. 195, 196 and 197. This is intended especially for the evaporation of non-foaming liquids and is made in two sizes 96 inches and 114 inches diameter with a range of heating surface from 590-2460 square feet. For concentrating liquids, such as caustic soda to high densities they also furnish a special form of evaporator shown in Fig. 198. For caustic the apparatus, including the tubes, is made entirely of cast iron. The tubes are 4 inches in diameter and are placed close together. Steam is supplied by small tubes



Fig. 197.

placed inside reaching to their ends. Care has been taken to reduce the number of joints and to protect them by special gaskets. This is built in four sizes with 110-660 square feet radiating surface.

(211) Multiple Effect.—"Suppose we had three single effect evaporators *A*, *B* and *C*, of the same size, each with an independent surface condenser and air pump. *A* takes exhaust steam at a temperature of 225° and delivers vapor to condenser *A* at 195°. *B* takes steam at 195° and delivers its vapor to condenser *B* at 165°. *C* takes steam at 165° and delivers vapor to condenser

C at 125° (Fig. 199). In this case excluding radiation and other losses, we would require for each pound of evaporation 1 pound of steam for producing the vapor, and about 25 pounds of cool



Fig. 198.

water for condensing it. But why not simplify our apparatus by rearrangement as follows: Eliminate condenser *A* and substitute for it the heating surface of single effect *B*—that is, let the vapor



Fig. 199. Multiple Effect.

from single effect *A*, take the place of the 195° steam previously fed into single effect *B*. In like manner let the vapor from single effect *B* be condensed in the tube of single effect *C*, while the vapor from the latter is condensed in condenser *C* as before. With our new method of operation the temperature difference in each effect is the same as before, so also is the amount of work done, but we are feeding steam into effect *A* only, and are injecting cold water into condenser *C* only, and are using but one-third as much of each as in the first case. Furthermore, we have discarded condensers *A* and *B*, together with their respective vacuum pumps. In the new dispensation we are working under the multiple effect system—that is, we have converted our three single effects into one triple effect thereby increasing our evaporation to 3 pounds of water per pound of steam used, and decreasing our water consumption from 25 pounds to about 9 pounds per pound of evaporation, the amount of evaporation produced being practically the same in both cases. The theoretic steam economy of the multiple effect, as stated above, is modified by a number of conditions, chief among which is the initial temperature of the liquor fed and the disposition made of the heat contained in the condensation from the various bodies. Ordinarily the number of effects used does not exceed four, but for special purposes as many as seven or eight effects can be used advantageously; it all depends upon the circumstances.

"The pumps necessary for operating the multiple effect consist of a vacuum pump for removing the air and other non-condensable gases from the condenser, a tail pump to withdraw the finished liquor from the evaporator, and condensation pumps to draw away the condensation from the steam chests operating at less than atmospheric pressure. As the steam exhaust from these pumps is used in the evaporator their operation costs practically nothing. In such circumstances to use motor driven pumps means a loss in economy.

"All forms of vacuum apparatus call for the use of a condenser in which the vapor coming from the last pan is condensed by contact with cold injection water. In the wet system the air and gases present are entrapped in this warm mixture of condensed

vapor and injection, the entire mass being withdrawn from the system by a wet vacuum pump discharge. In the dry system of condensation the condenser is made much larger and is mounted sufficiently high (about 34 feet) to allow the water discharge to flow into the hot well by its own weight against the pressure of the atmosphere. In this case air and non-condensable gases only are handled by the vacuum pump. In the surface condenser, which is practically a reversed evaporator, the vapor is confined to one chamber and the cooling water to another, being separated from each other by a tubular brass cooling surface.

"As a rule the amount of water required varies from 25 to 30 pounds per pound of vapor condensed. One of the great advantages of the wet system lies in the fact that such a condenser can generally be made to draw its own supply of injection water from a neighboring stream or tank. The dry system requires a circulating pump. There is a large supply of warm water at about 110° F. coming from the condenser, which can frequently be used to very good advantage. The first pan delivers a quantity of distilled water at 212°, equal to the amount of steam used; this is preferably returned to the boiler. From the condensation pumps another supply of warm water is obtained at a temperature between the two former.

"The steam pressures ordinarily carried vary from 5 pounds down to atmospheric pressure; the vacuum from 23 to 26 inches.

"There are two ways of handling the concentrated liquor. One method, 'batching,' calls for the carrying of the concentration of the entire body of liquor in the final pan to the proper finishing density, after which the heavy liquor is removed by the tail (or magma) pump. In the 'continuous' method the heavy liquor settling in the bottom of the final pan is withdrawn by the pump while the pan continues in operation." (Zaremba Co., Catalog, 1916.)

(212) It is evident that the heat in the multiple effect does double to quadruple work according to the number of effects. Theoretically it should be possible to use the heat over and over again indefinitely, but in practice a limit is found, due in part to

the loss of heat by radiation and in part to the increased cost and complexity of the apparatus. "In the salt vacuum pan the evaporation per pound of coal guaranteed is 6 pounds in the single effect, 12 pounds in the double effect, 18 pounds in the triple effect and 24 pounds in the quadruple effect from brine of 95 salinometer." (Letter of July 16, 1918, Manistee Iron Works, Manistee, Mich.)

(213) It is best that each pan have its own vacuum pump and that each multiple effect have its own condenser. In calculating, the evaporative power of the coal for raising steam for the pumps and for pumping water must be added to that as steam supplied direct to the first vacuum pan.

Fig. 200.

(214) The Zaremba Crystallizing Evaporator shown in Figs. 200-202 is designed for the evaporation of solutions that tend to encrust the heating surface. The circulation of liquid is very rapid and the tubes may be readily cleaned mechanically. Fig. 200 shows the heating surface. The circulation is up through the tubes and down through an annular space between the steam chest and the outer shell. The separated crystals drop into the

cone below the steam chest from which they drop into the salt filter and are removed through the door in front. Fig. 202 shows this apparatus in double effect. The construction is such that



Fig. 201.

the liquid in rising has a velocity of 30 feet per second while because of the greater area of the annular space the drop has a velocity of only one-tenth this so that the crystals readily settle

Fig. 202.

out. The salt filter has a sight glass and when filled with crystals these are washed with weak liquor by closing and opening appropriate cocks and the crystals are then removed. Any number of effects may be used and are so connected that one may be cut out without interfering with the others. As each effect operates at a different temperature it is possible to effect many separations.

(215) In the Lillie evaporator the steam tubes are horizontal and the liquid to be evaporated is showered over them. In the Kestner evaporator the liquid runs into upright tubes 23 feet long surrounded by steam. Bubbles of steam form and mount the tubes carrying a thin film of liquid which evaporates rapidly. The foam at the top strikes against the vanes of a centrifugal separator which separates steam and liquid completely. The liquid evaporates with tremendous rapidity and is exposed to the heat for so short a time as not to injure organic dissolved material, such as cane sugar, citric acid, tartaric acid and glue. Any deposit, such as gypsum, is blown out and settles in the pans. The Yaryan apparatus has horizontal tubes for film evaporation.

(216) **Acid Linings.**—Fig. 203 shows a method of constructing acid proof linings for vacuum evaporators used by the Zaremba Co. The difficulty of evaporating acid liquids by multiple effect lies chiefly in the difficulty of heating. If metal pipes are used they are quickly corroded. If enameled pipes are used they are very poor conductors of heat. For some acid liquids containing nitric or sulphuric acid duriron or one of the other iron silicon alloys may be used but these alloys are very hard and very brittle.

(217) By using steam at 100 pounds pressure in an evaporator constructed of steam pipes opening into the steam chest at the bottom and closed at the top the Zaremba Company have been able to concentrate caustic soda and other liquids of high boiling point so that solidification takes place on cooling.

(218) Another form of multiple effect, the Söderlund-Boberg evaporator, has recently appeared which if the statements made in its behalf are verified bids fair to revolutionize this branch of the industry. The apparatus is shown in single effect in Fig. 204

The evaporator comprises a tall shell *A*, the greater portion of which is taken up by the calandria *B* to the upper end of each tube *C*, of which is fitted a ferrule with a distributing nozzle *E*. The liquid which is raised by a pump *F* from the lower portion *G* of the shell *A* is fed into the tray *H* formed at the top of the calendria *B*, and passing through the nozzles *E* in the ferrules *D*, is spread as a thin and rapidly moving sheet over the inner surface of the tubes *C*.



Fig. 203.

The liquid collects again in the bottom of the shell, to which fresh liquid is automatically admitted by a constant lever feed *I*, to be returned by the pump *F* to the distributing tray *H*, while the steam given off by the films in the inside of the tubes and sep-



Fig. 204.

arated from the spray by the baffles *J* in the base of the shell and by the tangential disposition of the steam entry to the steam main *K* leading to the compressor *L*, passes to the compressor, having

the required quantity of make-up steam added to it on its way by a pressure controlled automatic steam inlet *M*. The compressed steam enters the space around the tubes *C* and condensing on them is drained off as hot water through a steam trap *N* connected to a counter current regenerator *O* through which the cold feed flows to the automatic feed valve *I*. The small quantity of non-condensable gases which is not driven off from the feed liquid through a blow-off *Q* at the hot end of the regenerator *O* is cleared out of the steam space by periodically blowing off a little steam or continuously allowing a small leak of steam out of this space. The compressor is driven by a constant speed by spur gear from a shaft belt driven direct from a gas engine, working for instance in connection with a small suction gas plant or by an oil engine. The exhaust in either case passes to a small boiler generating the make up steam.

In this apparatus, it is asserted, 240 pounds of distilled water may be obtained for every pound of coal burned.[1]

(219) Evaporation of Acid Liquids.—Liquids containing free hydrochlorine acid must be evaporated in glass, glass-enameled, stoneware or silica vessels. This may be done by blowing heated air or superheated steam through the liquid or by allowing the liquid to flow down and over checkerwork in a tower up which the heated gases are passing. Another method is to use glass or silica tubes as shown in the Hart Evaporator in Fig. 3. In this figure 1 is a longitudinal section, 2 plan and 3 a cross section. (See *Jour. Ind. & Eng. Chem.*, July, 1918, Vol. X, p. 555.)

[1] A discussion of the theory and practice of multiple effect evaporation will be found in the *Journ. Ind. & Eng. Chem.* for May, 1918, Vol. X, p. 191.

See also Badger and Shepard, *Chem. and Met. Eng.*, Vol. 23, No. 4, July 28, 1920.

Badger and Shepard, *Chem. and Met. Eng.*, Vol. 23, Nos. 6, 7 and 9, 1920.

W. L. Badger, *Chem. and Met. Eng.*, Vol. 25, No. 10, Sept. 7, 1921.

Some of the above papers are also printed in *Trans. Amer. Inst. Chem. Eng.*, Vol. 13, Part I, pp. 77, 101, 139 and 151.

CHAPTER XV.

CRYSTALLIZATION.

(220) Most solids are more soluble in hot than in cold liquids and separate out as crystals from such solutions on cooling. Because of a difference in solubilities this process often offers a ready and cheap method of purification. As an illustration we may take the preparation of potassium nitrate from Chile saltpeter ($NaNO_3$) and potassium chloride (KCl). When these are dissolved in hot water to saturation in the proportion:

$$NaNO_3 + KCl = 85 : 74.6,$$

we have four substances: $NaNO_3$, KNO_3, NaCl, KCl in solution. If we evaporate such a solution we soon reach a point where the common salt can remain in solution no longer, because common salt is very little more soluble in hot than in cold water, and it begins to crystallize out in cubes. On the contrary the three other salts are much more soluble in hot water than in cold and they remain in solution. As the common salt separates more forms in solution. The $NaNO_3$ and KCl diminish in quantity and the KNO_3 increases, salt continually separating, until the solution becomes saturated with KNO_3 and it, too, begins to crystallize out. The boiling is now stopped and the solution run into crystallizers. As the temperature falls in the crystallizers much potassium nitrate and a little salt separate.

(221) In order that the crystals of salt separated may be purified from adhering potassium nitrate solution, it is necessary that the crystals shall be small and if the boiling is rapid this will be the result. As the salt forms it is lifted out with perforated shovels thrown into a centrifugal, whizzed, to throw out the mother liquor, washed in the centrifugal with a little cold water and dried. This salt still contains a small quantity of nitrate which does not, however, interfere with its use for most purposes. In order to get it perfectly pure we should have to dissolve it and boil it down again, or wash it in the counter current apparatus.

(222) The crystals of potassium nitrate which begin to form in the crystallizers will become very large if the solution cools

slowly and quietly and films and globules of mother liquor will be enclosed in these large crystals. To prevent the formation of large crystals the solution is stirred as it cools and when cooled perfectly the crystals are whizzed in a centrifugal and rotated in a macerator with a cold saturated solution of potassium nitrate. The nitrate will not dissolve in this solution but the salt will and on again whizzing it in the centrifugal and washing with a little more solution of pure nitrate we get a nearly pure potassium nitrate. If this must be absolutely free from salt it must be redissolved in boiling water and recrystallized.

(223) It becomes evident from the above that means for controlling the size of the crystals is very desirable in order to insure greater purity. Too little attention has been paid to this point, except in the crystallization of cane sugar. When the cane juice has been properly evaporated in a multiple effect it is transferred to a single effect with high vacuum and the boiling continued.

(224) "As the evaporation goes on, the liquid becomes thicker and thicker until a density is reached at which the sugar, under the existing temperature in the pan, begins to crystallize. It is now that close attention is necessary in order that at the proper moment crystallization shall be checked, or rather, that the formation of an undue number of crystals shall be prevented so that finally crystals of the desired size shall be obtained. As the critical moment approaches, the pan-boiler takes samples of the boiling liquor out of the pan by means of a proof stick. This is a metal rod about 1 inch in diameter and about 2.5 feet long, freely running in a sleeve in the side of the pan. The sleeve has a ground face against which a ground shoulder on the proof stick fits in such a manner that a fairly tight contact is made and air is prevented from leaking into the pan. In the pan end of the proof stick there is a cup like depression in which about an ounce of liquid can be drawn from the pan. As the pan man draws this out, he throws the liquid on to a glass plate, or allows it to flow between his finger and thumb, at the same time examining it before a bright light. If the density of crystallization has been reached, the first young crystals will appear as tiny points of light flowing down the glass, and it will be necessary to watch the

rate of their increase very closely, for it is very rapid. The moment that the operator judges that enough of these crystals have been formed, he quickly opens the valve communicating with a suction tank from which a supply of liquor may be drawn in; the inflowing thinner liquor brings the boiling mass to a density at which no more crystals can be formed, but those remaining in the pan will begin to grow in size as the density of the liquor again begins to rise. It is, now that the nursing of the crystals goes on, and in order that they shall grow in vigor and in strength, they are treated to occasional 'drinks,' *i. e.*, liquor is drawn in whenever the density of the mother liquor tends to rise to the point at which a new lot of crystals would be born; if this last should happen, trouble would result for this second crop coming into the world so much later than the first would not grow to the same size as their older brethren, and thus the resulting sugar would show an uneven grain when finished and the washing in the centrifugal would be difficult. When the boiling mass, which is now a mixture of crystals floating in the mother liquor (syrup), through repeated 'drinks,' fills the pan, it is finally brought to a proper consistency, and the boiling is finished. The vacuum is broken, the steam is turned off and the whole mass allowed to flow through a foot-valve into a 'mixer,' where it is kept in motion by means of revolving paddles, and is drawn off in batches to the centrifugals to be purged from the syrup. The last traces of syrup that tend to adhere to the now white crystals on the walls of the centrifugals are washed away by spraying distilled or filtered water into the machines. The centrifugals are allowed to spin until the sugar is fairly dry, this last is then conveyed to a granulator to be dried." (*Chemical Industry in Canada*, p. 40, Toronto, 1909.)

(225) This growing of crystals is possible when there is not too much difference in the specific gravities of solid and solution. The sugar in this case has sp. gr. 1.593 while the syrup is about 1.33. In the case of ferrous sulphate these figures are 1.89 and 1.24 and in the case of common salt 2.16 and 1.21. As the difference grows some other means must be used to establish and maintain this control. If the solution is run into a cylinder which

can be rotated on its axis and is cooled while rotating by running cold water over the outside the crystals will form rapidly and will be small so that they can be easily freed from mother liquor by very little washing. Treated in this way alum, potassium nitrate and sulphate, barium nitrate and many other solutions can be treated very successfully but some other solutions are apt to form a thick mush of very fine needles difficult to handle.

(226) It has been suggested[1] that the viscosity of a liquid probably has also much to do with the growth of crystals in suspension. Whatever the cause may be the control of crystallization and its rapid completion so as to avoid the building of expensive crystallizing pans is greatly to be desired.[2]

(227) Crystallizing Pans are usually made of wood, sheet steel or cement. The first is commonly cheaper. If case wood is used the pans will swell and shrink with moisture and temperature changes. They are sure to leak and must be placed over a tight floor inclined towards a sump and pump. Wooden crystallizing tanks must be shallow since wood is a poor conductor and most cooling is from the surface. Sheet steel crystallizers may have a hopper shape with a door in the bottom so that the crystals can be shoveled directly into barrels or into a centrifugal. Cement crystallizers are stronger when cylindrical. For further discussion see under "Tanks."

[1] By F. C. Zeisberg in a letter to the author.

[2] Vant Hoff has studied the interactions of salts in solution (*Vorlesungen in Theoret. u. phys. Chem.*, 1898, p. 90) and the results have been applied to the utilization of salt water mother liquor by Hildebrand. (*J. Ins. Eng. Chem.*, 10, 96, 1918.)

CHAPTER XVI.

DRYING.

(228) Tunnel dryers are sometimes used for drying large quantities of materials. They consist of closed compartments with steam heating pipes and ventilating fans for renewing the air, and muslin screens for removing dust and soot from the



Fig. 205.—Crystallising and Drying Pan.

entering air when necessary. The material is placed on frames covered with cloth supported on racks placed on cars which are run into one and out the other end of such a tunnel. Or racks are placed on the sides of the tunnel, the frames filled placed in

the tunnel and when dry removed, emptied, refilled and replaced. Some substances, like citrate of iron and ammonia, are dried in scales by pouring on glass plates and when dry scraping off with



Fig. 206. - Vacuum Crystallizing and Drying Pan.

a knife. These shelf dryers may be made of metal tightly bolted so as to be air tight. If a vacuum is produced in them rapid drying is secured at a lower temperature.

(229) For evaporating and drying substances like ammonium nitrate the pan shown in Fig. 205, made by the Buffalo Foundry & Machine Co., is used. For evaporation, steam is injected into the cast iron jacket and when evaporation has proceeded far enough, cold water is run through the jacket to cause the mass to crystallize. This pan may also be used as a dryer for substances like T. N. T.

(230) The form shown in Fig. 206 made by the same company is used for vacuum work, where a low temperature is necessary.

A vacuum shelf dryer made by the same company is shown in Fig. 207. This cut also shows the pump and condenser.

(231) Fig. 208 shows a direct heat, shelf retort made by the same company for reclaiming high boiling point solvents.

It is provided with ducts passing from one side to the other. Shelves are formed between the ducts. The retort may be operated under vacuum. Hot gases from the furnace pass through the ducts and the temperature of each shelf is regulated by a separate damper.

(232) It has been known for many years that the pig iron output of an iron blast furnace varied considerably with the weather conditions and that wet weather was sure to cause disturbances. Mr. James Gayley showed[1] that it was often profitable to remove most of the moisture by cooling the air and then reheating it so as to secure constant moisture conditions in the furnace. Mr. Gayley's experiments at the Isabella Furnaces were conducted by passing the air over pipes containing brine cooled by an ice machine. The coils were soon coated with ice, which is a poor conductor, resulting in decreased efficiency and cooling the air to a temperature lower than was necessary.

In many drying operations it is very desirable to have dry air of uniform low moisture content. Some operations such as the handling of silk require uniform temperature and moisture. This regulation of moisture is spoken of as conditioning.

(233) The Carrier Air Conditioning Co., have shown that by blowing a spray of water at 35° through air and then passing through a separator, the moisture may be reduced with greatly

[1] *Trans. Am. Inst. Min. Eng.*, 35, 746, 1505.



Fig. 207.—Vacuum Shelf Dryer with Pump and Condenser.

simplified apparatus, and at less cost since no ice is formed and no loss in conductivity takes place. Ortman and Davis (*J. Amer.*



Fig. 208.—Direct Heat Shelf Retort.

Cer. Soc., Oct., 1921, p. 796) have described a "Humidity System of Drying Terra Cotta" which is interesting reading.

(234) The late W. B. Ruggles contributed in 1909 to Kent's Mechanical Engineers Pocket Book a very able article on Dryers and Drying which with the kind permission of the editor I am permitted to reproduce as follows:[1]

"Materials of different physical and chemical properties require different types of drying apparatus. It is therefore necessary to classify materials into groups, as below, and design different machines for each group.

"Group A: Materials which may be heated to a high temperature and are not injured by being in contact with products of combustion. These include cement rock, sand, gravel, granulated slag, clay, marl, chalk, graphite, asbestos, phosphate rock, slaked lime, etc.

"The most simple machine for drying these materials is a single revolving shell with lifting flights on the inside, the shell resting on bearing wheels and having a furnace at one end and a stack or fan at the other. The advantage of this style of machine is its low cost of installation and the small number of parts. The disadvantages are great cost of repairs and excessive fuel consumption, due to radiation and high temperature of the stack gases. If the material is fed from the stack and towards the furnace, the shell near the furnace gets red hot, causing excessive radiation and frequent repairs. Should the feed be reversed the exhaust temperature must be kept above 212° F., or recondensation will take place, wetting the material.

"In order to economize fuel the shell is sometimes supported at the ends and brickwork is erected around the shell, the hot gases passing under the shell and back through it. Although this method is more economical in the use of fuel, the cost of installation and the cost of repairs are greater.

"Group B: Materials such as will not be injured by the products of combustion but cannot be raised to a high temperature on account of driving off water of crystallization, breaking up chemical combinations, or on account of danger from ignition. Included in these are gypsum, fluorspar, iron pyrites, coal, coke, lignite, sawdust, leather scraps, cork chips, tobacco stems, fish scraps, tankage, peat, etc. Some of these materials may be dried

[1] Edition of 1913, page 547.

in a single-shell dryer and some in a bricked-in machine, but none of them in a satisfactory way on account of the difficulty of regulating the temperature and, in some cases, the danger of the explosion of dust.

"Group C: Materials which are not injured by a high temperature but which can not be allowed to come into contact with products of combustion. These are kaolin, ocher and other pigments, fuller's earth, which is to be used in filtering vegetable or animal oils, whiting and similar earthy materials a large portion of which would be lost as dust in direct heat drying. These may be dried by passing through a single shell dryer incased in brickwork and allowing heat to come into contact with the shell only; but this is an uneconomical machine to operate, due to the high temperature of the escaping gases.

"Group D: Organic materials which are used for food either by man or the lower animals, such as grain which has been wet, cotton seed, starch feed, corn germs, brewers' grains, and breakfast foods, which must be dried after cooking. These, of course, can not be brought into contact with the furnace gases and must be kept at a low temperature. For these materials a dryer using either exhaust or live steam is the only practical one. This is generally a revolving shell in which are arranged steam pipes. Care should be exercised in selecting a steam dryer which has perfect and automatic drainage of the pipes. The condensed steam always amounts to more than the water evaporated from the material.

"Group E; Materials which are composed wholly or contain a large proportion of soluble salts, such as nitrate of soda, nitrate of potash, carbonates of soda or potash, chlorates of soda or potash, etc. These in drying form a hard scale which adheres to the shell, and a rotary dryer can not be profitably used on account of frequent stops for cleaning. The only practical machine for such materials is a semicircular cast-iron trough having a shaft through the center carrying paddles that constantly stir up the material and feed it through the dryer. This machine has brick side walls and an exterior furnace; the heat from the furnace passing under the shell and back through the drying material or

out through a stack or fan without passing through the material, as may be desired. Should the material also require a low temperature, the same type of dryer can be used by substituting steam jacket steel sections instead of cast iron."

The efficiency of a dryer is the ratio of the theoretical heat required to do the drying to the total heat supplied. The greatest loss is the heat carried out by the exhaust or waste gases; this may be as great as 40 per cent. of the total heat from the fuel, or with a properly designed dryer may be as small as 8 per cent. The radiation from the shell or walls may be as high as 25 per cent. or as low as 4 per cent. The heat carried away by the dried material may amount under conditions of careless operation to as much as 25 per cent. or may be as low as nothing.

A properly designed dryer of the direct heat type for either group "A" or "B" will give an efficiency of from 75 per cent. to 85 per cent.; a bricked-in return draught single-shell dryer, from 60 per cent. to 70 per cent.; and a single shell straight draught dryer, from 45 per cent. to 55 per cent. A properly designed indirect-heat dryer for group "C" will give an efficiency of 50 per cent. to 60 per cent., and a poorly designed one may not give more than 30 per cent. The best designed steam dryer for group "D" in which the losses in the boiler producing the steam must be considered, will not often give an efficiency of more than 42 per cent.; and, while a poorly designed one may have an equal efficiency, its capacity may not be more than one-half of a good dryer of equal size. The dryer described for group "E" will not give an efficiency of more than 55 per cent.

Fig. 209 gives details of a single shell dryer arranged for the drying of nitrate of soda. This machine has a shell 36 inches in diameter and 20 feet long, equipped with a specially designed furnace and has a capacity of 27 tons of nitrate of soda per 24 hours, reducing the moisture from 5 per cent. to less than one-half of 1 per cent. The fuel consumption per ton of nitrate of soda, is 28 pounds of coal with a thermal value of 14,000 B. t. u. and the power required is 6 horse-power. One man can operate the machine and do the firing, as well as attending to any feeding and delivering conveyers.


Elevation & Half Section Thru Furnace
Plan
Section A-A
Section B-B
Class F-1 Dryer
Pugsley-Dake Eng. Co.
York, Pa. New York Cincinnati

Fig. 209.



Fig. 210.

(235) The Lowden Dryer manufactured by the Colorado Iron Works Co., Denver, Colo., is shown in Figs. 210, 211 and 212.



Fig. 211.



Fig. 212.

"The drying is done upon a hearth which is composed of cast iron plates, *A*, beneath which is the flue *B*, through which the gases of combustion pass. The plates comprising the hearth are

so joined as to prevent the escape of gases into the atmosphere, as well as the escape of the material being dried into the flue below. The manner of providing for expansion and contraction of the hearth is simple and effective, consisting in anchoring each plate by means of lugs, *N*, which enter corresponding sockets imbedded in the side walls of the flue. Expansion of the hearth plates lengthwise is accommodated by the overlapping edges which have ample allowance for movement, and sidewise by the lugs *N*, sliding in their sockets which are designed to permit sufficient movement in that direction."

(236) The efficiency which may be expected from such a dryer varies from 30 to 60 per cent., and the following illustrates the method of calculation:

QUANTITIES PER HOUR.

Feed, wet weight.....3,638 lbs.	Fuel Col. lignite.
Feed, dry weight.....2,583 lbs.	Calorific power.
Moisture in feed 29%...1,005 lbs.	10,000 B. t. u. per lb.
Moisture in product 13% 382 lbs.	Fuel burned 166 lbs.
Moisture evaporated 16% 673 lbs.	Fuel per ton of feed 91.3
Water evaporated per lb.	Fuel per ton of product 111.9.
of fuel ..... 4.05 lbs.	
Specific heat of solids	
assumed 0.25	
Temperature of feed.... 52° F.	
Temperature of product. 212° F.	

CALCULATION.

Heat usefully applied:

In raising temperature of solids $2,583 \times 0.25 \times 160 =$	103,320 B. t. u.
In raising temperature of total water $1,055 \times 160 =$	168,800 B. t. u.
In evaporating water 673×976..... $=$	650,118 B. t. u.
Total heat usefully applied.....	922,238 B. t. u.
Total heat developed $166 \times 10,000$..... $=$	1,660,000

Whence efficiency = 55.5%.

Performance of Different Types of Dryers.

(W. B. Ruggles)

Type of dryer	Double shell direct heat.	Indirect heat 705 sq. ft.	Single shell bricked-in direct heat.	Single shell direct heat.	Stationary with paddles direct heat.
Material	Sand	Coal	Cement slurry	Lime-stone	Nitrate of soda
Moisture, initial, per cent.	4.58	10.2	61.2	3.6	7.2
Moisture, final, per cent.	0.0	0.0	40.7	0.5	0.3
Calorific value of fuel B. t. u.	12100.0	12290.0	13200.0	13180.0	13600.0
Fuel consumed per hour, lbs.	398.0	213.6	667.0	460.0	87.0
Water evaporated per hour, lbs.	2196.0	924.2	4057.0	1325.0	349.0
Water evap. per pound fuel, lbs.	5.3	4.3	6.1	2.3	4.0
Material dried per hour, lbs.	36460.0	8300.0	7680.0	41400.0	4581.0
Fuel per ton dried material, lbs.	21.8	51.3	17.3	22.2	38.0
Heat lost in exhaust air, per cent.	11.3	42.8	38.4	38.2	40.7
Heat lost by radiation, etc., per cent.	7.6	7.7	12.5	15.6	13.8
Heat used to evaporate water, per cent.	52.5	39.4	52.0	24.4	33.1
Heat used to raise temperature of material, per cent.	28.6	10.1	7.1	21.8	12.4
Total efficiency, per cent.	81.1	49.5	59.1	46.2	45.5

Performance of a Steam Dryer.

Material: Starch feed. Moisture: initial 39.8%, final 0.22%. Dried material per hour 831 lbs. Water evaporated per pound steam, 0.691 lb. Temperature of material: moist 58°, dry 212°. Steam pressure, 98 lbs. gauge.

Total heat to evaporate 548 lbs. water at 58° into steam,
$548 \times (154.2 + 969.7) = 615{,}897$ B. t. u.

Heat supplied by 793 lbs. steam condenser to water at 212°,
$793 \times (1{,}188.2 - 180.3) = 799{,}265$ B. t. u.

Heat used to evaporate water,
$(615{,}897 \div 799{,}263) = 77.1\%$.

Heat used to raise temperature of material,
$(831 \times 154 \times 0.492) = 62{,}963 = 7.9\%$.

Loss by radiation: $100 - (77.1 + 7.9) = 15\%$.

Total efficiency: 85.0%.

WATER EVAPORATED AND HEAT REQUIRED FOR DRYING.

M = percentage of moisture in material to be dried.
Q = lbs. of water evaporated per ton (2,000 lbs.) of dry material.
H = British thermal units required for drying per ton of dry material.

M	Q	H	M	Q	H	M	Q	H
1	20.2	85,624	14	325.6	424,884	35	1,077	1,269,240
2	40.8	108,696	15	352.9	458,248	40	1,333	1,555,960
3	61.9	130,424	16	381.0	489,720	45	1,636	1,895,320
4	83.3	156,296	17	409.6	521,752	50	2,000	2,303,000
5	105.3	180,936	18	439.0	554,680	55	2,444	2,800,380
6	127.7	206,024	19	469.1	588,392	60	3.000	3,423,000
7	150.5	231,560	20	500.0	623,000	65	3.714	4,222,680
8	173.9	257,768	21	531.6	658,392	70	4,667	5,290,040
9	197.8	284,536	22	564.1	694,792	75	6,000	6,783,000
10	222.2	311,864	23	597.4	732,088	80	8,000	9,023,000
11	247.2	339,864	24	631 6	770,392	85	11,333	12.7-5,960
12	272.7	368.424	25	666.7	809,704	90	18,000	20,223,000
13	298.9	397,768	30	857.0	1,022,840	95	38 000	42,623,000

Formulae; $Q = \frac{2000M}{100-M}$; $H = 1120Q + 63,000$.

The value of H is found on the assumption that the moisture is heated from 62° to 212° and evaporated at that temperature, and that the specific heat of the material is 1.21.

$$2,000 \times (212 - 62) \times 0.21 = 63,000.$$

CHAPTER XVII.

DISTILLATION.

(237) In a book like this it is impossible to go into detail on the theory of fractional distillation because too much space would be needed. For an account of this part of the subject the student must consult Sidney Young's book on Fractional Distillation. A careful study of this subject is a very necessary part of the preparation for work with such apparatus.

(238) The most familiar example of distillation is the preparation of whiskey, brandy or alcohol from fermented liquors. In the laboratory this is accomplished by means of dephlegmators or distillation tubes. One of the simplest of these consists of a wide glass tube filled with marbles or large glass beads.

(239) The object of the distillation is the more or less complete separation of water from alcohol. Water boils at 100° and alcohol at 80°. If we boil a mixture of 5 per cent. alcohol and 95 per cent. water the vapor at first given off will contain more than 5 per cent. alcohol and less than 95 per cent. water. As the mixed vapors ascend the tube they are condensed in part, the water condensing most easily. The vapor therefore grows richer in alcohol and poorer in water as it rises in the tube. If the tube were long enough we might reasonably expect that alcohol entirely free from water would issue from the side tubes at the top. We find, however, that no matter how long the tube, the alcohol will still contain about 5 per cent. water, so that distilled alcohol or cologne spirits contain 95 per cent. alcohol.

(240) Where there is no great tendency to combine, as is the case with alcohol and water, the separation may be more complete, but in no case is the separation absolutely perfect. In many cases, as in petroleum distillation, a partial separation is sufficient. Fig. 213 illustrates an apparatus for distilling acetic acid, made by Doulton and Co. In this case the dephlegmating column, Woulf bottles and condenser are made of stoneware.

In Figs. 214 and 215 two forms of rectifying still of copper made by the Walter E. Lummis Co., are illustrated.

(241) For Distilling Acids the Hart apparatus, shown in Fig. 216 is best adapted. This consists of a porcelain body *A* with hanging tubes of glass, open at the top and closed at the bottom,



S. Still. R. Return Receiver.
F. Fractioning Column. C. Condenser.
O. Outlet for Pure Acid.

Fig. 213.—Column Apparatus For Distilling Acetic Acids.

B. The acid is admitted at *E* and overflows at *G*. For hydrochloric acid the packing between tube and manifold may be of rubber, which must be kept from direct contact with the flame by an asbestos shield, but for nitric acid only asbestos fiber or

The Walter E. Lummus Co., 173 Milk St., Boston, Mass.



Fig. 214.—Benzol & Toluol Rectifying Still with Internal Reflux.

The Walter E. Lummus Co., 173 Milk St., Boston, Mass



Fig. 215.—Benzol & Toluol Rectifying Still with External Reflux.

the best quality carefully packed by an experienced hand will answer. This apparatus is defective in that there is no circulation in the tubes and, in distilling large quantities of crude acid containing dissolved salts, these are apt to deposit in the tubes. When the tubes become clogged the apparatus must be taken apart and cleaned.



A. Acid receivers.
B. Acid tubes.
C. Furnace.
D. Grates.
E. Acid Inlet Funnel.
F. Acid vapor exit pipes.
G. Residue outlet.

Fig 216.—Apparatus For Distilling Acids.

(242) For acid liquids containing at the same time dissolved salts and free acid, either the apparatus shown in Fig. 3 or the modified Hart boiler shown in Fig. 217 may be used. In the apparatus shown in Fig. 217, *E* is a leaden trough with leaden side tubes *J*, terminating over thistle tubes *F*, reaching to the bottom of the boiling tubes *B*. The evaporated liquid passes over at *G*, and the acid vapor goes off at *F*. Both this furnace and that shown in Fig. 216 are best fired with oil or gas. This form of

apparatus though appearing fragile is very practical and has distilled many thousand tons of nitric and hydrochloric acids with great economy.



Fig. 217.—Improved Apparatus—For Distilling Acids.

(363) **Many Forms of Condenser** have been used for the condensation of acid liquids. The simplest of these depends on the

cooling for condensation, but this has generally been given up as too slow and uncertain in operation. A water-cooled worm is shown in Fig. 213. The Hart condenser for nitric acid is shown in Fig. 218. As here shown this is intended to produce a strong acid nearly free from nitrous acid. The vapor enters at *D* into the



Explanation.

A. Receiver for HNO_3.
B. Condensing Tubes.
C. Stand Pipes.
D. Inlet Pipe.
E. Siphon.
F. Water Sprinkler.
G. Muslin Cover.
H. Waste Water Trough.
I. Showing manner of using muslin condense cover.
J. Stops.

Fig. 218.—Hart's Nitric Acid Condenser.

first manifold *C*, and then by the 3-inch glass tubes *B* into the second manifold. There are 12 of these tubes shown. At *J* the second manifold has a partition so that the remaining vapor must pass through the four tubes shown into the first manifold which

also has a partition *J*. The remaining uncondensed vapor passes to the left through four tubes and to another condenser or to the towers or into the outer air by the tube *G*. The condensed acid runs backward in the tubes thus effecting a partial fractionation and the hot condensate collects in *A*. Water from a perforated pipe flows over the tubes and is distributed by means of muslin covers shown on the upper left hand corner and in section at *I*. This apparatus has the great advantage of taking little space, may be placed out of doors in freezing weather without loss of the tubes through freezing. If proper care is exercised it is very economical. Considerably more than half of the nitric acid made in the United States during the late war and much of that made abroad was condensed in this apparatus.

(244) Hough has devised a condenser in which the cooling coils are made of duriron. This answers for nitric acid, but has



Fig. 219.—Enameled Condenser.

the disadvantage that if allowed to stand in the open in freezing weather it will be destroyed. The Moore and Hall condenser (U. S. Patent No. 986,846, Mar. 14, 1911) consists of an upright cylinder in which a number of very long test tubes are suspended. Into each of these tubes a stream of water is led, the nitric acid condensing on the outside. This also has the objection that it cannot be exposed to frost. The S condenser is built of large silica pipe rising above the retort in a series of flat curves, so that the condensed acid may run backward. This is a good condenser but is quite expensive.

(245) As ordinarily constructed very few condensers are really efficient. In order that the Liebig condenser may have maximum efficiency the cooling liquid must move rapidly through the annular space between the inner and outer tubes. In order that this may be possible this space must be narrow. We then get a highly efficient apparatus; that is to say, a much greater amount of vapor may be cooled in the modified condenser and the water for cooling will be very hot as it leaves the cooler. Most condensers appear to have been designed in entire forgetfulness of the fact that water is a very poor conductor of heat, and that to ensure maximum work in minimum space the cooling water must pass over the cooling surface rapidly.

For this reason the many tube condenser, with an outer shell filled with inner tubes passing through headers in the ends, is more or less inefficient unless the tubes are small and are closely spaced. To add to this condition the vapors are passed through the tubes when rapid flow of the water is impossible. Only the surface of these tubes is useful, and the center of the tubes should be filled with other tubes so that a rapid current of water might pass in the narrow annular space vapor being admitted within the casing around the tubes and into the inner tubes as well.

The worm condenser is worst of all: a lamentable case of inefficiency that should not be tolerated. No plant can afford to pump unnecessary water or to fill up valuable space unnecessarily.

CHAPTER XVIII.

ABSORPTION OF GASES.

(248) Hydrochloric and hydrofluoric acids and ammonia are usually sold as solutions in water. Solutions of carbon dioxide in water under pressure are sold as soda water. The solution of



Fig. 220.—Hydrochloric Acid Condenser.

A. Roaster Gas. (Weak)
B. Pan Gas. (Strong)
C. Cooling and Washing Tower.
D. Bombonnes or Absorbers. (30)
E. Coke Tower. (20 ft. high)
F. Fire Boxes.
P. Sulphate Pan.
R. Sulphate Roaster.
S. Opening for pushing pan sulphate cake into roaster.

several gases in water (SO_2 and NO_2) is used as a step in the manufacture of other substances (sulphites and bisulphites, nitric acid). In many other cases the solution is accompanied by evolution of considerable heat and as gases are most soluble in cold water means must be employed to keep the liquid at a temperature at least as low as that of the air if concentrated solutions are to be obtained.

Pütter—for Hydrochloric Acid



	Capacity gallons	Outside diameter inches	Height inches
I.	43½	26¾	31½
II.	52¾	29½	37½
III.	59½	29½	34½
IV.	66	31½	36¾
V.	79¾	32¾	40¾
VI.	118¾	35½	43¾

Normal—for Nitric Acid.



	Capacity gallons	Outside diameter inches	Height inches
I.	14½	19¾	21¾
II.	26½	21¾	28¾
III.	39½	26	30
IV.	43½	26¾	31½
V.	52¾	29¾	37¾
VI.	58	29½	34½
VII.	66	31½	36¾
VIII.	79¾	32¾	40¾
IX.	118¾	35½	53¾

Cellarius—for Nitric Acid.



		I.	II.	III.
Length	inches	31½	39½	40¾
Width	"	19¾	26	35½
Height	"	12¾	15	20½
Approximate Cooling Surface	Sq. Ft.	9¾	15	23½
Gas Inlet and Outlet, Diameter	Inches	6	8¼	12¾
Liquid Inlet and Outlet	"	1½	2	2¾
Capacity	Gallons	18½	29	66

Fig. 221.—Stoneware Tourills.



Fig. 22.—Circular Stoneware Towers. Lunge-Rohrmann-System.

(247) In the oldest form of apparatus, shown in Fig. 220, the gas, first properly cooled in a tower *C*, was passed through a series of Woulffe bottles connected at the tops by large inverted U



Fig. 223.—Hydrochloric Acid Plant.

tubes. The solution obtained flowed from one bottle to another by side tubes as shown at *D*. The heat generated by solution

was dissipated by air cooling or sometimes by setting the bottles in water. Other forms of stoneware bottle are shown in Fig. 221. This tower was faulty theoretically and did not lend itself to rapid production. The tower made of stoneware shown in Fig. 222 with details on 223, or of lead lined with chemical brick (Fig. 220 gave larger production but had the same theoretical defect and only relatively weak solutions were produced.

(248) In the Hart-Adamson absorber and cooler shown in Fig. 224, the gases pass in at *A* into the manifold C from which



Fig. 224.—Acid Condenser. (Hydrochloric)

A. Acid Gas Inlet.
B. Acid Receiver.
C. Stand Pipe.
D. Condenser Pipes.
E. Stand Pipe.
F. Inlet for Absorbing Fluid.
G. Sprinkler.
H. Waste Water Trough.
a. Condenser Pipe Trough.
b. " " Spout.
c. Condenser Pipe Dam.

they pass through each of the tubes *D* into the manifold *E*. The absorbing liquid flows from the tap through the funnel *F*, through the first tube, back through the second tube, etc., until it reaches the vessel *B*, from which it is removed by the tap as desired. Each tube has a dam so that part of the liquid remains in the tube. Cooling is effected by running cold water over the tubes from the pipe *G*. The joints at either ends are made with rubber gaskets for hydrochloric acid. With this apparatus very strong hydrochloric acids can readily be made in any quantity desired.

(249) The absorption of NO_2 and its conversion into reasonably strong HNO_3 offers considerable difficulty as the reactions occurring are of small velocity and consequently large surfaces are required. The heat liberation is negligible and so towers offer the cheapest solution. The theory of such towers is discussed by Partington and Parker in the *Journal of the Society of Chemical Industry*, Vol. XXXVIII, 1919, p. 75. Recently, another paper by Donnan and Masson on the theory of Gas Scrubbing Towers has appeared, *Ibid.*, **39**, 239, 1920. See also W. Hempel, *Ztsch. für Angew. Chem.*, **6**, 1917.

An interesting paper on Tower Packing Efficiencies will be found in *Chemical and Metallurgical Industry*, Vol. 24, p. 741.

The absorption of gases by liquids is, of course, always subject to the law of partial pressures, and for this reason it is difficult to remove the last trace of any gas from a mixture. This difficulty becomes greater if the gas is only slightly soluble in the liquid.

Gases may be rapidly absorbed because they diffuse, but solid or liquid mists are difficult to condense. This is especially true of the very finely divided mists produced by sudden cooling. Air containing hydrochloric acid gas may be cleansed by passing through two or three wash bottles, but if the air contains moisture and a fine mist forms the problem becomes difficult. Such mists may be arrested by filtering the gas through cotton, wool or asbestos, by whirling in a centrifugal, which throws the particles against the casing, or by passing a high voltage direct current through a wire passing through the center of the tube (Cottrell system).

In the middle of the nineteenth century a large manufacture of Leblanc soda grew up in England, the first step being the manufacture of salt cake (Na_2SO_4) from salt and sulphuric acid. The hydrochloric acid resulting was condensed in part and used for making bleaching powder but more was produced than was needed and about half of it was allowed to escape. This caused a serious nuisance and in 1867 the Lord Derby Alkali Act provided that 95 per cent. of the gas must be condensed and that not more than 0.454 gm. HCl per cubic meter could be allowed in the chimney

gas. A year later the average condensation was 89.72 per cent., two years later 99.11 per cent. and now about 99.27 per cent.

The methods of purifying gases have been most carefully and successfully studied in the manufacture of illuminating gas, and the theory and apparatus so evolved will be found worthy of careful study.

In a paper describing a new salt cake furnace received as this Edition goes to press is comprised a study of the purification and absorption of hydrochloric acid gas which will repay careful study (See "A New Salt Cake and Hydrochloric Acid Furnace" by N. A. Laury, *Chem. and Met. Eng.*, Nov. 2, 1921).

CHAPTER XIX.

MIXING AND KNEADING.

(250) In a great many operations mixing or kneading, according to the nature of the material must be accomplished. As illustrations of this we have the preparation of bread dough and the manufacture of spaghetti and macaroni, rubber mixing and kneading, the manufacture of graphite crucibles, crayon manufacture, dynamite, emery wheels, porcelain and pottery masses, etc., etc. For this purpose a great variety of machinery is manufactured. Among the prominent manufacturers of this class of machinery are the Werner & Pfleiderer Co., of Saginaw, Mich. Fig. 225 shows an asbestos mixer, Fig. 226 a vacuum masticator, and Fig. 227 shows how a battery of small experimental mixers may be driven from one countershaft.



Fig. 225.

Fig. 226.



Fig. 227.

CHAPTER XX.

AUTOCLAVES.

(251) Autoclaves are closed pots with or without linings intended for operations which must be carried out at pressures above atmospheric. They are made of cast iron or steel and for high pressures, say, up to 1,000 pounds, are very heavy. They may be heated by steam, heated oil, direct fire or electricity.

Those working at high pressures have special provision made for ensuring tight joints, at the same time being so arranged that they may be quickly opened for cleaning. In some cases it is necessary to stir the contents continually. In this case care must be taken that while the packing is tight it shall not too greatly retard the turning of the stirrer. Linings of silicon iron, lead, bronze, copper or aluminum are sometimes necessary. When ferrosilicon liners are used it is usual to put a lead liner next to the iron and place the ferrosilicon liner inside this so that the brittle ferrosilicon may not be cracked when the pressure is applied.

Blow-off valves are not provided because this would weaken the pot. It is better to discharge by blowing the charge out through a siphon run through the cover. Where high pressures are used it is necessary to provide safety devices to relieve the pressure, and to provide for frequent inspection.

It seems scarcely necessary to say that both the construction and capacity of an autoclave must depend altogether upon the purpose for which it is to be used. Very large autoclaves are used in the cellulose industry in the preparation of paper stock. Here large capacity and comparatively low pressures are the rule and blow-off valves and other conveniences may properly be driven through the shell. Most of these digesters are lined with chemical brick to resist the action of the sulphite liquor.

It is self evident that too much care can not be taken in the operation of autoclaves. When improperly handled they become very dangerous.



Fig. 228. Autoclave without stirrer.

Oil heating, which is frequently used in heat transmission like this where temperature control is necessary, has considerable advantages for certain work. The system consists of a heater fired by coal, oil or gas, a circulating pump and a jacket surrounding the autoclave or other container. The oil used is high boiling petroleum with high flash point.

The Parks-Cramer Co. of Fitchburg, Mass., who exploit the Merrill process, claim that 50 to 60 per cent. of the fuel value may be utilized, the losses being less than with direct firing, electric heating or heating by superheated steam. Since oil flows slowly when cold and penetrates the smallest openings when hot special plumbing and pumping arrangements are necessary.



Fig. 229. Autoclave with stirrer.

CHAPTER XXI.

CONTAINERS.

(252) Containers may be of wood such as barrels and boxes, of fiber corrugated or plain and varnished or paraffined, of paper, metal or glass.

(253) Barrels.—A great variety of metal barrels are on the market. For small lots second hand sugar or flour barrels are often collected. Where large quantities of wooden barrels are used it is better to install a barrel factory as part of the equipment. The capacity of a small barrel plant is from 250 barrels up. The staves and ends are bought in carload lots and three buildings will be needed, one for storing material, a second for the barrel making machinery and a third for barrel storage.

Barrel making machinery is made by the Peter Gerlach Co., Cleveland, Ohio, and the E. & B. Holmes Machinery Co., Buffalo, N. Y. Paper liners for barrels may be had.

(254) Boxes may be had in car-load lots put up in shooks with all the pieces of one box tacked together. Machines for driving a number of nails at one time so as to put such boxes together with a minimum of labor are on the market.

(255) Corrugated Fiber Boxes are sometimes satisfactory containers. Glass bottles and carboys are packed in box cars in salt hay or excelsior. Salt hay makes the best packing as it is very elastic. For acid carboys those with elastic slats or pieces of old rubber hose as resting surfaces are best.

(256) Glass Packages are usually charged at an advance on cost so as to cover breakage and cost of handling.

(257) Paper or Cloth Bags are sometimes used, as for cement. When possible, packages of all kinds should be non-returnable.

Index

Absorption of gases, 224.
Acids, distillation of, 216, 217, 220.
Acid liquids, evaporation of, 196.
Acid proof linings, 193.
Air, compressed, 112.
Air lift, 78.
Aluminum, 8.
Amalgamation, 19.
American filter, 153-157.
Arsenic, 19.
Atherite, 5.
Autoclaves, 233.

Bags, 235.
Bakelite, 15; enamel, 16.
Barium sulphide, waste disposal of, 26.
Barrels, 235.
Beams and girders, 40; a coefficient for, 40.
Benzol and toluol still, 218.
Blake crusher, 83.
Blow case pump, 76.
Brick for buildings, 27.
Brick laying, 34; American bond, 35; English bond, 35.
Brick linings, 14; cement for, 14.
Brick walls, 33.
Bronze, 10.
Buildings, spacing, 25; construction of, 26; framed, 30.
Buffalo Foundry & Machine Co., 185.
Buff-Dunlop apparatus, 113, 114.
Boilers, internally fired upright, 44, 45; horizontal tubular, 44, 45; Cornish, 46; Adamson seam, 46; Galloway, 47; Lancashire, 47; tubes and settings, 48, 49; grates, 48; water tube, 50, 51; qualifications of, 50; foaming, 50; circulation in, 50; testing, 50; with no chimneys, 53; surface combustion, 56; heat transmission in, 56.
Bottles, 235.
Box cars, 24.
Boxes, 235.

Calcium chloride waste, disposal of, 26.
Carbon dioxide analyzer, 53; recorder, 57.
Cars, gondola, coal and box cars, 24.
Caustic soda, corrosion of, 21.
Cellarius for nitric acid, 225.
Cement gun, 27, 28.
Cements, 16; proportions used concrete, 32.
Cements for brick and tile linings, 14.
Check valve, 52.
Chemist, chief, 42.
Chemicals' effect on woods, 172, 173.
Centrifugals, 81; Tolhurst, 121, 121A, 122; Schaum and Uhlinger, 123, 124; uses, 125, 126, 127.
Chile or Chaser mills, 99.
Chimneys, boilers with no, 53.
Chimney gases, composition and temperature, 56, 57.
Coal cars, 24.
Combustion, 56; heat transmission, 56.
Combustion chamber, 53.
Compressed air, 112.
Concrete, 26; mixers, 26; floors, 30, 38; piles, 31, 32; proportion, 32.
Condensers, 220, 221, 222.
Conducting, 203.
Containers, cast iron for, 1; mild steel for, 2; duriron for, 2; copper for, 6; lead and lead lined, 6; aluminum, 8; glass, 10; fused silica, 14; chemical stoneware, 14; bakelite, 15; glass lined, 13; enameled, 13, 235.
Conveyors, screw, 106, 107; spiral, 106; work truck, 106, 107.
Copper, 6.
Copper-iron alloys, 9.

Corrosion, cause and rate, 18; extent of, 19, 20; effect of amalgamation on, 19; gold, 20; caustic soda, 21.
Cream separators, 117.
Crystallization, 197.
Crystallizing pans, 200; drying pans, 201.
Crystals, methods for controlling size of, 198.
Crusher, jaw, 83; Blake, 83; gyratory, 85; Kennedy gearless, 85, 86, 87; Dodge, 87; Sturtevant, 88; Traylor, 89.
Crushers, power required, 90; cost of, 90.
Crushing, 82; classification of substances, 82; cost of, 90.
Cutter, pipe, 72.

Dissolving, 109, 110, 111; power required in, 110, 111; Werner and Pfleider Co., 111, 112; Pachuca tank, 112, 113; Buff-Dunlop apparatus, 113, 114.
Distillation, 205; of acids, 216.
Dodge crushers, 87.
Dopp evaporators, 178.
Dorr thickener, 130, 132, 133.
Dry air blast, 203.
Drying, 201; ammonium nitrate and T. N. T., 203.
Dryers, tunnel, 201; vacuum shelf, 205; Lowden, 211.
Dryers and drying, 206.
Duriron, analysis, 2; physical properties, 3; chemical properties, 3; action of nitric acid on, 4; action of hydrochloric acid on, 4; action of sulphuric acid, 4; design of apparatus, 4; installation of apparatus, 5.

Economics, business, 43.
Elbows, 74.
Enameled apparatus, 10.
Engine, steam, 58.
Engines, single acting, double acting, condensing and non-condensing, 58; expansive working, 58; parts, 59; slide valve, 59; Crosby indicator, 59; horse-power, 60; work done, 60; heat and work, 60; indicator diagram, 60; indicator piston, 61; economy of, 61; the piston, 61, 62; stuffing box, 61, 63; cross head of, 63, 64; connecting rod, 63, 64; governor, 63, 64; gas, see gas engines, Diesel, 64.
Evaporation, 174; by spraying, 174; tower, 176; efficiency, 176; capacity, 177; of acid liquids, 196.
Evaporators, atomizing, 175; arrangement of the pans, 177; steam heated, 177; Dopp, 178; vacuum, 181; Zaremba, 183, 190; horizontal, 185; multiple effect, 185, 189; crystallizing, 190; Lillie, 193; Kestner, 193; Yaryan, 193; Söderlund-Boberg, 193, 195.

Feeders for rolls, 93.
Feed water for boilers, 53.
Filter boxes, 235.
Filter-Cel, 161.
Filters, 135; Shimer, 135.
Filter presses, 135; D. R. Sperry & Co., 136, 137; T. Shriver & Co., 137, 138, 139, 140; Kelly, 141, 142, 143, 144, 145; Sweetland, 145, 146, 147, 148, 150, 151, 152; Moore, 149; American, 153, 154, 155; Oliver, 155, 156, 157; Portland, 155, 158; varnish, 159; wax or tallow, 160.
Filtration, 116.
Filtros, 163.
Fire door for boilers, 49.
Fleischmann Yeast Plant, 118.

Floors, concrete, 38; yellow pine, 38.
Foreman, the, 41.
Footings for foundations, 31.
Foundations, 30; materials for, 32.
Framed buildings for acid, 30.

Gas engines, 64, 65, 65a, 66, 67, 68, 69.
General Filtration Co., 161.
Glass apparatus, 10; glass-lined apparatus, 10.
Gold, 8; corrosion of, 20.
Gondola cars, 24.
Grinding, process of, 93.

Hardinge mills, 93, 94.
Hart's evaporator, 10; apparatus for distilling acids, 219; dissolved salts and free acids, 220; condenser, 221.
Hart-Adamson condenser, 228.
Hauser-Stander Tank Co., 172.
Hillside location of plant, 25.
Hydrochloric acid, action on duriron, 4; absorption of, 224, plant for, 227; condenser for, 228.

Illium, 9.
Impact screen, 97, 98, 100.
Industrial Management, 41.
Iron, cast, 1; enameled, 14.
Iron silicon alloys, 2.

Jaeger Machinery Co., 26.
Jaw crushers, 83.
Jeffrey swing hammer mill, 99.
Jet pump, 79.

Kelly filter press, 142.
Kennedy-Van Saun gearless standard crushers, 85, 86.
Kestner evaporator, 193.
Kieselguhr Co. of America, 161.

Lead, 6; lead lined pipe and valve, 7; pipe, 70.
Lead thallium alloys, 9.
Lillie evaporator, 193.
Linings for evaporator, acid, 193.
Location of works, 24.
Lowden dryers, 211.
Lummis Co., Walter E., 215.

Magnalium, 6.
Manager, general, 41.
Masonry, weight of, 33.
Materials, 1; mechanical handling of, 105.
Men employed, 42.
Mills, Hardinge, 93, 94; ball, 93, 95; tube, 93; pulverizer jar, 93, 96; Chile or chaser, 99; stamp, 99; roller, 99; buhr, 99; beater, 99; Jeffrey swing hammer, 99, 101; Raymond, 101, 102, 103; Williams, 102, 104.
Mixers for concrete, 26.
Mixing and kneading, 231.
Monel metal, 10.
Moore filter, 149.
Municipal Engineering Co., 27.

New Jersey Zinc Co., 19.
Nickel, 6.
Nichrome, 5.
Nitric acid, action on duriron, 4; condenser, 221.
Niter cake, disposal of, 26.

Oliver filter, 155, 156, 157.
Ore pockets, 25.

Pachuca tanks, 112, 113, 171.
Paints as protective coatings, 16.
Pans, crystallizing, 200; drying, 201.
Parks-Cramer Co., 234.
Paucity of information, 22.
Physical effects of chemicals upon wood, 172, 173.
Pilasters, 38.
Pipe, lead, 70; stoneware, 70; silica, 75; fittings, 71; tools, 72; unions, 72; wrench, 72; threader, 72.

Platinum, 9.
Platforms, shipping, 25.
Plath acid elevator, 76, 77.
Plug cock, 52.
Plumbing, 70.
Plunger and piston pumps, 80.
Portland filter, 155, 158.
Prime movers, 58.
Pulsometer pump, 79.
Pumps, Worthington, 53, 54, 55; blowcase, 76; Plath acid elevator, 76, 77; air lift, 78; jet, 79; pulsometer, 79; plunger and piston, 80; centrifugal, 81.

Raymond mill, 101, 102, 103.
Radiation, 57.
Reports of foremen, 42.
Resistal, 5.
Rolls, Cornish, 90; angle of nip of, 91; ataching to shaft, 91; Sturtevant, 92; feeders, 93; shafts, 93.
Roofs, flat slag and tar, 30; flat, gravel, tin, slate, wooden, 39.
Rubber vessels, 14.
Ruggles, dryers and drying, 206.

Safety valve, 52.
Scale in boilers, 53.
Schaum and Uhlinger, centrifugals, 123, 124.
Screen, impact, 97, 98, 100.
Separators, 116; cream, 117; Sharpless, super centrifuge, 118, 119, 120.
Settlers, 127.
Shafts for rolls, 93.
Sharpless super centrifuges, 118, 119, 120.
Shimer filter, 135.
Shriver & Co., T., filter presses, 137, 138, 139, 140.
Sidings, railway, 26.
Silex, fused, 14; tubing, 75.
Silicon iron alloys, 2.
Sil-o-cel brick, 57.
Silver, 8.
Söderlund-Boberg evaporator, 193, 195.
Sperry & Co.'s filter press, 136, 137.
Steam gage, 52.
Steel, mild, 2; enameled, 10.
Stirrers, 109; compressed air, 112.
Stoneware, chemical, 14; linings, 73; pipe connections, 73; stopcock, 73; tanks, 168, 169; pipe, joints for, 70.
Sturtevant crusher, 88; rolls, 92.
Superintendent, 91.
Sulphuric acid, action on duriron, 4.
Survey of land, 24.
Sweetland filter press, 145, 146, 147, 148, 150, 151, 152.

Tallow, filtration of, 160.
Tanks, 163; wooden, 163, 164; hoops for, 165; pressure in, 165; for muriatic acid, 166; lugs for, 166; rectangular, 168; stoneware, 168; concrete, 169, 170; cheap, 170; lined, 171; Pachuca, 171.
Tap, pipe, 72.
Traylor crusher, 89.
Thickener, Dorr, 130, 132, 133.
Threader, 72.
Tile, hollow, 36; safe load for, 38; roofs, 39.
Tile linings, 14; cement for, 14; hollow, 29.
Tracks for works, 108; laying out of, 108.
Trucks, work, 106, 107.
Tolhurst centrifugal, 121, 121a, 122.
Toluol and benzol still, 218.
Towers, gas scrubbing, 229.
Vacuum evaporator, 181; dryer, 202.
Variable speed power transmission system 69.
Varnish, press for filtering, 139.
Varnishes as protective coatings, 10.

Walls, crushing strength of, 33.
Waste, disposal of, 26.
Waterloo Cement Machinery Corp., 26.
Water supply, 26.
Watts and Whipple, 22.
Wax, filtration of, 160.
Werner & Pfleiderer Co.'s dissolver, 112.
Wharves for cars, 25.
Williams mill, 102, 104.
Wood vessels, 14.
Wood, weight of, 39.
Woods, tests of various substances in solution on, 172, 173.
Work trucks, 106, 107; tracks for, 108.
Worthington pumps, 53, 54, 55.
Wrench, pipe, 72.

Yaryan evaporator, 193.

Zaremba evaporators, 183; crystallizing evaporator, 190.
Zinc nails, 30.

SCIENTIFIC BOOKS

PUBLISHED BY

The Chemical Publishing Company,

Easton, Penna.

ARNDT-KATZ—A Popular Treatise on the Colloids in the Industrial Arts. Translated from the Second Enlarged Edition. 12mo. Pages VI + 73.

ARNOLD—The Motor and the Dynamo. 8vo. Pages VI + 178. 166 Figures.

BENEDICT—Elementary Organic Analysis. Small 8vo. Pages VI + 82. 15 Illustrations.

BERGEY—Handbook of Practical Hygiene. Small 8vo. Pages 164.

BILTZ—Practical Methods for Determining Molecular Weights. (Translated by Jones.) Small 8vo. Pages VIII + 245. 44 Illustrations.

BOLTON—History of the Thermometer. 12mo. Pages 96. 6 Illustrations.

BURGESS—Soil Bacteriology Laboratory Manual. 12mo. Pages VIII + 123. 3 Illustrations.

CAMERON—The Soil Solution, or the Nutrient Medium for Plant Growth. 8vo. Pages VI + 136. 3 Illustrations.

CLINTON—Further Light on the Theory of the Conductivity of Solutions. Pages 15. Paper Cover.

DOLT—Chemical French. 2nd Edition. 8vo. Pages VIII + 413.

EMERY—Elementary Chemistry. 12mo. Pages XIV + 666. 191 Illustrations.

ENGELHARDT—The Electrolysis of Water. 8vo. Pages X + 140. 90 Illustrations.

FRAPS—Principles of Agricultural Chemistry. 8vo. 2nd Edition. Pages VI + 501. 94 Illustrations.

GILMAN—A Laboratory Outline for Determination in Quantitative Chemical Analysis. Pages 88.

GUILD—The Mineralogy of Arizona. Small 12mo. Pages 104. Illustrated.

HALLIGAN—Elementary Treatise on Stock Feeds and Feeding. 8vo. Pages VI + 302. 24 Figures.

HALLIGAN—Fertility and Fertilizer Hints. 8vo. Pages VIII + 156. 12 Figures.

HALLIGAN—Soil Fertility and Fertilizers. 8vo. Pages X + [illegible]. 23 Figures.

[illegible]—Infinitesimals and Limits. Small 12mo. Paper. Pages [illegible]. 8 Figures.

HART—Text Book of Chemical Engineering. 2nd Edition 8vo. Pages XIV + 236. 229 Illustrations.

HART—Chemistry for Beginners. Small 12mo. Vol. I. Inorganic. Pages VIII + 214. 55 Illustrations, 2 Plates.

HART—Second Year Chemistry. Small 12mo. Pages 165. 31 Illustrations.

HART, R. N.—Leavening Agents. 8vo. Pages IV + 90. 13 Illustrations.

HEESS—Practical Methods for the Iron and Steel Works Chemist. 8vo. Pages 60.

HILL—A Brief Laboratory Guide for Qualitative Analysis. 3rd Edition. 12mo. Pages VIII + 104.

HINDS—Qualitative Chemical Analysis. 8vo. Pages VIII + 266.

HOWE—Inorganic Chemistry for Schools and Colleges. 8vo. 3rd Edition. Pages VIII + 443.

JONES—The Freezing Point, Boiling Point and Conductivity Methods. Pages VIII + 76. 2nd Edition, completely revised.

KRAYER—The Use and Care of a Balance. Small 12mo. Pages IV + 42. 18 Illustrations.

LANDOLT—The Optical Rotating Power of Organic Substances and Its Practical Applications. 8vo. Pages XXI + 751. 83 Illustrations.

LEAVENWORTH—Inorganic Qualitative Chemical Analysis. 8vo. Pages VI + 153.

LE BLANC—The Production of Chromium and Its Compounds by the Aid of the Electric Current. 8vo. Pages 122.

LOCKHART—American Lubricants. 2nd Edition. 8vo. Pages XII + 341. Illustrated.

MASON—Notes on Qualitative Analysis. 8th Edition. Small 12mo. Pages 58.

MEADE—Chemists' Pocket Manual. 12mo. 3rd Edition. Pages IV + 530. 42 Figures.

MEADE—Portland Cement. 2d Edition. 8vo. Pages X + 512. 169 Illustrations.

MOELLER-KRAUSE—Practical Handbook for Beet-Sugar Chemists. 8vo. Pages VIII + 132. 19 Illustrations.

MOISSAN—The Electric Furnace. 2nd Edition. 8vo. Pages XVI + 313. 42 Illustrations.

NIKAIDO—Beet-Sugar Making and Its Chemical Control. 8vo. Pages XII + 354. 65 Illustrations.

NISSENSON—The Arrangement of Electrolytic Laboratories. 8vo. Pages 81. 52 Illustrations.

NOYES—Organic Chemistry for the Laboratory. 4th Edition, revised. 8vo. Pages XII + 293. 41 Illustrations.

NOYES AND MULLIKEN—Laboratory Experiments on Class Reactions and Identification of Organic Substances. 8vo. Pages 81.

PARSONS—The Chemistry and Literature of Beryllium. 8vo. Pages VI + 180.

PFANHAUSER—Production of Metallic Objects Electrolytically. 8vo. Pages 162. 100 Illustrations.

PHILLIPS—Chemical German. 2d Edition. 8 vo. Pages VIII + 252.

PHILLIPS—Methods for the Analysis of Ores. Pig Iron and Steel. 2nd Edition. 8vo. Pages VIII + 170. 3 Illustrations.

PRANKE—Cyanamid (Manufacture, Chemistry and Uses). 8vo. Pages VI + 112. 8 Figures.

SEGER—Collected Writings of Herman August Seger. Papers on Manufacture of Pottery. 2 Vols. Large 8vo.

STILLMAN—Engineering Chemistry. 5th Edition. 8vo. Pages VIII + 760. 150 Illustrations.

STILLMAN—Examination of Lubricating Oils. 8vo. Pages IV + 125. 35 Illustrations.

TOWER—The Conductivity of Liquids. 8vo. Pages 82. [illegible] Illustrations.

Van KLOOSTER—Lecture Demonstrations in Physical Chemistry. 12mo. Pages VI + 196. 83 Figures.

VENABLE—The Development of the Periodic Law. Small 12mo. Pages VIII + 321. Illustrated.

VENABLE—The Study of the Atom. 12mo. Pages VI + 290.

VULTE—Household Chemistry. 12mo. 3rd Edition. Pages VI + 243.

VULTE AND VANDERBILT—Food Industries—An Elementary Text-book on the Production and Manufacture of Staple Foods. 3rd Edition. 8vo. Pages X + 325. 82 Illustrations.

WILEY—Principles and Practice of Agricultural Analysis. Vol. I—Soils. Pages XII + 636. 92 Illustrations.

WILEY—Principles and Practice of Agricultural Analysis. Vol. II—Fertilizers and Insecticides. Pages 684. 40 Illustrations 7 Plates.

WILEY—Principles and Practice of Agricultural Analysis. Vol. III—Agricultural Products. Pages XVI + 846. 127 Illustrations.

WYSOR—Analysis of Metallurgical and Engineering Materials—a Systematic Arrangement of Laboratory Methods. Size 6½ × 10½. Pages 82. Illustrated. Blank Pages for Notes.

WYSOR—Metallurgy—a Condensed Treatise for the Use of College Students and Any Desiring a General Knowledge of the Subject. 2d Edition, revised and enlarged. 8vo. Pages XIV + 391. 104 Illustrations.

ZIEGEL—Brief Course in Metallurgical Analysis. Pages VI + [illegible]